



Permit # PP- _____ - _____

TOWN OF COLCHESTER
APPLICATION FOR
PRELIMINARY PLAT REVIEW

All information requested on this application must be completed in full. Failure to provide the requested information either on this application form or on the plat plan will result in your application being rejected and a delay in the review before the Development Review Board.

1) OWNER OF RECORD (Name as shown on deed, mailing address, phone and email) _____
Hazelett Strip-Casting Corporation; 135 W Lakeshore Drive, Colchester, VT 05446
802-863-6376; davedi@hazelett.com

2) APPLICANT (Name, mailing address, phone and email) Same

3) CONTACT PERSON (Name, mailing address, phone and email) Benjamin Avery
Greenfield Growth, LLC; 802-316-0004; ben@greenfieldgrowthllc.com

4) CONSULTANT INFORMATION (Name, mailing address, phone and email) Scott Homsted
Krebs & Lansing Consulting Engineers, Inc.; 802-878-0375; scott.homsted@krebssandlansing.com

5) PROJECT STREET ADDRESS: 166 & 180 West Lakeshore Drive

6) TAX MAP & PARCEL #(can be obtained at Assessor's Office) 65-019002-0000000; 65-020002-0000000

7) PROJECT DESCRIPTION

a) Please note if new lots are being created and whether or not the request is for a regular subdivision, planned residential development, or planned unit development: See attached narrative.

b) Existing Uses on Property (including description and size of each separate use) _____
Current use is marina and recreational for Hazelett employees. Historical use included a hotel.

c) Proposed Uses on property (include description and size of each new use and existing uses to remain) Proposed use is for a 20 room Inn with a supporting restaurant and event space. The existing marina and recreational use will remain. See attached narrative.

d) Total building square footage on property (proposed buildings and existing buildings to remain)
Proposed: 4,982 total sq.ft. in 1 Main Building, 4 cottages, 1 future Phase 2 cottage.

e) Height of building & number of floors (proposed buildings and existing buildings to remain, specify if basement and mezzanine) Each building will have 2 stories and a basement level; Height will be 40' or less.

f) Number of residential units (if applicable, new units and existing units to remain) 0 new, 0 proposed

g) Number of employees & company vehicles (existing and proposed, note office versus non-office employees): 0 existing employees/vehicles; 12 proposed employees, 0 company vehicles

h) Other (list any other information pertinent to this application not specifically requested above, please note previous approvals and if the Overlay Districts are applicable): Allowed use in the Shoreland Protection Zone. No increase in "usable area" is proposed.

8) LOT INFORMATION

a) Existing Lot Size: 2.0

b) Number of Lots Being Created (please also note lot size): 0; Existing two lots will be merged into one

c) Acreage to be Disturbed: 1.3

d) Overall Coverage (building, parking, outside storage, etc)
Existing 5.5 % Proposed %

e) Front Yard Coverage (along each street) Existing 26.1 % Proposed %

f) Building Setbacks: Front 25 Rear 65 Side 104 Side 15

g) Parking Lot Setbacks: Front 18 Rear 17 Side 19 Side 108

h) Distance From Shoreline (95.5' elevation): 100

9) ESTIMATED PROJECT COMPLETION DATE 2026

10) TYPE OF EXISTING OR PROPOSED ENCUMBRANCES ON PROPERTY (easements, covenants, leases, rights of way, etc.) Easement to the Town of Colchester for existing stormwater pipe

11) PROPOSED EXTENSION, RELOCATION, OR MODIFICATION OF MUNICIPAL FACILITIES (sanitary sewer, water supply, streets, storm drainage, etc.) New water and sewer services lines are proposed to serve the new buildings.

12) PUBLIC IMPROVEMENT, ROAD, & UTILITY INFORMATION

a) Will municipal sewer be used? Yes If yes, has an allocation been requested? No

- b) For on site wastewater disposal describe: NA
- c) Has the Wastewater Official been contacted to review soil test pits? NA
- d) Will municipal water be used? Yes If no describe water supply: NA
- e) Linear footage & width of each road/driveway proposed: Reconfigured existing driveway
- f) Corner sight distance for each road/driveway: East Entrance: 800' east; 425' west;
West Entrance: 500' east, 300' west
- g) Do proposed roads include sidewalks? NA

13) COST ESTIMATES

- a) Building (including interior renovations): \$ 8,000,000.00
- b) Landscaping: \$ 244,533.10
- c) Describe Landscaping & Other Site Improvements: See Plans and Narrative.

14) ESTIMATED TRAFFIC

- a) Average daily traffic for entire property (in and out): See attached Traffic Impact Assessment
- b) A.M. Peak hour for entire property (in and out): See attached Traffic Impact Assessment
- c) P.M. Peak hour for entire property (In and out): See attached Traffic Impact Assessment

15) PEAK HOURS OF OPERATION: 4-6

16) PEAK DAYS OF OPERATION: Fri - Sun

17) PRELIMINARY PLAT PLAN AND FEE

A preliminary plat plan shall be submitted which shows the information listed on Exhibit B attached. A preliminary plat plan application fee shall be paid to the Town at the time of submittal (see Exhibit B). In accordance with Colchester's Fee Ordinance Chapter 6 ½ - 4 (9) applicants for all permits are responsible for costs of reviews conducted by third-party consultants/experts requested by the Town.

*Please submit one paper copy and a digital copy of the application in pdf (file not exceeding 20mb) via email to pzinfo@colchestervt.gov. If online submittal is not feasible, submissions will be accepted via CD/ DVD. Application forms, plans, and supporting documents shall each be separate pdfs and plans shall be submitted as a set whenever feasible. Files shall be named the address of the property and the type of document followed by the year (i.e. 205RooseveltHwyApp15). Each file name shall be unique with no spaces and characters shall be numbers or letters (no characters such as hyphens, #, &, or *). All pdfs shall be at least at 300dpi, color, and to scale if a plan, elevation, or similar document.*

18) PRELIMINARY PLAT REVIEW CRITERIA NARRATIVE

A narrative description of how the proposed project meets the criteria of Article Nine of the Development Regulations shall be submitted with this application.

See Attached.

I hereby certify that all the information requested as part of this application has been submitted and is accurate to the best of my knowledge.

SIGNATURE OF APPLICANT

SIGNATURE OF PROPERTY OWNER

By the land owner signature, the land owner is authorizing the applicant to act on their behalf.

☒ Check this box if the consultant listed is authorized to act on behalf of the applicant and land owner.

☒ Check this box if the contact person listed is authorized to act on behalf of the applicant and land owner.

Do not write below this line

DATE OF SUBMISSION: _____

FEE PAID: _____

I have reviewed this preliminary plat application and find it to be: ☐ Complete ☐ Incomplete

Zoning Administrator or Designee

Date

EXHIBIT A
ADJOINING PROPERTY OWNER INFORMATION

(please use the interactive map at Colchestervt.gov for info & try to include direct abutters as well as adjacent properties along the shoreline within the area of affect as well as across the street)

Example: Tax Map 7, Parcel 57 John and Jane Doe P.O. Box 55, 835 Blakely Road Colchester, VT 05446		

EXHIBIT B

PRELIMINARY PLAT

The following information must be shown on the plat plans meeting Article Nine of the Development Regulations. Failure to provide the following information will result in your application being rejected and a delay in the review before the Development Review Board.

- Complete survey of property by a licensed land surveyor drawn to scale (20 ft. is preferred).
- Name, license number, seal, and contact number of licensed land surveyor & date prepared.
- Survey data (acreage, property lines, zoning boundaries, watercourse, base flood elevation, etc.)
- Location of easements, public lands, r.o.w.s, sidewalks, and public or private street (w/names)
- Contours at two (2) foot elevation intervals (existing and finished)
- Boundaries and area of all abutting properties
- Building elevations & building level floor plans
- Proposed landscaping schedule (number, variety and size)
- Location of streets, abutting properties, fire hydrants, existing buildings, existing landscaping
- Location of proposed hydrants and/or building sprinkler hook-ups and fire lanes.
- Zoning boundaries
- Number and location of parking spaces (including handicapped spaces)
- Location of septic tanks, fields, & lines and/or septic test pit, and percolation information
- Lot coverage information: Building footprint, total lot, and front yard
- Numerical and graphical scale, date last revised, and north arrow.
- Exterior lighting details (cut sheets). All lights should be down casting and shielded.
- Dumpster or trash area locations
- Bicycle rack
- If restaurant is proposed, provide number seats and square footage of floor area provided for patron use but not containing fixed seats
- Area for accumulating snow
- Details of all proposed bridges or culverts.
- Location of temporary markers.
- Water line location (existing & proposed), fire flows, and pressures
- Details of drainage systems & stormwater facilities
- Physical features (streams, wetlands, vegetative cover, etc.)
- Existing highway geometries including access points near project
- Existing & proposed entrances and curb cuts (dimensions, widths, & turning radii)
- Sight distance in both direction of all driveway intersections
- Traffic level of service/capacity analysis for existing/future conditions
- Loading areas & truck circulation patterns
- Existing & proposed sidewalks, recreation paths, and pedestrian walkways
- A list of waivers desired (if any).
- Development timetable (including number of phases and start and completion dates).
- Location & size of open spaces reserved for recreation or conservation
- Location & type of restricted land (i.e. rights-of-way, easements, open space covenants, etc.)

APPLICATION FEE

- ☐ Base fee \$1223 plus:
 - ☐ Tiered cost per unit: Units 1-10: \$153/unit, Units 11-20: \$102/unit, Units 21+: \$72/unit; and
 - ☐ \$51/acre



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Subject Properties:

Parcel Number: 06-023002-0000000
CAMA Number: 06-023002-0000000
Property Address: 135 WEST LAKESHORE DR

Mailing Address: HAZELETT STRIP-CASTING CORP
PO BOX 600
COLCHESTER, VT 05446

Parcel Number: 65-019002-0000000
CAMA Number: 65-019002-0000000
Property Address: 180 WEST LAKESHORE DR

Mailing Address: HAZELETT STRIP-CASTING CORP
PO BOX 600
COLCHESTER, VT 05446

Parcel Number: 65-020002-0000000
CAMA Number: 65-020002-0000000
Property Address: 166 WEST LAKESHORE DR

Mailing Address: HAZELETT STRIP CASTING CORP
PO BOX 600
COLCHESTER, VT 05446

Abutters:

Parcel Number: 06-013002-0000000
CAMA Number: 06-013002-0000000
Property Address: 118 MALLETTTS BAY AVE

Mailing Address: SISON BROADCASTING COMPANY INC
118 MALLETTTS BAY AVE
COLCHESTER, VT 05446

Parcel Number: 06-013002-0000000
CAMA Number: 06-013002-0000000
Property Address: 118 MALLETTTS BAY AVE

Mailing Address: SISON BROADCASTING COMPANY INC
124 MIDNIGHT PASS
COLCHESTER, VT 05446

Parcel Number: 06-013002-0000000
CAMA Number: 06-013002-0000000
Property Address: 118 MALLETTTS BAY AVE

Mailing Address: SISON BROADCASTING COMPANY INC
PO BOX 136
COLCHESTER, VT 05446

Parcel Number: 06-013002-0000000
CAMA Number: 06-013002-0000000
Property Address: 118 MALLETTTS BAY AVE

Mailing Address: SISON BROADCASTING COMPANY INC
118 MALLETTTS BAY AVE
COLCHESTER, VT 05446

Parcel Number: 06-013002-0000000
CAMA Number: 06-013002-0000000
Property Address: 118 MALLETTTS BAY AVE

Mailing Address: SISON BROADCASTING COMPANY INC
124 MIDNIGHT PASS
COLCHESTER, VT 05446

Parcel Number: 06-013002-0000000
CAMA Number: 06-013002-0000000
Property Address: 118 MALLETTTS BAY AVE

Mailing Address: SISON BROADCASTING COMPANY INC
PO BOX 136
COLCHESTER, VT 05446

Parcel Number: 06-013002-0000000
CAMA Number: 06-013002-0000000
Property Address: 118 MALLETTTS BAY AVE

Mailing Address: SISON BROADCASTING COMPANY INC
118 MALLETTTS BAY AVE
COLCHESTER, VT 05446



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number: 06-013002-0000000
CAMA Number: 06-013002-0000000
Property Address: 118 MALLETT'S BAY AVE

Mailing Address: SISON BROADCASTING COMPANY INC
124 MIDNIGHT PASS
COLCHESTER, VT 05446

Parcel Number: 06-013002-0000000
CAMA Number: 06-013002-0000000
Property Address: 118 MALLETT'S BAY AVE

Mailing Address: SISON BROADCASTING COMPANY INC
PO BOX 136
COLCHESTER, VT 05446

Parcel Number: 06-014002-0000000
CAMA Number: 06-014002-0000000
Property Address: 0 MALLETT'S BAY AVE

Mailing Address: COLCHESTER TOWN SCHOOL DIST
PO BOX 27
COLCHESTER, VT 05446

Parcel Number: 06-022002-0000000
CAMA Number: 06-022002-0000000
Property Address: 34 BLAKELY RD

Mailing Address: COLCHESTER TOWN OF
781 BLAKELY RD
COLCHESTER, VT 05446

Parcel Number: 06-026072-0000000
CAMA Number: 06-026072-0000000
Property Address: 0 MACRAE RD

Mailing Address: WINOOSKI VALLEY PARK DIST
1 ETHAN ALLEN HOMESTEAD
BURLINGTON, VT 05408

Parcel Number: 63-025002-0000000
CAMA Number: 63-025002-0000000
Property Address: 373 SHORE ACRES DR

Mailing Address: BAUMANN WALTER E
373 SHORE ACRES DR
COLCHESTER, VT 05446

Parcel Number: 63-026002-0000000
CAMA Number: 63-026002-0000000
Property Address: 411 SHORE ACRES DR

Mailing Address: PLACE DENIS H
411 SHORE ACRES DR
COLCHESTER, VT 05446

Parcel Number: 63-027002-0000000
CAMA Number: 63-027002-0000000
Property Address: 463 SHORE ACRES DR

Mailing Address: SPENGLER JEFFREY E
463 SHORE ACRES DR
COLCHESTER, VT 05446

Parcel Number: 63-030002-0000000
CAMA Number: 63-030002-0000000
Property Address: 581 SHORE ACRES DR

Mailing Address: COGLEY JOSEPH M
581 SHORE ACRES DR
COLCHESTER, VT 05446

Parcel Number: 63-033002-0000000
CAMA Number: 63-033002-0000000
Property Address: 663 SHORE ACRES DR

Mailing Address: BOUDREAU THERESA A LIFE ESTATE
663 SHORE ACRES DR
COLCHESTER, VT 05446

Parcel Number: 64-001002-0000000
CAMA Number: 64-001002-0000000
Property Address: 683 SHORE ACRES DR

Mailing Address: NAULT MATTHEW R
683 SHORE ACRES DR
COLCHESTER, VT 05446

Parcel Number: 64-002002-0000000
CAMA Number: 64-002002-0000000
Property Address: 717 SHORE ACRES DR

Mailing Address: HAMMOND JAMES F
717 SHORE ACRES DR
COLCHESTER, VT 05446



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.

3/3/2025

Page 2 of 13



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number: 64-003002-0000000
CAMA Number: 64-003002-0000000
Property Address: 751 SHORE ACRES DR

Mailing Address: MYERS TODD A
751 SHORE ACRES DR
COLCHESTER, VT 05446

Parcel Number: 64-004002-0000000
CAMA Number: 64-004002-0000000
Property Address: 827 SHORE ACRES DR

Mailing Address: KATZ JON
827 SHORE ACRES DR
COLCHESTER, VT 05446

Parcel Number: 64-005002-0000000
CAMA Number: 64-005002-0000000
Property Address: 849 SHORE ACRES DR

Mailing Address: FRANCIS AND SUSAN CONNORS REV
TRUST
849 SHORE ACRES DR
COLCHESTER, VT 05446

Parcel Number: 64-013002-0000000
CAMA Number: 64-013002-0000000
Property Address: 921 SHORE ACRES DR

Mailing Address: BARTLETT LIVING TRUST
921 SHORE ACRES DR
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0000000
Property Address: 88 MALLETT'S BAY
CAMPGROUND

Mailing Address: 88 MALLETT'S BAY CAMPGROUND LLC
75 SO WINOOSKI AVE
BURLINGTON, VT 05401

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0010000
Property Address: 1 MALLETT'S BAY CAMPGROUND

Mailing Address: NEWTON THOMAS
1 MALLETT'S BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0010100
Property Address: 1A MALLETT'S BAY
CAMPGROUND

Mailing Address: MARSHALL TINA
40 TYRONE RD
MORGANTOWN, WV 26508

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0020010
Property Address: B10 MALLETT'S BAY
CAMPGROUND

Mailing Address: BUSHEY JOHN
B10 MALLETT'S BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0020500
Property Address: B5 MALLETT'S BAY
CAMPGROUND

Mailing Address: LIBERTY HEATHER
16 ELIZABETH ST
SO BURLINGTON, VT 05403

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0020600
Property Address: B6 MALLETT'S BAY
CAMPGROUND

Mailing Address: KING SHAWN
PO BOX 604
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0020800
Property Address: B8 MALLETT'S BAY
CAMPGROUND

Mailing Address: MCDOWELL DOUG
B8 MALLETT'S BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0020800
Property Address: B8 MALLETT'S BAY
CAMPGROUND

Mailing Address: MCDOWELL DOUG
PO BOX 404
COLCHESTER, VT 05446



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number:	65-001002-0000000	Mailing Address:	MCDOWELL DOUG B8 MALLETT'S BAY CAMPGROUND COLCHESTER, VT 05446
CAMA Number:	65-001002-0020800		
Property Address:	B8 MALLETT'S BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	MCDOWELL DOUG PO BOX 404 COLCHESTER, VT 05446
CAMA Number:	65-001002-0020800		
Property Address:	B8 MALLETT'S BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	DUFRESNE KEVIN 99 LORI LN BURLINGTON, VT 05408
CAMA Number:	65-001002-0020900		
Property Address:	B9 MALLETT'S BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	WALL LESLIE B1 MALLETT'S BAY CAMPGROUND COLCHESTER, VT 05446
CAMA Number:	65-001002-0021000		
Property Address:	B1 MALLETT'S BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	DEVARAJAN ASHLEY 12726 NW NAOMI LN PORTLAND, OR 97229
CAMA Number:	65-001002-0030100		
Property Address:	3A MALLETT'S BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	VOIGT DENNIS 21 LOUBIER DR ESSEX JCT, VT 05452
CAMA Number:	65-001002-0040000		
Property Address:	4 MALLETT'S BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	ANGIER JOHN 4A MALLETT'S BAY CAMPGROUND COLCHESTER, VT 05446
CAMA Number:	65-001002-0040100		
Property Address:	4A MALLETT'S BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	BRADLEY ALLEN 9 CAPTAIN HALL RD MIDDLEBORO, MA 02346
CAMA Number:	65-001002-0050100		
Property Address:	5A MALLETT'S BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	STANLEY LEVI PO BOX 256 COLCHESTER, VT 05446
CAMA Number:	65-001002-0060000		
Property Address:	6 MALLETT'S BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	MAIN GEORGE 8041 MEADOW LARK LANE PORT ST. LUCIE, FL 34952
CAMA Number:	65-001002-0060100		
Property Address:	6A MALLETT'S BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	CASWELL ANNE G 7 MALLETT'S BAY CAMPGROUND COLCHESTER, VT 05446
CAMA Number:	65-001002-0070000		
Property Address:	7 MALLETT'S BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	CASWELL ANNE G PO BOX 65084 BURLINGTON, VT 05406
CAMA Number:	65-001002-0070000		
Property Address:	7 MALLETT'S BAY CAMPGROUND		



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number:	65-001002-0000000	Mailing Address:	CASWELL ANNE G
CAMA Number:	65-001002-0070000		7 MALLETT'S BAY CAMPGROUND
Property Address:	7 MALLETT'S BAY CAMPGROUND		COLCHESTER, VT 05446

Parcel Number:	65-001002-0000000	Mailing Address:	CASWELL ANNE G
CAMA Number:	65-001002-0070000		PO BOX 65084
Property Address:	7 MALLETT'S BAY CAMPGROUND		BURLINGTON, VT 05406

Parcel Number:	65-001002-0000000	Mailing Address:	HARRINGTON STEVE
CAMA Number:	65-001002-0080000		PO BOX 372
Property Address:	8 MALLETT'S BAY CAMPGROUND		JONESVILLE, VT 05466

Parcel Number:	65-001002-0000000	Mailing Address:	GRIFFITH MAURICE
CAMA Number:	65-001002-0080100		22646 CLIFFSIDE WAY
Property Address:	8A MALLETT'S BAY CAMPGROUND		LAND O LAKES, FL 34639

Parcel Number:	65-001002-0000000	Mailing Address:	GRIFFITH MAURICE
CAMA Number:	65-001002-0080100		5015 ABIGAIL LN
Property Address:	8A MALLETT'S BAY CAMPGROUND		CHATTANOOGA, TN 37416

Parcel Number:	65-001002-0000000	Mailing Address:	GRIFFITH MAURICE
CAMA Number:	65-001002-0080100		PO BOX 602
Property Address:	8A MALLETT'S BAY CAMPGROUND		COLCHESTER, VT 05446

Parcel Number:	65-001002-0000000	Mailing Address:	GRIFFITH MAURICE
CAMA Number:	65-001002-0080100		PO BOX 90
Property Address:	8A MALLETT'S BAY CAMPGROUND		COLCHESTER, VT 05446

Parcel Number:	65-001002-0000000	Mailing Address:	GRIFFITH MAURICE
CAMA Number:	65-001002-0080100		22646 CLIFFSIDE WAY
Property Address:	8A MALLETT'S BAY CAMPGROUND		LAND O LAKES, FL 34639

Parcel Number:	65-001002-0000000	Mailing Address:	GRIFFITH MAURICE
CAMA Number:	65-001002-0080100		5015 ABIGAIL LN
Property Address:	8A MALLETT'S BAY CAMPGROUND		CHATTANOOGA, TN 37416

Parcel Number:	65-001002-0000000	Mailing Address:	GRIFFITH MAURICE
CAMA Number:	65-001002-0080100		PO BOX 602
Property Address:	8A MALLETT'S BAY CAMPGROUND		COLCHESTER, VT 05446

Parcel Number:	65-001002-0000000	Mailing Address:	GRIFFITH MAURICE
CAMA Number:	65-001002-0080100		PO BOX 90
Property Address:	8A MALLETT'S BAY CAMPGROUND		COLCHESTER, VT 05446

Parcel Number:	65-001002-0000000	Mailing Address:	GRIFFITH MAURICE
CAMA Number:	65-001002-0080100		22646 CLIFFSIDE WAY
Property Address:	8A MALLETT'S BAY CAMPGROUND		LAND O LAKES, FL 34639



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0080100
Property Address: 8A MALLETTTS BAY
CAMPGROUND

Mailing Address: GRIFFITH MAURICE
5015 ABIGAIL LN
CHATTANOOGA, TN 37416

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0080100
Property Address: 8A MALLETTTS BAY
CAMPGROUND

Mailing Address: GRIFFITH MAURICE
PO BOX 602
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0080100
Property Address: 8A MALLETTTS BAY
CAMPGROUND

Mailing Address: GRIFFITH MAURICE
PO BOX 90
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0080100
Property Address: 8A MALLETTTS BAY
CAMPGROUND

Mailing Address: GRIFFITH MAURICE
22646 CLIFFSIDE WAY
LAND O LAKES, FL 34639

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0080100
Property Address: 8A MALLETTTS BAY
CAMPGROUND

Mailing Address: GRIFFITH MAURICE
5015 ABIGAIL LN
CHATTANOOGA, TN 37416

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0080100
Property Address: 8A MALLETTTS BAY
CAMPGROUND

Mailing Address: GRIFFITH MAURICE
PO BOX 602
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0080100
Property Address: 8A MALLETTTS BAY
CAMPGROUND

Mailing Address: GRIFFITH MAURICE
PO BOX 90
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0090000
Property Address: 9 MALLETTTS BAY CAMPGROUND

Mailing Address: DICKINSON JESSICA
143 PARK ST
BURLINGTON, VT 05401

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0110000
Property Address: 11 MALLETTTS BAY
CAMPGROUND

Mailing Address: CARDINAL RON
11 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0110100
Property Address: 11A MALLETTTS BAY
CAMPGROUND

Mailing Address: BRIGHAM SABRINA
11A MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0120000
Property Address: 12 MALLETTTS BAY
CAMPGROUND

Mailing Address: PARIZO RAY III
12 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0120000
Property Address: 12 MALLETTTS BAY
CAMPGROUND

Mailing Address: PARIZO RAY III
193 BROWNS RIVER RD
ESSEX JCT, VT 05452



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number:	65-001002-0000000	Mailing Address:	PARIZO RAY III
CAMA Number:	65-001002-0120000		12 MALLETTTS BAY CAMPGROUND
Property Address:	12 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	PARIZO RAY III
CAMA Number:	65-001002-0120000		193 BROWNS RIVER RD
Property Address:	12 MALLETTTS BAY CAMPGROUND		ESSEX JCT, VT 05452
Parcel Number:	65-001002-0000000	Mailing Address:	PAAP LARRY
CAMA Number:	65-001002-0120100		132 NO CHAMPLAIN ST
Property Address:	12A MALLETTTS BAY CAMPGROUND		BURLINGTON, VT 05401
Parcel Number:	65-001002-0000000	Mailing Address:	PAAP LARRY
CAMA Number:	65-001002-0120100		PO BOX 371
Property Address:	12A MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	PAAP LARRY
CAMA Number:	65-001002-0120100		132 NO CHAMPLAIN ST
Property Address:	12A MALLETTTS BAY CAMPGROUND		BURLINGTON, VT 05401
Parcel Number:	65-001002-0000000	Mailing Address:	PAAP LARRY
CAMA Number:	65-001002-0120100		PO BOX 371
Property Address:	12A MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	AMOUR SUE
CAMA Number:	65-001002-0140000		778 SAND HILL RD #24
Property Address:	14 MALLETTTS BAY CAMPGROUND		ESSEX JCT, VT 054452
Parcel Number:	65-001002-0000000	Mailing Address:	ALDERMAN KAREN
CAMA Number:	65-001002-0150000		15 MALLETTTS BAY CAMPGROUND
Property Address:	15 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	LEMIEUX PIERRE
CAMA Number:	65-001002-0160000		1416 HINESBURG RD
Property Address:	16 MALLETTTS BAY CAMPGROUND		SO BURLINGTON, VT 05403
Parcel Number:	65-001002-0000000	Mailing Address:	RAFFERTY THOMAS
CAMA Number:	65-001002-0170000		PO BOX 265
Property Address:	17 MALLETTTS BAY CAMPGROUND		WILLISTON, VT 05495
Parcel Number:	65-001002-0000000	Mailing Address:	DAMPIERRE RUTH
CAMA Number:	65-001002-0190000		19 MALLETTTS BAY CAMPGROUND
Property Address:	19 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	VANASSE RAYMOND
CAMA Number:	65-001002-0200000		37 ST NICHOLAS ST
Property Address:	20 MALLETTTS BAY CAMPGROUND		SOREL TRACY PQ, J3P 4X7



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number:	65-001002-0000000	Mailing Address:	BUTLER DANIELLE
CAMA Number:	65-001002-0210000		21 MALLETTTS BAY CAMPGROUND
Property Address:	21 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	BARTLETT CHRIS
CAMA Number:	65-001002-0220000		22 MALLETTTS BAY CAMPGROUND
Property Address:	22 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	BARTLETT CHRIS
CAMA Number:	65-001002-0220000		PO BOX 341
Property Address:	22 MALLETTTS BAY CAMPGROUND		SO BARRE, VT 05670
Parcel Number:	65-001002-0000000	Mailing Address:	BARTLETT CHRIS
CAMA Number:	65-001002-0220000		22 MALLETTTS BAY CAMPGROUND
Property Address:	22 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	BARTLETT CHRIS
CAMA Number:	65-001002-0220000		PO BOX 341
Property Address:	22 MALLETTTS BAY CAMPGROUND		SO BARRE, VT 05670
Parcel Number:	65-001002-0000000	Mailing Address:	HEINRICH WILLIAM
CAMA Number:	65-001002-0260000		26 MALLETTTS BAY CAMPGROUND
Property Address:	26 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	COLBERT VIRGINIA
CAMA Number:	65-001002-0270000		27 MALLETTTS BAY CAMPGROUND
Property Address:	27 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	GILBERSON GARY
CAMA Number:	65-001002-0270100		27A MALLETTTS BAY CAMPGROUND
Property Address:	27A MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	REPOSA DAVID
CAMA Number:	65-001002-0280100		218 MALLETTTS BAY AVE 473
Property Address:	28 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	REPOSA DAVID
CAMA Number:	65-001002-0280100		28 MALLETTTS BAY CAMPGROUND
Property Address:	28 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	REPOSA DAVID
CAMA Number:	65-001002-0280100		218 MALLETTTS BAY AVE 473
Property Address:	28 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446
Parcel Number:	65-001002-0000000	Mailing Address:	REPOSA DAVID
CAMA Number:	65-001002-0280100		28 MALLETTTS BAY CAMPGROUND
Property Address:	28 MALLETTTS BAY CAMPGROUND		COLCHESTER, VT 05446



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number:	65-001002-0000000	Mailing Address:	REPOSA DAVID 218 MALLETTTS BAY AVE 473 COLCHESTER, VT 05446
CAMA Number:	65-001002-0290000		
Property Address:	29 MALLETTTS BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	BEVINS RICHARD 30 MALLETTTS BAY CAMPGROUND COLCHESTER, VT 05446
CAMA Number:	65-001002-0300000		
Property Address:	30 MALLETTTS BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	BURKE BILL B4 MALLETTTS BAY CAMPGROUND COLCHESTER, VT 05446
CAMA Number:	65-001002-0301000		
Property Address:	B4 MALLETTTS BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	GUERIN SHELBY 476 NORTH AVE BURLINGTON, VT 05401
CAMA Number:	65-001002-0310000		
Property Address:	31 MALLETTTS BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	GUERIN SHELBY 6 FIDDLEHEAD RD VERGENNES, VT 05491
CAMA Number:	65-001002-0310000		
Property Address:	31 MALLETTTS BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	GUERIN SHELBY 476 NORTH AVE BURLINGTON, VT 05401
CAMA Number:	65-001002-0310000		
Property Address:	31 MALLETTTS BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	GUERIN SHELBY 6 FIDDLEHEAD RD VERGENNES, VT 05491
CAMA Number:	65-001002-0310000		
Property Address:	31 MALLETTTS BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	GUERIN SHELBY 476 NORTH AVE BURLINGTON, VT 05401
CAMA Number:	65-001002-0310000		
Property Address:	31 MALLETTTS BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	GUERIN SHELBY 6 FIDDLEHEAD RD VERGENNES, VT 05491
CAMA Number:	65-001002-0310000		
Property Address:	31 MALLETTTS BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	CORREIA RICHARD PO BOX 163 COLCHESTER, VT 05446
CAMA Number:	65-001002-0330000		
Property Address:	33 MALLETTTS BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	MERCIER DENNIS 34 MALLETTTS BAY CAMPGROUND COLCHESTER, VT 05446
CAMA Number:	65-001002-0340000		
Property Address:	34 MALLETTTS BAY CAMPGROUND		
Parcel Number:	65-001002-0000000	Mailing Address:	SWEENEY LARRY 35 MALLETTTS BAY CAMPGROUND COLCHESTER, VT 05446
CAMA Number:	65-001002-0350000		
Property Address:	35 MALLETTTS BAY CAMPGROUND		



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0360000
Property Address: 36 MALLETTTS BAY
CAMPGROUND

Mailing Address: SMITH DENNIS L
128 INDIAN CIR 1
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0370000
Property Address: 37 MALLETTTS BAY
CAMPGROUND

Mailing Address: MANNING TOM
37 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0380000
Property Address: 38 MALLETTTS BAY
CAMPGROUND

Mailing Address: LAMAR MAX
38 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0390000
Property Address: 39 MALLETTTS BAY
CAMPGROUND

Mailing Address: LYNDES CRAIG
70 SOUTH WINOOSKI AVE # 121
BURLINGTON, VT 05401

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0410000
Property Address: 41 MALLETTTS BAY
CAMPGROUND

Mailing Address: COMBS MARILYN
27110 JONSTOP 3306
PUNTA GORDA, FL 33982

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0420000
Property Address: 42 MALLETTTS BAY
CAMPGROUND

Mailing Address: GALIETTA STEPHEN
260 RAND HILL RD
MORRISONVILLE, NY 12962

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0430000
Property Address: 43 MALLETTTS BAY
CAMPGROUND

Mailing Address: LUNDERVILLE FRANCIS
403 TIMBER PASSAGE TRAIL
WILLIAMSBURG, VA 23185

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0430000
Property Address: 43 MALLETTTS BAY
CAMPGROUND

Mailing Address: LUNDERVILLE FRANCIS
6498 POPLAR POND DR
GLOUCESTER, VA 23061

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0430000
Property Address: 43 MALLETTTS BAY
CAMPGROUND

Mailing Address: LUNDERVILLE FRANCIS
403 TIMBER PASSAGE TRAIL
WILLIAMSBURG, VA 23185

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0430000
Property Address: 43 MALLETTTS BAY
CAMPGROUND

Mailing Address: LUNDERVILLE FRANCIS
6498 POPLAR POND DR
GLOUCESTER, VA 23061

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0440000
Property Address: 44 MALLETTTS BAY
CAMPGROUND

Mailing Address: MCLEOD SANDRA
18545 NW 45TH AVE RD
CITRA, FL 32113

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0450000
Property Address: 45 MALLETTTS BAY
CAMPGROUND

Mailing Address: LANDON MARK
675 LUZERNE RD
QUEENSBURY, NY 12804



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0460000
Property Address: 46 MALLETTTS BAY
CAMPGROUND

Mailing Address: FERGUSON GEORGE JR
104 FERGUSON RD
FAIRFAX, VT 05454

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0460000
Property Address: 46 MALLETTTS BAY
CAMPGROUND

Mailing Address: FERGUSON GEORGE JR
88 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0460000
Property Address: 46 MALLETTTS BAY
CAMPGROUND

Mailing Address: FERGUSON GEORGE JR
104 FERGUSON RD
FAIRFAX, VT 05454

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0460000
Property Address: 46 MALLETTTS BAY
CAMPGROUND

Mailing Address: FERGUSON GEORGE JR
88 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0470000
Property Address: 47 MALLETTTS BAY
CAMPGROUND

Mailing Address: BUSHEY MICHAEL
2631 N CAMBRIDGE RD
JEFFERSONVILLE, VT 05464

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0480000
Property Address: 48 MALLETTTS BAY
CAMPGROUND

Mailing Address: BENNETT JAMES
48 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0490000
Property Address: 49 MALLETTTS BAY
CAMPGROUND

Mailing Address: AURELLI MIKE
49 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0500000
Property Address: 50 MALLETTTS BAY
CAMPGROUND

Mailing Address: HARVEY ROBERT P
1 WILSON ST
BARRE, VT 05661

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0550000
Property Address: 55 MALLETTTS BAY
CAMPGROUND

Mailing Address: COOK THEODORE
55 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0590000
Property Address: 59 MALLETTTS BAY
CAMPGROUND

Mailing Address: CLEVELAND TOM
59 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0610000
Property Address: 61 MALLETTTS BAY
CAMPGROUND

Mailing Address: DAIGLE CAROLYN
261 JOURDAN ST
HINESBURG, VT 05461

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0740000
Property Address: 74 MALLETTTS BAY
CAMPGROUND

Mailing Address: HOWE GARY
74 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0800000
Property Address: 80 MALLETTTS BAY
CAMPGROUND

Mailing Address: ASKEW TOBY
3524 MARILYN RD
PORTSMOUTH, VA 23703

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0800000
Property Address: 80 MALLETTTS BAY
CAMPGROUND

Mailing Address: ASKEW TOBY
80 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0800000
Property Address: 80 MALLETTTS BAY
CAMPGROUND

Mailing Address: ASKEW TOBY
3524 MARILYN RD
PORTSMOUTH, VA 23703

Parcel Number: 65-001002-0000000
CAMA Number: 65-001002-0800000
Property Address: 80 MALLETTTS BAY
CAMPGROUND

Mailing Address: ASKEW TOBY
80 MALLETTTS BAY CAMPGROUND
COLCHESTER, VT 05446

Parcel Number: 65-003002-0000000
CAMA Number: 65-003002-0000000
Property Address: 105 WEST LAKESHORE DR

Mailing Address: HAZELETT STRIP CASTING
CORPORATION
135 WEST LAKESHORE DR
COLCHESTER, VT 05446

Parcel Number: 65-004002-0000000
CAMA Number: 65-004002-0000000
Property Address: 215 WEST LAKESHORE DR

Mailing Address: LURVEY RAYA J
42 KYLIES WAY
COLCHESTER, VT 05446

Parcel Number: 65-004002-0000000
CAMA Number: 65-004002-0000000
Property Address: 215 WEST LAKESHORE DR

Mailing Address: LURVEY RAYA J
4001 ETHAN ALLEN HWY APT D
GEORGIA, VT 05478

Parcel Number: 65-004002-0000000
CAMA Number: 65-004002-0000000
Property Address: 215 WEST LAKESHORE DR

Mailing Address: LURVEY RAYA J
22 FERN CT #1
COLCHESTER, VT 05446

Parcel Number: 65-004002-0000000
CAMA Number: 65-004002-0000000
Property Address: 215 WEST LAKESHORE DR

Mailing Address: LURVEY RAYA J
42 KYLIES WAY
COLCHESTER, VT 05446

Parcel Number: 65-004002-0000000
CAMA Number: 65-004002-0000000
Property Address: 215 WEST LAKESHORE DR

Mailing Address: LURVEY RAYA J
4001 ETHAN ALLEN HWY APT D
GEORGIA, VT 05478

Parcel Number: 65-004002-0000000
CAMA Number: 65-004002-0000000
Property Address: 215 WEST LAKESHORE DR

Mailing Address: LURVEY RAYA J
22 FERN CT #1
COLCHESTER, VT 05446

Parcel Number: 65-004002-0000000
CAMA Number: 65-004002-0000000
Property Address: 215 WEST LAKESHORE DR

Mailing Address: LURVEY RAYA J
42 KYLIES WAY
COLCHESTER, VT 05446



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.

3/3/2025

Page 12 of 13



100 feet Abutters List Report

Colchester, VT

March 03, 2025

Parcel Number: 65-004002-0000000
CAMA Number: 65-004002-0000000
Property Address: 215 WEST LAKESHORE DR

Mailing Address: LURVEY RAYA J
4001 ETHAN ALLEN HWY APT D
GEORGIA, VT 05478

Parcel Number: 65-004002-0000000
CAMA Number: 65-004002-0000000
Property Address: 215 WEST LAKESHORE DR

Mailing Address: LURVEY RAYA J
22 FERN CT #1
COLCHESTER, VT 05446

Parcel Number: 65-005002-0000000
CAMA Number: 65-005002-0000000
Property Address: 61 JAKES PLACE

Mailing Address: DEFORGE GERALD B
PO BOX 69
COLCHESTER, VT 05446

Parcel Number: 65-006002-0000000
CAMA Number: 65-006002-0000000
Property Address: 0 WEST LAKESHORE DR

Mailing Address: 332 WEST LAKESHORE DRIVE, LLC
218 OVERLAKE DR
COLCHESTER, VT 05446

Parcel Number: 65-017002-0000000
CAMA Number: 65-017002-0000000
Property Address: 278 WEST LAKESHORE DR

Mailing Address: SP COVE LLC
171 CRESCENT RD
BURLINGTON, VT 05401

Parcel Number: 65-021002-0000000
CAMA Number: 65-021002-0000000
Property Address: 76 WEST LAKESHORE DR

Mailing Address: GARDNER NEIL
319 MARBLE ISLAND RD
COLCHESTER, VT 05446



www.cai-tech.com

Data shown on this report is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this report.



135, 166 & 180 West Lakeshore Dr


Town of Colchester, VT

1 inch = 1075 Feet



www.cai-tech.com

March 5, 2025



Data shown on this map is provided for planning and informational purposes only. The municipality and CAI Technologies are not responsible for any use for other purposes or misuse or misrepresentation of this map.



Project Overview: “The H”

The vision for “The H” is to establish a unique hospitality destination that attracts visitors to Malletts Bay year-round. This development has been meticulously planned to provide a diverse range of experiences and activities, offering an immersive connection to the waterfront while maintaining a harmonious relationship with the surrounding environment.

The proposed plan includes the following key elements:

- **Accommodations:**
 - Four cottage-style buildings, housing a total of **19 guest rooms**, ranging from studio units to one- and two-bedroom suites.
- **Main Building (Project Centerpiece):**
 - A **48-seat restaurant**, featuring both indoor dining and an outdoor patio on the lower level.
 - **Event and meeting space** on the main floor, designed for gatherings, conferences, and community events.
 - **Health and wellness amenities** on the upper level, providing guests with access to fitness and relaxation facilities.
- **Waterfront Access and Recreation:**
 - All accommodations and amenities will offer **unobstructed lake views**, direct **waterfront access**, and a designated **lakeside recreational area**.
- **Future Expansion:**
 - A **single cottage** to the east, with design and planning to be completed at a later stage through a separate approval process.

Design Approach

Our design approach has been guided by a commitment to preserving and enhancing the historic character of the Malletts Bay shoreline district. The project has been carefully crafted to seamlessly integrate with the surrounding environment while providing a welcoming and visually appealing experience for guests and the public alike.

- **Architectural Considerations:**
 - All buildings are **two stories in height**, adhering to required height limitations while ensuring a traditional and unobtrusive shoreline aesthetic.
 - Thoughtful building placement has been implemented to **preserve lake views**, creating an open and inviting atmosphere.
 - A carefully developed **landscaping plan** will enhance the site's visual appeal from both the road and the water, meeting all planning requirements while maintaining natural beauty.
- **Lakeside Experience & Outdoor Activities:**
 - The buildings feature **private lower walkout areas** for guests, offering direct access to the lake.
 - A **central lakefront access point** has been designed to serve as a communal gathering area, providing space for seating and various recreational activities.
 - Guests will have the opportunity to enjoy a range of **outdoor activities**, including **kayaking, paddleboarding, pétanque, volleyball, curling, and sailing**.
- **Community Gathering Space:**
 - A **multi-functional communal gathering area** has been designed to overlook the water, seamlessly blending into the natural landscape of the hillside.
 - This space will provide a scenic and welcoming environment for social engagement, relaxation, and special events.

Parking & Site Integration

To maintain a pedestrian-friendly and guest-centric environment, parking and related accessory structures have been strategically positioned to minimize visual and functional disruption to the site. These facilities have been designed to integrate efficiently with the **main Hazelett operation**, streamlining parking and maintenance logistics while preserving the overall guest experience.

Conclusion

We believe that this **thoughtfully designed, well-planned project** will serve as a valuable addition to Malletts Bay and the broader Colchester community. By blending **modern hospitality offerings with a deep respect for the natural landscape**, "The H" is poised to bring **fresh energy, innovation, and year-round activity** to this iconic waterfront location.

Thank you for your time and consideration. We look forward to your feedback and the opportunity to bring this vision to life.

PRELIMINARY PLAT REVIEW CRITERIA NARRATIVE

The “H” at Malletts Bay

Project Description

The project is a proposed redevelopment of the Hazelett water parcel located at 166 and 180 West Lakeshore Drive, entitled “The H at Malletts Bay”. This will be a hospitality project comprised of an Inn with a series of 5 cottages and a total of 20 rooms. In addition, the centerpiece of the project is a main building with a 48-seat restaurant at the main level, event space, and spa facilities. A new bathhouse will be constructed as well to enable beach users to use the facilities without having to go back the cottages/main building. New parking will be constructed across the street at 135 West Lakeshore Drive as part of a Site Plan application for that parcel.

We offer the following description of how the site complies with the Subdivision Review Standards of the Colchester Development Regulations.

Section 9.05-A Required Improvement List

The project features the merging of the lots encompassing 166 and 180 West Lakeshore Drive. A boundary survey of these parcels has been completed and any missing monuments or lot markers will be set.

A complete set of Landscaping Plans and budget has been prepared by T.J. Boyle Associates, LLC.

Potable water supply and wastewater disposal will be via new municipal connections.

There are no new roadways proposed as part of the project.

Stormwater management will be done in conjunction with stormwater improvements at 135 Lakeshore Drive which shares the same discharge point.

Section 9.05-B Suitability of Land

The area of land proposed for development is well suited for type of development proposed. There are no wetlands, natural areas, or areas prone to flooding near the proposed building sites. The slopes on the site are conducive to “walk out” buildings that are desirable for this type of project.

Section 9.05-C Lot Layout

There are no new lots proposed as part of the project. The lots serving 166 and 180 West Lakeshore Drive will be merged into a single lot.

Section 9.05-D Building Envelope

The building envelope for the merged lots is defined by the zoning setbacks to the front and side, and the lakeshore setback to the rear. These setbacks are shown on the plans.

Section 9.05-E Monuments and Lot Corners Markers

There are no public streets being created as part of this subdivision. Lot corners created as part of the subdivision shall be marked in accordance with regulations.

Section 9.05-F Energy Conservation

The proposed buildings will be constructed to current Vermont Residential Energy Standards.

Section 9.05-G Water

The proposed project is located in an area served by Colchester Fire District#2 (CFD2). CFD2 has previously indicated there is adequate water capacity to serve the project. A new 4" water line will be tapped from the existing main on West Lakeshore Drive and extended to the main building. Individual service lines for each cottage will be tapped off the 4" line. An additional service will be extended to the proposed bathhouse.

Section 9.05-H Wastewater Disposal

The proposed project is located in an area to be served by the new Mallets Bay sewer project. The site has previously approved plan for an on-site wastewater disposal system accommodating 4,482 gallons/day. It is our understanding that this design flow has been allocated to the property in terms of flows to the municipal sewer. The "H" has been designed to have flows within this original allocation. We have attached a worksheet outlining the project design flows as well as correspondence with Town Public Works staff indicating the that our strategy is acceptable. A State of Vermont Wastewater Disposal System and Potable Water Supply Permit Application will be filed for the project.

The system will include individual sanitary services from each building, flowing to a collection system. The sanitary sewer collection line will flow via gravity to a new pump station. The pump station will pump wastewater to one of the two sewer stubs installed for the property as part of the Mallets Bay sewer project.

Section 9.05-I Site Preservation and Landscaping

The project proposes grading and site improvements located on a steep, northeast-facing slope along the Lake Champlain shoreline in Colchester, VT, part of which is located within the 100' Protected Lakeshore Buffer. The existing vegetation on this slope is a mix of native and invasive species. The proposed finished grades within the lakeshore buffer will not exceed 2:1, and disturbed areas will be stabilized with erosion control measures, seeding and native vegetation. Biodegradable erosion control matting and an appropriate annual cover crop that germinates quickly will provide short-term stabilization and protection from storm events, while a custom seed mix of long-lived, deep-rooted species formulated for the sandy, north-facing slope will provide more permanent stabilization once established. Woody shrub and tree species have been carefully selected to reflect the naturally occurring plant communities found along Lake Champlain and nearby forests. The newly rebuilt slope is designed with ecology, reduced maintenance and aesthetics in mind. Matrix-style plantings comprised of native ferns, sedges, and groundcovers are proposed to surround the north foundations and courtyards. These dense, mixed plantings mimic the way plants grow together naturally, fomenting a

resilient plant community that requires less weeding, watering, and mulching than traditional landscaping installations. Larger trees and shrubs are also proposed in appropriate locations on the slope, replacing the predominantly invasive black locust that currently exists (see <https://vtinvasives.org/invasive/black-locust>). A survey of the existing trees with greater than 1" caliper has been conducted, and a more thorough evaluation of the various species will be conducted later in the spring.

A complete set of landscaping plans and details has been prepared by T.J. Boyle Associates, LLC and is attached.

Section 9.05-J Streets

No new streets are proposed with this project. The proposed project will be accessed from curb cuts located on West Lakeshore Drive. In order to reduce impervious surface and impacts to the existing slopes on the site, a narrow, one-way driveway is proposed. The entrance will be on the south end of the site, and the exit will be on the north end. Both curb cuts will align with existing curb cuts serving the Hazelett property across the street. Each curb cut will be approximately 45' in length, with a 30' throat. This is a massive reduction in the existing curb cuts on the property. There are currently three curb cuts with a total length of approximately 270 feet. Five parallel parking spaces are proposed in front of the main building. These will be primarily for check-in and drop off purposes, with the main parking areas being located across the road.

Access to south marina area will be maintained via a reconfigured driveway. This driveway will be 2-way and have room for a turnaround, and 6 parking spaces. The existing driveway to the recreation area to the north of the site will be removed and replaced with a pedestrian path.

Section 9.05-K Pedestrian Access

Pedestrian routes are an integral part of the site design. There is a sidewalk along the front of the buildings. Access to the waterfront is provided via a central stair and path near the main building. An additional path/stair on the north end of the site will replace the existing paved driveway at that end. A gravel walkway along the base of the slope will provide pedestrian connectivity through the site. There is a net reduction of impervious surface in the Shoreland protection zone.

The parking area at 135 Lakeshore Drive will connect to the site via a sidewalk from the parking lot and a cross-walk at West Lakeshore Drive. A flashing beacon is proposed for pedestrian safety.

The design team met with Amanda Clayton, the Town Engineer at the time, regarding the request at Sketch Plan for *"A 5-ft permanent easement for future sidewalk along West Lakeshore Drive and a 10-ft temporary construction easement adjacent to the permanent easement shall be granted to the Town of Colchester"*. We explained that due to the limited space for development on the lot, easements of this width would actually extend well into the travel way of our design plan. It was determined that any future sidewalk along the west side of West Lakeshore Drive could be located within the Town right of way, and that only the construction easement would be needed.

Section 9.05-L Utilities

There are no public utilities proposed with this subdivision. Utility services to the new buildings will be underground.

Section 9.05-M Traffic

A Traffic Impact Analysis has been prepared by Vanasse Hangen Brustlin (VHB) and is attached.

Section 9.05-N Stormwater & Erosion Control

The project will greater than 5,000 square feet of impervious surface to a common plan of development having greater than one acre of impervious surface. Therefore, a State of Vermont Stormwater Discharge Permit (coverage under General Permit 3-9050) will be required. We have prepared a stormwater narrative and supporting modeling and calculations, which are attached.

Erosion prevention and sediment control measures will be installed during construction in accordance with the Vermont Standards for Erosion Prevention and Sediment Control. Temporary erosion prevention and sediment control practices will include silt fence, rolled erosion control products, limiting disturbed areas, and stabilized construction entrances. Because over one acre of ground disturbance is proposed, coverage under State of Vermont General Permit 3-9020 will be required.

Section 9.05-O Excavation and Grading

No construction of public improvements is proposed as part of this subdivision. Excavation and grading related to construction of the buildings, driveways, and utilities will be conducted in the locations shown on the plan.

Section 9.05-P Outdoor Lighting

Site lighting is shown on the plans. All proposed lighting is downshielded and in compliance with Town regulations.

Section 9.05-Q Municipal Facilities & Recreation Areas

No additional recreation areas are required or proposed.

Section 9.05-R Governmental Services

The driveway for the proposed buildings is shown on the plans. E-911 address will be displayed on the buildings. The site is readily accessible from an existing municipal road.

Section 9.05-S Aesthetics

The project design provides appealing architecture and landscaping while maintaining lake views from the existing road.

Section 9.05-T Town Plan

No additional recreation areas are required or proposed.

Section 9.05-U Owners' Association

The project will remain under the control of a single owner.



THE H AT MALLETT'S BAY

A1

CONCEPTUAL PERSPECTIVES

05/09/25





THE H AT MALLETT'S BAY

A2

CONCEPTUAL PERSPECTIVES

05/09/25





THE H AT MALLETT'S BAY


A3

MAIN BUILDING


05/07/25




7 CARMICHAEL ST. ESSEX JUNCTION, VT 05452
P: 802.879.5153
F: 802.872.2764
SCOTTPARTNERS.COM



② NORTH ELEVATION (LAKE SIDE)
1/8" = 1'-0"



① EAST ELEVATION
1/8" = 1'-0"




⑤ CROSS SECTION
1/8" = 1'-0"

AVERAGE EXISTING GRADE = 123.3'
MAX PERMITTED HEIGHT (AVG+40') = 163.3'
MEASURED HEIGHT TO TALLEST RIDGE = 162.5'
ACTUAL HEIGHT = 39.2' (162.5' - 123.3')



③ SOUTH ELEVATION (STREET SIDE)
1/8" = 1'-0"






④ WEST ELEVATION
1/8" = 1'-0"

THE H AT MALLETT'S BAY

A4

MAIN BUILDING


05/07/25



7 CARMICHAEL ST. ESSEX JUNCTION, VT 05452
P: 802.879.5153
F: 802.872.2764
SCOTTPARTNERS.COM




4 NORTH
1/8" = 1'-0"



5 WEST
1/8" = 1'-0"

NOTE: COTTAGE 4 DOES NOT HAVE THIS WINDOW




8 CROSS SECTION
1/8" = 1'-0"

AVERAGE EXISTING GRADES:
COTTAGE 1 = 117.0'
COTTAGE 2 = 126.8'
COTTAGE 4 = 116.6'


MAX PERMITTED HEIGHTS (AVE+40')
COTTAGE 1 = 157.0'
COTTAGE 2 = 166.8'
COTTAGE 4 = 156.6'

MEASURED HEIGHTS TO TALLEST RIDGE:
COTTAGE 1 = 155.4'
COTTAGE 2 = 156.4'
COTTAGE 4 = 155.4'


ACTUAL HEIGHTS: (MEASURED HEIGHT - AVG GRADE)
COTTAGE 1 = 38.4'
COTTAGE 2 = 29.6'
COTTAGE 4 = 38.8'



(1) 2-BEDROOM SUITE
UPPER LEVEL
1/8" = 1'-0"



(2) STUDIO UNITS
GROUND FLOOR
1/8" = 1'-0"



(2) STUDIO UNITS
LOWER LEVEL
1/8" = 1'-0"

SCALE: 1/8" = 1'-0" FT / 30.48 CM
0' 1' 5' 10' 20'
30.48 152.4 304.8 609.6

SCALE (CM)
0 50 100 200 300 400 500 600

THE H AT MALLETT'S BAY


TYPICAL COTTAGE (1, 2 & 4)

05/07/25 THREE BUILDINGS, EACH CONTAINING (4) STUDIOS
& (1) 2-BEDROOM SUITE


A5



④ NORTH
1/8" = 1'-0"




⑤ WEST
1/8" = 1'-0"




⑧ CROSS SECTION
1/8" = 1'-0"


AVERAGE EXISTING GRADE = 127.0'
MAX PERMITTED HEIGHT (AVE+40') = 167.0'
MEASURED HEIGHT TO TALLEST RIDGE = 157.4'
ACTUAL HEIGHT = 30.4' (157.4' - 127.0')




⑥ SOUTH
1/8" = 1'-0"




⑦ EAST
1/8" = 1'-0"




(1) 2-BEDROOM SUITE
③ UPPER LEVEL
1/8" = 1'-0"



(2) STUDIO UNITS
① GROUND FLOOR
1/8" = 1'-0"



(1) MANAGER'S APARTMENT
(1) STUDIO UNIT
② LOWER LEVEL
1/8" = 1'-0"




THE H AT MALLETT'S BAY

COTTAGE 3

05/07/25 ONE BUILDING, CONTAINING (3) STUDIOS, (1) 2-BEDROOM SUITE & MANAGER'S APARTMENT


A6





① LOWER LEVEL
1/8" = 1'-0"



② GROUND FLOOR
1/8" = 1'-0"



③ UPPER LEVEL
1/8" = 1'-0"




THE H AT MALLETT'S BAY

COTTAGE 5

05/07/25

A7




④ NORTH
1/8" = 1'-0"




⑤ WEST
1/8" = 1'-0"



⑦ EAST
1/8" = 1'-0"




⑥ SOUTH
1/8" = 1'-0"



① CROSS SECTION
1/8" = 1'-0"

AVERAGE EXISTING GRADE = 124.2'
MAX PERMITTED HEIGHTS (AVE+40') = 164.2'
MEASURED HEIGHTS TO TALLEST RIDGE = 152.4'
ACTUAL HEIGHTS: (MEASURED HEIGHT - AVG GRADE) = 28.2'




THE H AT MALLETT'S BAY


COTTAGE 5

05/07/25

A8




① FLOOR PLAN
1/4" = 1'-0"




AVERAGE EXISTING GRADE = 115'
MAX PERMITTED HEIGHT (AVE+20') = 125'
MEASURED HEIGHT TO TALLEST RIDGE = 117'
ACTUAL HEIGHT = 2' (117' - 115')


⑦ CROSS SECTION
1/8" = 1'-0"




② NORTH ELEVATION
1/8" = 1'-0"



③ WEST ELEVATION
1/8" = 1'-0"



④ EAST ELEVATION
1/8" = 1'-0"









THE H AT MALLETT'S BAY

A9

BATH HOUSE

05/07/25




AVERAGE EXISTING GRADE = 131.6'
 MAX PERMITTED HEIGHT (AVE+40') = 171.6'
 MEASURED HEIGHT TO TALLEST RIDGE = 150.8'
 ACTUAL HEIGHT = 19.2' (150.8' - 131.6')

THE H AT MALLETT'S BAY

A10

ANNEX BUILDING

05/07/25



RELOCATED TRASH AND RECYCLING
6' SCREENING FENCE, MATCH
ARCHITECTURAL, SEE DETAIL 5
(WEST ELEVATION) AT COTTAGE 3

ENCROACHMENT INTO 100'
SHORELINE SETBACK
(SEE SUMMARY TABLE)

6 48" STONE STEPS
AND HANDRAIL DETAIL, TYP.

STONE PATH - 48" WIDE
DETAIL L4.0

PAVER
DETAIL L4.0

STONE SEAT WALL
DETAIL L4.0

GREEN ROOF
DETAIL L4.0

SNOW
STORAGE

FIRE LANE

FLUSH CURB

WASHED 3-6" RIVER STONE
DETAIL, TYP. L4.0

WEST LAKESHORE DRIVE

4 WALL MOUNTED FIXTURE
L3.0

BIKE RACK
DETAIL L4.0

CANOPY FIXTURE
L3.0

SITE LIGHT FIXTURE
L3.0

SNOW STORAGE

6" BLACK VINYL CHAIN LINK
FENCE WITH PRIVACY SLATS


LANDSCAPE AREA = 2,202.2 SF (10.2%)


PARKING AREA = 21,582.3 SF

Encroachment Summary Table

Building Walls		Total Encroachment
Existing	92.6	740.5
10% increase	9.26	
allowable w/ 10% increase	101.86	
Proposed		
COTTAGE #1	99.12	282.77
COTTAGE #2	0	36.19
COTTAGE #3	0	20.2669
COTTAGE #5	0	0
ACCESSORY BUILDING	0	0
MAIN BUILDING	0	368
TOTALS	99.12	734.99
2.74	12.03	5.51
Remaining Building	Remaining Appurtenance	Remaining Total


RELEASED FOR
PERMITTING
05/12/2025





LEGEND

- EXISTING DECIDUOUS TREES
- EXISTING CONIFER TREES
- DECIDUOUS TREES/SHRUBS
- CONIFER TREES/SHRUBS
- LAKESHORE RESTORATION PLANTING
- UPLAND SLOPE RESTORATION PLANTING
- GROVE PLANTING WITH SEEDED UNDERSTORY




Planting Schedule: Shrubs and Perennials						
Shrubs and Woody Groundcovers						
Quantity		Code	Scientific Name	Common Name	Size	
Inside Lake Setback	Outside Lake Setback					
54	22	AM	ARCTOSTAPHYLOS uva-ursi	Bearberry	6" #1	
21	9	CA	ARONIA melanocarpa	Black Chokeberry	#10	
27	0	SS	CORYLUS americana	American Hazelnut	36" #5	
18	0	SS	SALIX exigua ssp. 'interior'	Sandbar Willow	6" B&B	
99	0	SC	SAMBUCUS canadensis	Black Elderberry	#3	
33	11	DI	DIERVILLA lonicera	Bush Honeysuckle	#5	
23	9	SA	SYMPHORICARPOS albus	Snowberry	#2	
2	2	HV	HAMAMELIS virginiana	Witch-hazel	6-7" B&B	
4	22	HA	HYDRANGEA arborescens	Smooth Hydrangea	#5	
12	18	FG	POTERILLIA glandulifera	Ox-eye Daisy	4-5" B&B	
20	3	VA	VIBURNUM acerifolium	Maple-leaved Viburnum	#3	
7	3	ST	STAPHYLEA trifolia	Bladdernut	#5	
0	3	SV	SYRINGA vulgaris 'Monge'	Dark Purple Common Lilac	6" B&B	
0	16	STO	SPERULA tomentosa	Steeplebush	2" Gal	
0	19	PF	POTENTILLA fruticosa 'Pink Beauty'	Shrubby Cinquefoil	#5	
0	6	PO	PHYSCOCARPUS opulifolius	Common Ninebark	24" #5	
0	24	RAG	RHUS aromatica 'Grow Low'	Grow Low Fragrant Sumac	6" #1	
24	5	CSAF	CORNUS sericea 'Arctic Fire'	Arctic Fire Dogwood	#7	
Total Qty:		344	223			

Shade Perennial Matrix (S.P.M.)						
Quantity		Code	Scientific Name	Common Name	Size	
Inside Lake Setback	Outside Lake Setback					
112	274	A	CAREX pensylvanica	Pennsylvania Sedge	2" q	
74	183	B	ATHYRIUM filix-femina	Lady Fern	2" q	
81	146	C	DRYOPTERIS marginalis	Marginal Wood Fern	2" cal	
79	153	D	CAREX lasiocarpa	Broad-leaved sedge	2" cal	
35	67	E	CAREX blanda	Common wood sedge	2" cal	
21	61	F	TIARELLA cordifolia	Foamflower	1" q	
Total Qty:		402	884			
Other Perennials						
Qty	Code	Scientific Name	Common Name	Size		
0	84	OC	OSMUNDA cinnamomea	Cinnamon Fern	1 gal	
0	11	AMT	ACHILLEA millefolium 'Salmon Beauty'	Salmon Beauty Yarrow	#2	
0	18	CAP	CLEMATIS alpinia 'Pamela Jackson'	Alpine Clematis	#2	
0	20	CV	COREOPSIS verticillata 'Moonbeam'	Moonbeam Tickseed	#2	
0	33	FGE	FESTUCA glauca 'Elijah Blue'	Blue Fescue	#1	
0	71	NWL	HEPETA x fessendii 'Walters' Low'	Walters' Low Catmint	#2	
0	15	CB	CALAMAGROSTIS brachytricha	Korean Feather Reed Grass	#1	
Total Qty:		6	252			
Seed Mixes						
Qty	Code	Scientific Name	Application Rate	Unit Size		
3		Vermont Wetland Hummock Mix	20lbs per acre	Pound		
3		Shortgrass Woods Edge or Savanna Seed Mix	10 lbs per acre	1000 sf coverage		
14		VT Native Custom Steep Slope Erosion Control Mix (10,000 sf)	60 lbs/acre	Pound		

Planting Schedule: Trees						
Trees (deciduous)						
Quantity		Code	Scientific Name	Common Name	Size	
Inside Lake Setback	Outside Lake Setback					
1	0	AR	ACER rubrum	Red Maple	4" cal	
11	1	BP	BETULA populifolia 'Whitespire'	Gray Birch	3" cal	
1	0	SN	SALIX nigra	Black Willow	10"	
0	3	NS	NYSSA sylvatica	Tupelo	3" cal	
0	3	OV	OSYRIS virginiana	American Hophornbeam	2" cal	
0	1	QR	QUERCUS rubra	Red Oak	3"	
1	5	TA	TILIA americana	Basswood	3"	
0	5	GT	GLEDETIA fraxinifolia var. inermis 'Shademaster'	Shademaster Thornless Ho	3"	
0	5	BN	BETULA nigra 'Cully'	Cully River Birch	3"	
0	4	AF	ACER x freemanii 'Autumn Blaze'	Autumn Blaze Hybrid Maple	3" cal	
0	2	CeO	CELTIS occidentalis	Hackberry	3" cal	
2	7	ASGM	ACER saccharum 'Green Mountain'	Green Mountain Sugar Map	3" cal	
1	0	AP	ACER pensylvanicum	Striped Maple	2" cal	
6	0	PV	PRUNUS virginiana	Chokecherry	4" cal	
2	5	CCG	CRATAEGUS crus-galli inermis 'Cruscan'	Crusader Thornless Cocks'	2"	
Total qty:		25	41			

Evergreen trees and shrubs						
Quantity		Code	Scientific Name	Common Name	Size	
Inside Lake Setback	Outside Lake Setback					
1	12	AB	ABIES balsamea	Balsam Fir	6"	
0	4	PG	PICEA glauca	White Spruce	6"	
1	5	JV	JUNIPERUS virginiana	Eastern Red Cedar	6"	
6	0	TO	THUJA occidentalis	White Cedar	10"	
0	7	TON	THUJA occidentalis 'Nigra'	Dark American Arborvitae	8"	
0	5	TR	TRAXUS 'Hicoria'	Hick's Yew	30"	
0	9	PJM	RHODODENDRON 'PJM Elite'	PJM/Rhododendron	36"	
6	3	IG	ILEX glabra 'Shamrock'	Isaberry/Holly	#7	
0	12	TOS	THUJA occidentalis 'Smaragd'	Emerald Green Arborvitae	8"	
0	22	JS	JUNIPERUS 'Blue Green'	Sea Green Juniper	30"	
0	2	TCP	TSUGA canadensis 'Pendula'	Dwarf Weeping Hemlock	5-6" B&B	
Total qty:		14	81			

Summary of Existing and Proposed Vegetation Within 100' Lake Setback	
Total Stems > 1" Existing	124
Total Stems > 1" DBH to Remain:	70
Total Stems > 1" DBH to Be Removed:	54 (17 of which exceed 8" DBH)
Total DBH inches to Be Removed:	358" (254" are from the 17 referenced immediately above, or 70%)
Total Number of Trees > 1" Cal. to be Planted:	49
Total Cal. Inches of Proposed Trees:	85
Total Number of Woody Shrubs to be Planted:	321



Colchester Zoning Requirements

Classification	Ave. Luminance		Ave. Uniformity Ratio	Max. Uniformity Ratio
Area	Avg.	Max.	Min.	Max./Min.
Parking Lot	1.0			20:1
Walkway	0.5			
Canopy	3.0			

Proposed Lighting Calculations

Area	Avg.	Max.	Min.	Ave./Min.	Max./Min.
Drives and Parking North of W. Lakeshore Dr.	1.0				17.4 : 1
Drives and Parking South of W. Lakeshore Dr.	0.8				14.8 : 1
Sidewalks North of W. Lakeshore Dr. ^{2,4}	0.5				
Sidewalks South of W. Lakeshore Dr. ^{2,4}	0.5				
Sidewalk at Mid-Block Crossing	1.5 (2.0 @ +5') ⁴				
Canopies North of W. Lakeshore Dr. ³	1.7				
Canopy South of W. Lakeshore Dr. ³	1.7				

Footnotes:

¹ Illuminance - All calculations are in Horizontal Footcandles (fc) and apply depreciation and dirt factors



² Walkway Lighting - Light levels for pedestrian areas meet Iesna recommendations per Lighting For Exterior Environments (RP-33-14), which recommends a Minimum Maintained Average Horizontal Illuminance Level of 0.5 Footcandles and a 4:1 Horizontal Average to Minimum Ratio. This is recommended for Lighting Zone 0 (LZ-0) (Iesna) - which is described as 'Areas in which permanent lighting is not expected and when used, is limited in the amount of lighting and the period of operation. LZ-0 typically includes undeveloped areas of open space, wilderness parks and preserves, areas near astronomical observatories, or any other area where the protection of a dark environment is critical.'

³ Canopy Lighting - Light Levels at entries are under 3 Footcandles Maximum.


⁴ Mid-Block Crossings - Light Levels for mid-block crossings (over West Lakeshore Drive) meet IESNA recommendations per ANSI/IES Roadway Lighting (RP-8-14), which recommends on average a vertical illuminance level of 2.0 Footcandles measured at 1.5m (5 ft) from the road surface to allow drivers to detect pedestrians in mid-block crosswalks at adequate stopping distance under rural conditions.

- GENERAL LIGHTING NOTES:**
- MOUNTING HEIGHT IS DISTANCE BETWEEN THE LIGHT SOURCE AND THE GROUND PLANES FOR PHOTOMETRIC ANALYSIS, CUT POLES AS NEEDED
 - VOLTAGE TO BE VERIFIED BY ELECTRICAL ENGINEER PRIOR TO ORDERING
 - DRIVE CURRENT - REVIEW DRIVE CURRENT AND WATTAGE WITH ELECTRICAL ENGINEER AND CONTRACTOR PRIOR TO ORDERING
 - DIMMING TO BE VERIFIED BY ELECTRICAL ENGINEER PRIOR TO INSTALLATION. THE FIXTURE SHOULD BE SET AT THE PERCENTAGE AS SHOWN ON THE LIGHT SCHEDULE.
 - REFER TO LIGHTING SCHEDULE FOR QUANTITIES AND SPECIFICATIONS
 - SEE LIGHTING DETAILS FOR PRODUCT CUT SHEETS


RELEASED FOR PERMITTING
05/09/2025




C SECTION C: LOOKING WEST
SCALE: $\frac{1}{16}'' = 1'$




B SECTION B: LOOKING WEST
SCALE: $\frac{1}{16}'' = 1'$



A SECTION A: LOOKING WEST
SCALE: $\frac{1}{16}'' = 1'$




RELEASED FOR
PERMITTING
05/09/2025



TREE PRUNING NOTES:

- REFER TO ANSI A300 (Part 1, MOST UPDATED VERSION) PRUNING SPECIFICATIONS FOR ADDITIONAL INFORMATION.
- WORK SHOULD BE PREFORMED BY A **CERTIFIED ARBORIST** OR **PROFESSIONAL TREE COMPANY**.
- AVOID DAMAGING BARK AND OTHER LIVING TISSUE THROUGHOUT THE PRUNING PROCESS.
- MAKE SURE PRUNING TOOLS ARE SHARP.
- MAKE CLEAN CUT AS CLOSE TO THE BRANCH COLLAR AS POSSIBLE. DO NOT LEAVE A STUB.
- REDUCE THE SIZE OF THE BRANCH FOR A BETTER CUT.
- THE FIRST AND SECOND CUTS SHOULD BISECT THE ANGLE BETWEEN ITS BRANCH BARK RIDGE AND AN IMAGINARY LINE PERPENDICULAR TO THE BRANCH OR STEM.
- NOT MORE THAN 25% OF GROWTH SHOULD BE REMOVED FROM A CANOPY DURING A GROWING SEASON.



10 TREE PRUNING ILLUSTRATION
L2.0 NTS


TREE PROTECTION NOTES:

- PRIOR TO ANY CONSTRUCTION ACTIVITY, ALL TREE PRESERVATION MEASURES MUST BE IMPLEMENTED.
- CONTRACTOR CHOSEN FOR THIS WORK WILL BE AN EXPERIENCED TREE SERVICE FIRM THAT HAS SUCCESSFULLY COMPLETED TREE PROTECTION, ROOT PRUNING, AND TRIMMING WORK, SIMILAR TO THAT REQUIRED FOR THIS PROJECT.
- PRIOR TO CONSTRUCTION SHALL LOCATE AND VERIFY THE EXISTENCE OF ALL UTILITIES PRIOR TO STARTING WORK. CONTACT DIG SAFE TWO FULL BUSINESS DAYS BEFORE PLANTING. (48 HOUR MIN.)
- PRIOR TO THE SITE VISIT ALL TREE PRESERVATION AREAS SHALL BE STAKED OUT ON SITE BY SURVEY.
- TREE PROTECTION FENCING SHALL REMAIN INTACT THROUGHOUT ALL CONSTRUCTION ACTIVITY.
- THERE WILL BE NO EXCAVATION FOR PROPOSED SITE WORK WITHIN FENCED AREA.
- NO MATERIALS OR EQUIPMENT SHALL BE STORED, STOCKPILED OR OPERATED WITHIN TREE PROTECTION AREAS.
- TREE PROTECTED AREAS WILL BE LEFT AS NATURAL AS POSSIBLE.
- IN AREAS OF EXCAVATION NEAR TREE, IDENTIFY AND CUT ROOTS IN CONSULTATION WITH OWNER.
- REMOVE POORLY ATTACHED AND RUBBING LIMBS. CLEAN THE CROWN OF DEAD, DISEASED AND WEAK LIMBS. THINNING OF HEALTHY LIMBS IS NOT RECOMMENDED AT THIS TIME.
- ANY NECESSARY TRENCHING SHALL BE IMMEDIATELY BACKFILLED WITH REMOVED SOIL OR OTHER SOIL MIX AS DESCRIBED IN CONTRACT SPECIFICATIONS.
- AN AIR SPADE/AIR KNIFE IS TO BE USED TO EXCAVATE DOWN TO MINIMUM OF 2'. SEE DETAILS

SIGN DETAIL

- ATTACHMENTS OF SIGNS TO TREES IS PROHIBITED.
- SIGNS SHOULD BE MADE OF VINYL OR PLASTIC.
- SIGNS SHOULD BE PROPERLY MAINTAINED, PENALTIES WILL BE ENFORCED FOR REMOVAL OF SIGNS.
- AVOID INJURY TO ROOTS WHEN PLACING POSTS FOR THE SIGNS.
- SIGNS SHOULD BE POSTED 50' O.C. AND WITHIN 20' OF THE BEGINNING AND END OF EACH FENCE TO BE VISIBLE TO ALL CONSTRUCTION PERSONNEL.
- SIGNS TO BE SECURELY FASTENED TO THE FENCE OR FENCE POSTS.
- SIGNS TO HAVE A WHITE BACKGROUND AND ORANGE OR RED TEXT.



- FENCE DETAIL:
- THIS FENCE SERVES AS A TREE PROTECTION DEVICE ONLY.
 - ROOT DAMAGE SHALL BE AVOIDED WITHIN FENCED AREA.
 - FENCE SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.



9 TREE PROTECTION FENCE
L2.0 NTS

ROOT PRUNING TRENCH NOTES:

- USE AN AIR SPADE/AIR KNIFE TO DIG THE 2' TRENCH AND EXPOSE THE ROOTS.
- EXPOSED ROOTS SHOULD BE CUT WITH A SAW OR LOPPERS TO MAKE A CLEAN SMOOTH CUT, NOT TORN OR RIPPED.
- MULCH EXPOSED ROOTS DURING THE CUTTING PROCESS TO KEEP FROM DRYING OUT.
- BACKFILL TRENCH WITH MIXTURE OF TOPSOIL AND COMPOST AS PER CONTRACT SPECIFICATIONS.



8 TREE PROTECTION
L2.0 NTS

GENERAL PLANTING NOTES:


- THE LANDSCAPE CONTRACTOR SHALL LOCATE AND VERIFY THE EXISTENCE OF ALL UTILITIES PRIOR TO STARTING WORK. CONTACT DIG SAFE TWO FULL BUSINESS DAYS BEFORE PLANTING. (48 HOUR MIN.)
- THE LANDSCAPE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIAL IN QUANTITIES SUFFICIENT TO COMPLETE THE PLANTING SHOWN ON ALL DRAWINGS. THE PLAN QUANTITIES SHALL ALWAYS SUPERCEDE THE PLANT LIST.
- ALL PLANT MATERIAL SHALL CONFORM AND BE INSTALLED TO THE GUIDELINES ESTABLISHED BY THE CURRENT ANSI Z60.1.
- NO PLANT SHALL BE PUT INTO THE GROUND BEFORE ROUGH GRADING HAS BEEN FINISHED AND APPROVED BY THE PROJECT LANDSCAPE ARCHITECT OR EQUAL.
- THE LANDSCAPE CONTRACTOR SHALL PROVIDE AMENDED PLANTING SOIL AS PER THE CONTRACT SPECIFICATIONS.
- SOIL DEPTH SHOULD BE AS LISTED BELOW. EXISTING SOIL ON SITE WHICH MEETS THE CONTRACT SPECIFICATIONS MAY BE USED. REMOVE SUB GRADE AND OTHER GRAVEL FILL IN PLANTING AREAS ON SITE.

6.1. GROUND COVER BEDS: 12" DEPTH.
6.2. LAWN AREAS: 6" DEPTH
6.3. SHRUB/PLANT BEDS: 18" DEPTH
- PLANTS SHALL BE INSTALLED SUCH THAT THE ROOT FLARE IS AT OR SLIGHTLY ABOVE FINAL GRADE (DUE TO NURSERY PRACTICES THIS MAY REQUIRE REMOVING SOIL FROM THE TOP OF THE ROOT BALL TO LOCATE THE ROOT FLARE).
- ALL PLANTS SHALL BE BALLED AND BURLAPPED OR CONTAINER GROWN AS SPECIFIED. NO CONTAINER GROWN STOCK WILL BE ACCEPTED IF IT IS ROOT BOUND. ALL ROOT WRAPPING MATERIAL MADE OF SYNTHETICS OR PLASTICS SHALL BE REMOVED AT THE TIME OF PLANTING.
- WITH CONTAINER GROWN STOCK, THE CONTAINER SHALL BE REMOVED AND THE CONTAINER BALL SHALL BE CUT THROUGH THE SURFACE IN TWO VERTICAL LOCATIONS.
- THE DAY PRIOR TO PLANTING, THE LOCATION OF ALL TREES AND SHRUBS SHALL BE FLAGGED FOR APPROVAL BY THE PROJECT LANDSCAPE ARCHITECT OR EQUAL.
- LANDSCAPE ARCHITECT MAY REQUIRE ALL PLANTS BE SPRAYED WITH AN ANTIDESSICANT WITHIN 24 HOURS AFTER PLANTING. IN TEMPERATE ZONES, ALL PLANTS SHALL BE SPRAYED WITH AN ANTIDESSICANT AT THE BEGINNING OF THEIR FIRST WINTER.
- STAKING PLANTS IS AT THE DISCRETION OF THE LANDSCAPE CONTRACTOR. ONLY STAKE PLANTS IN THE MANNER SPECIFIED IN THE PLANTING DETAILS.
- ALL PLANTS SHALL BE WATERED THOROUGHLY TWICE DURING THE FIRST 24 HOUR PERIOD AFTER PLANTING. ALL PLANTS SHALL THEN BE WATERED WEEKLY, IF NECESSARY, DURING THE FIRST GROWING SEASON.
- THE LANDSCAPE CONTRACTOR SHALL REFER TO THE CONTRACT SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- THE LANDSCAPE CONTRACTOR SHALL REFER TO THE PLANT LIST FOR SEASONAL REQUIREMENTS RELATED TO THE TIME OF PLANTING.

PLANT SPACING CHART


Spacing 'D'	Row 'A'	Number of Plants	Area Unit
6" O.C.	5.2'	4.61	1 SQ. FT.
8" O.C.	6.93"	2.6	
10" O.C.	8.66"	1.66	
12" O.C.	10.4"	1.15	
15" O.C.	13.0"	7.38	10 SQ. FT.
18" O.C.	15.6"	5.12	
24" O.C.	20.8"	2.91	
30" O.C.	26.0"	1.55	
36" O.C.	30.0"	1.25	100 SQ. FT.
4" O.C.	3.46'	7.25	
5" O.C.	4.38'	4.61	
6" O.C.	5.2'	3.2	
8" O.C.	6.93'	1.8	
10" O.C.	8.66'	1.16	1000 SQ. FT.
12" O.C.	10.4'	8	
15" O.C.	13.0'	5	
20" O.C.	17.3'	2.88	
25" O.C.	21.65'	1.85	10,000 SQ. FT.
30" O.C.	26.0'	1.29	
40" O.C.	34.6'	7.22	10,000 SQ. FT.

O.C. = ON CENTER FOR USE WHEN PLANTS ARE SHOWN EQUIDISTANT FROM EACH OTHER (AS SHOWN) PLANT SPACING CHART




7 PLANT SPACING CHART DETAIL
L2.0 NTS

- SOIL COMPACTION AFTER INSTALLATION SHALL BE 75-250 PSI AT SOIL MOISTURE BETWEEN FIELD CAPACITY AND WILTING POINT




6 PLANT BED
L2.0 NTS


- SOIL COMPACTION AFTER INSTALLATION SHALL BE 75-250 PSI AT SOIL MOISTURE BETWEEN FIELD CAPACITY AND WILTING POINT




5 LAWN & SEEDING AREA
L2.0 NTS



4 GROUNDCOVER PLANTING
L2.0 NTS




3 SHRUB PLANTING
L2.0 NTS




2 TREE PLANTING ON SLOPE DETAIL
L2.0 NTS

- PRUNE DAMAGED OR BROKEN BRANCHES



1 TREE PLANTING DETAIL
L2.0 NTS



3 SITE LIGHT POLE BASE DETAIL
L3.0

BEACON
design + production technology

RSA-B-S Series Poles
ROUND STRAIGHT ALUMINUM

DATE: LOCATION:
TYPE: PROJECT:
CATALOG #:

APPLICATIONS

- Lighting installations for side and top mounting of luminaires with effective projected area (EPA) not exceeding maximum allowable loading of the specified pole in its installed geographic location

CONSTRUCTION

- SHAFT: One-piece straight aluminum with round cross section; Extruded shafts of 6061-T6 aluminum in 1/8", 3/16", or 1/4" thickness. Base plate of 356 cast aluminum.
- BOLT COVERS: Four (4) individual bolt covers provided, painted to match pole and base finish.
- POLE CAP OR FINALS: Cap or decorative finials available for side mounted luminaires. Open top or tenons provided for post top mounted luminaires.
- HAND HOLE: Aluminum hand hole frame; Mounting provisions for grounding lug located behind cover.
- ANCHOR BOLTS: Four galvanized anchor bolts provided per pole with minimum yield of 55,000 psi (ASTM F1554). Galvanized hardware with two washers and two nuts per bolt for leveling.

FINISH

- Durable Thermostat polyester powder coat paint finish with nominal 3.0 mil thickness
- Powder paint finish coat available in multiple standard colors; Custom colors available; RAL number preferable.

ORDERING EXAMPLE

RSA-B-S - 16 - 40 - A/B/C - CAP - 2L - B3 - DBT - VM2

TEENOS & POLE CAPS

BASE DETAIL

OPTICS

- LEDs mount to a metal printed circuit board assembly (MCPCB).
- Molded silicone gasket throughout insures the sealing between the two compartments and provides ingress protection.
- All external fasteners are stainless steel.
- Cover is secured to Lens frame by the latch and hinge.

OPTIONAL BACKLIGHT CONTROL ON EACH LED MODULE TO COMPLETELY CONTROL UNWANTED BACKLIGHT

OPTIONAL FUTURE FINISH OPTICAL SURFACES WILL NOT EXCEED BUG RATINGS OF THE STANDARD WHITE FINISH.

LENS

- Standard lens (CLR) K108
- Clear Polycarbonate Lens (CP) K103

INSTALLATION

- Features must be grounded in accordance with national, state and/or local electrical codes. Failure to do so may result in serious personal injury.

ACCESSORIES - Order Separately

CATALOG NUMBER **DESCRIPTION**

Current

2 SITE LIGHT POLE
L3.0

KIM LIGHTING

UR20 - Post Top
ARCHITECTURAL AREA/SITE

DATE: LOCATION:
TYPE: PROJECT:
CATALOG #:

FEATURES

- 20" size in single/dual arm post top, pole and wall mount
- High performance optics up to 16,874 delivered lumens
- Elegant form factor
- Diffusion lens option
- ULCUL listed for wet locations, IP66 and 4015.5G vibration rated

CONTROL TECHNOLOGY

LightGRID

SPECIFICATIONS

CONSTRUCTION

- Low copper aluminum alloy die-casting is designed as one-piece.
- Molded silicone gasket throughout insures the sealing between the two compartments and provides ingress protection.
- All external fasteners are stainless steel.
- Cover is secured to Lens frame by the latch and hinge.

OPTICS

- LEDs mount to a metal printed circuit board assembly (MCPCB).
- Molded silicone gasket throughout insures the sealing between the two compartments and provides ingress protection.
- All external fasteners are stainless steel.
- Cover is secured to Lens frame by the latch and hinge.

OPTIONAL BACKLIGHT CONTROL ON EACH LED MODULE TO COMPLETELY CONTROL UNWANTED BACKLIGHT

OPTIONAL FUTURE FINISH OPTICAL SURFACES WILL NOT EXCEED BUG RATINGS OF THE STANDARD WHITE FINISH.

LENS

- Standard lens (CLR) K108
- Clear Polycarbonate Lens (CP) K103

INSTALLATION

- Features must be grounded in accordance with national, state and/or local electrical codes. Failure to do so may result in serious personal injury.

ACCESSORIES - Order Separately

CATALOG NUMBER **DESCRIPTION**

Current

1 SITE LIGHT FIXTURE
L3.0

Juno

Juno SlimForm™ LED with Selectable CCT
5" and 7" Round Downlight for JBox Installation

JSF Series

Product Features

- Sleek, ultra-low profile energy efficient LED surface mount downlights available in 5" and 7" sizes. Optional finish trim available for custom, designer look similar to standard recessed downlights. Provides general illumination in residential and commercial applications including multi-family and hospitality. Ideal for use in corridors, living spaces, closets, hallways, pantries, stairways, outdoor covered areas and much more.
- With the newly added selectable CCT switch, the JSF gives the ultimate in flexibility for both the distributor as well as the end user.

Applications

- Suitable for wet locations (indoor covered ceilings): perfect for closets, showers, bathrooms, outdoor soffits, and covered ceiling applications.
- Residential and Light Commercial applications including multi-family and hospitality.
- Ideal for use in corridors, foyers, living spaces, closets, hallways, pantries, stairways and much more.
- Installs directly into industry standard junction boxes
- Suitable for use within closet storage spaces when installed per NEC requirements. Junction box sizes vary. Verify compatibility with fixture prior to installation.

Performance

Delivered Lumens JSF 5IN = 700L JSF 7IN = 1000L
Led Color Temperature Switchable White (2700K, 3000K, 3500K, 4000K, 5000K) Default set at 3000K
CRI 90+
Voltage Dedicated 120V and MVOLT (120V/277V)
Dimming Phase Dimming down to 10%

Specifications

JSF 5IN 5.25 (13.34) 0.75 (1.91)
JSF 7IN 7.75 (19.77) 0.75 (1.91)

All dimensions are in inches (centimeters unless otherwise indicated).

Acuity Brands
One Lithonia Way • Conyers, GA 30012 • Phone: 1-800-755-SERV (7378) • Visit us at www.acuitybrands.com
Light Commercial & Residential

5 CANOPY LIGHTING FIXTURE
L3.0

WDGE1 LED
Architectural Wall Sconce

Specifications

Depth (D1): 5.5"
Depth (D2): 1.5"
Height: 8"
Width: 9"
Weight: 9 lbs (without options)

Introduction

The WDGE LED family is designed to meet specific every wall-mounted lighting need in a widely accepted shape that blends with any architecture. The clean, rectangular design comes in four sizes with lumen packages ranging from 1,200 to 25,000 lumens, providing true site-wide solution.

WDGE1 delivers up to 2,000 lumens with a soft, non-pixelated light source, creating a visually comfortable environment. The compact size of WDGE1, with its integrated emergency battery backup option, makes it an ideal over-the-door wall-mounted lighting solution.

Ordering Information

EXAMPLE: WDGE1 LED P2 4K 80CRI MV VOLT SRM PE DDBXD

Series

Package

Color Temperature

CR

Distribution

Voltage

Mounting

Shipped included

Shipped separately

Notes

Finish

Commercial Outdoor

One Lithonia Way • Conyers, Georgia 30012 • Phone: 1-800-755-SERV (7378) • www.lithonia.com








WDGE1 LED
Rev 02/24/25

4 WALL MOUNTED LIGHT FIXTURE
L3.0

NOTE:
LIGHT FIXTURE SELECTION MAY BE
ADJUSTED FOR FINAL PLAN

GENERAL LIGHTING NOTES:

- MOUNTING HEIGHT EQUATES BETWEEN THE LIGHT SOURCE AND THE POLE BASE FOR USING CALCULATION PHOTOMETRIC ANALYSIS, CUT POLES AS NEEDED
- VOLTAGE TO BE VERIFIED BY ELECTRICAL ENGINEER PRIOR TO ORDERING
- DRIVE CURRENT - REVIEW DRIVE CURRENT AND WATTAGE WITH ELECTRICAL ENGINEER AND CONTRACTOR BEFORE INSTALLATION
- DIMMING TO BE VERIFIED BY ELECTRICAL ENGINEER PRIOR TO INSTALLATION. THE FIXTURE SHOULD BE SET AT THE PERCENTAGE (1/3 THE TOTAL POWER) AS SHOWN ON THE LIGHT SCHEDULE.
- SEE LIGHTING SCHEDULE ON LIGHTING PLAN FOR QUANTITIES AND SPECIFICATIONS



B-1

Owner Information

Hazelett Strip-Casting Corporation

Planning & Zoning Information



Parcel ID: 65-019002-00000 & 65-020002-00000
Zoning: Lake Shore 1 (LS1)

180 W. Lakeshore Drive Area = 1.11 Ac
166 W. Lakeshore Drive Area = 1.36 Ac

Total Lot Coverage: 40% maximum allowed
Minimum Lot Size: 30,000 sf
Lot Frontage: 120 ft
Front Yard Setback: 15 ft
Side Yard Setback: 15 ft
Rear Yard Setback: 15 ft
Building Height Max: 40ft Ridge - 35ft Flat (com.)

LOT COVERAGE

LOT COVERAGE	Existing	Proposed
166 & 180 W. Lakeshore Drive	22.3%	30.4%
135 W. Lakeshore Drive	5.05%	5.44%
FRONT YARD COVERAGE		
166 & 180 W. Lakeshore Drive	26.1%	43.7%
135 W. Lakeshore Drive	28.0%	28.0%



Notes:

- This plan is not a boundary survey. Refer to Boundary Survey prepared by Krebs and Lansing Consulting Engineers, "Lands of Hazellet Strip-Casting Corporation, dated March 3, 2025.
- The underground utilities shown on this plan are based on visible utilities located during a topographic survey performed by Krebs & Lansing in June 2017 and January 2025. Underground utilities are approximate and not warranted to be exact or complete. Dig Safe shall be contacted prior to any excavation.
- The location of the Malletts Bay sanitary sewer and force main are taken from design plans prepared by Aldrich & Elliot Water Resource Engineers, entitled "West Lakeshore Drive Mainline Sewers Contract No.1A", dated Dec. 2023.
- Elevations are based on the NAVD 88 (Geoid 12A) vertical datum.
- Project Horizontal Coordinates derived from GPS observation using reference frame NAD83 (2011) 2010.00 epoch.
- Aerial photography is based on information provided by the Vermont Center for Geographical Information, 2023 flight.

Legend

- Iron pipe or rebar found
- 12 Survey Control Point
- Existing Sign
- Existing Light Pole
- Existing Deciduous Tree
- Existing Evergreen Tree
- 314.7 x Existing Spot Grade Elevation
- 150 Existing 1ft Contour Interval
- 95.5 Existing 1ft Contour Interval
- g Existing Gas Line/Valve
- Existing Sewer Line/Manhole
- fm Existing Sewer Forcemain
- Existing Storm Line/Manhole/Basin
- ohp Existing Overhead Electric Line/Power Pole
- ohu Existing Overhead Utility
- comm Existing Communications Line
- ue&t Existing Underground Electric & Telephone Line
- lite Existing Site Lite Line
- Existing Guardrail
- Existing Tree Line
- Existing Chain Link Fence
- Existing Barbed Wire Fence
- Existing Stockade Fence
- ugp Existing Underground Power
- w Existing Water Line/Hydrant/Valve/Shutoff
- Approximate Property Line
- Existing Setback
- Existing Easement
- Existing Rock Retaining Wall
- G New Gas Line/Valve
- S New Sewer Line/Manhole
- FM New Sewer Forcemain
- ST New Storm Line/Manhole/Basin
- W New Water Line/Hydrant/Valve/Shutoff
- UGP New Underground Power


HAZELETT
STRIP-CASTING
CORPORATION

COLCHESTER, VT



164 Main Street, Suite 201 P: (802) 878-0375
Colchester, Vermont 05446 www.krebsandlansing.com

STAMP:



Project:

THE 'H'
AT
MALLETTS BAY

180 & 166 W. Lakeshore Drive
Colchester, Vermont

Project No.	23314
Scale	1" = 50'
Drawn by	SWH
Checked by	
Date	03/03/25


Revisions		
No.	Date	Description
	05/09/25	site layout

Drawing Title

OVERALL SITE
PLAN

Drawing No.

C-1.0




SEE SHEET C-2.1

REFER TO SITE NOTES AND LEGEND
SHEET C-1.0

Project:	
THE 'H' AT MALLETTS BAY	
180 & 166 W. Lakeshore Drive Colchester, Vermont	
Project No.	23314
Scale	1" = 20'
Drawn by	SWH
Checked by	
Date	03/03/25

Revisions		
No.	Date	Description
	05/09/25	site layout







KREBS & LANSING
CONSULTING ENGINEERS
164 Main Street, Suite 201
Colchester, Vermont 05446
P: (802) 878-0375
www.krebsandlansing.com


Drawing Title	
SITE & UTILITY PLAN	

STAMP:

Drawing No.	
C-2.0	







Legend

- Inlet protection around catch basin
- Barrier Fence
- Silt Fence
- Crushed stone for stabilization
- Stone check dam

REFER TO ADDITIONAL EPSC NOTES
ON DETAIL SHEETS CD-8 AND CD-9

Project:

**THE 'H'
AT
MALLETTS BAY**

180 & 166 W. Lakeshore Drive
Colchester, Vermont

Project No.	23314
Scale	1" = 20'
Drawn by	SWH
Checked by	
Date	03/03/25


Revisions		
No.	Date	Description
01	05/09/25	site layout

Drawing Title

**GRADING & EPSC
PLAN**

Drawing No.

C-3.0




**KREBS &
LANSING**
CONSULTING ENGINEERS

164 Main Street, Suite 201 P. (802) 878-0375
Colchester, Vermont 05446 www.krebsandlansing.com

STAMP:

SEE SHEET C-2.1

REFER TO SITE NOTES AND LEGEND
SHEET C-1.0




REFER TO SITE NOTES AND LEGEND
SHEET C-1.0

SEE SHEET X-1.1

Project:
**THE 'H'
AT
MALLETTS BAY**
180 & 166 W. Lakeshore Drive
Colchester, Vermont

Project No. 23314
Scale 1" = 20'
Drawn by JAR/SWH
Checked by
Date 03/03/25

Revisions		
No.	Date	Description




KREBS & LANSING
CONSULTING ENGINEERS
164 Main Street, Suite 201 P. (802) 878-0375
Colchester, Vermont 05446 www.krebsandlansing.com

STAMP:

Drawing Title
**EXISTING
CONDITIONS PLAN**

Drawing No.
X-1.0



REFER TO SITE NOTES AND LEGEND
SHEET C-1.0

Project:
**THE 'H'
AT
MALLETT'S BAY**
180 & 166 W. Lakeshore Drive
Colchester, Vermont

Project No. 23314
Scale 1" = 20'
Drawn by JAR/SWH
Checked by
Date 03/03/25

Revisions		Description
No.	Date	

Drawing Title
**EXISTING
CONDITIONS PLAN**



STAMP:

Drawing No.
X-1.1

GENERAL CONSTRUCTION NOTES:

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ALL DISTURBED AREAS BACK TO ORIGINAL CONDITION, INCLUDING BUT NOT LIMITED TO CURBING, SIDEWALKS, ROAD, PARKING AREAS, LANDSCAPING, SITE LIGHTING, ELECTRICAL, AND ETC. ALL ASPHALT SHALL BE SAW-CUT PRIOR TO PAVING.
2. THE METHODS AND MATERIALS OF CONSTRUCTION SHALL CONFORM TO THE LATEST STANDARDS OF THE STATE OF VERMONT AND TOWN OF BOLTON, ALL WORK SHALL BE IN CONFORMANCE WITH ALL PERMITS AND APPROVALS ISSUED FOR THE PROJECT. IN CASE OF CONFLICT, THE MORE STRINGENT SPECIFICATION SHALL APPLY AS DIRECTED BY ENGINEER. ALL WORK SHALL BE DONE IN A WORKMANLIKE MANNER AND COMPLETED IN THE TIME SPECIFIED BY OWNER.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK AND MATERIALS SHOWN AND REQUIRED TO MAKE THE JOB COMPLETE. THESE DRAWINGS DO NOT SHOW EVERY FITTING OR APPURTENANCE. MATERIALS SHALL BE AS SPECIFIED ON THE DRAWINGS. MANUFACTURER'S PRODUCT SPECIFICATIONS SHALL BE SUBMITTED FOR ALL MATERIALS TO THE ENGINEER FOR APPROVAL PRIOR TO INSTALLATION.
4. THE LOCATION AND SIZE OF EXISTING UNDERGROUND UTILITIES IS NOT WARRANTED TO BE EXACT OR COMPLETE. THE CONTRACTOR SHALL FIELD LOCATE ALL UTILITIES AND SHALL CONTACT THE AFFECTED UTILITY COMPANY, THE ENGINEER AND THE MUNICIPALITY PRIOR TO MAKING ANY HOOK UPS. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL EXISTING UTILITIES AND THEIR UNINTERRUPTED SERVICES. ALL OFF-SITE BACKFILL, SHEETING, SHORING, DEWATERING, CLEARING AND GRUBBING, EROSION CONTROL, DUST CONTROL, TRAFFIC CONTROL, GRADING, AND ALL INCIDENTALS SHALL BE INCLUDED AS PART OF THE REQUIRED WORK.
5. THE CONTRACTOR SHALL VERIFY ALL TEMPORARY BENCH MARKS BEFORE USE.
6. THE WORKMEN AND PUBLIC SHALL BE PROTECTED BY THE CONTRACTOR FROM ANY AND ALL HAZARDS CONNECTED WITH THE CONSTRUCTION WORK. OPEN TRENCHES, MATERIALS, OR EQUIPMENT WITHIN THE WORKING LIMITS ARE TO BE GUARDED BY THE USE OF ADEQUATE BARRICADES OR FLAGMEN. ALL BARRICADES LEFT IN POSITION OVERNIGHT ARE TO BE PROPERLY LIGHTED. KEROSENE POTS ARE NOT ACCEPTABLE. WHEN WORK NARROWS THE USABLE PAVEMENT, FLAGMEN SHALL BE EMPLOYED TO AID THE FLOW OF TRAFFIC SO THAT THERE WILL BE NO UNDUE DELAYS. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR THE SAFETY OF ALL WORKMEN, THE GENERAL PUBLIC AND ALL DAMAGES TO PROPERTY OCCURRING FROM OR UPON THE WORK OCCASIONED BY NEGLIGENCE OR OTHERWISE GROWING OUT OF A FAILURE ON THE PART OF THE CONTRACTOR TO PROTECT PERSONS OR PROPERTY FROM HAZARDS OF OPEN TRENCHES, MATERIALS, OR EQUIPMENT AT ANY TIME OF THE DAY OR NIGHT WITHIN THE WORKING AREA. ALL WORK SHALL BE IN CONFORMANCE TO OSHA REGULATIONS, TITLE 19, PARTS 1926.651 AND 1926.652, AND APPLICABLE TO VOSHA REGULATIONS.
7. THE CONTRACTOR SHALL VERIFY ALL UTILITY INTERSECTIONS AND CONTACT ENGINEER AND OWNER WITH CONFLICTS.
8. THE CONTRACTOR SHALL CALL, DIG SAFE PRIOR TO ANY EXCAVATION.
9. THE CONTRACTOR SHALL COORDINATE FINAL LOCATION AND INVERTS FOR WATER, SEWER, AND STORM BUILDING CONNECTIONS WITH THE ARCHITECT, STRUCTURAL ENGINEER, AND MECHANICAL ENGINEER.
10. ALL STUMPS, ROCK, AND OTHER NON-APPROVED TRENCH BACKFILL MATERIAL DISCOVERED DURING CONSTRUCTION IS THE EXCLUSIVE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE PROPERTY AND DISPOSED OF IN A STATE APPROVED DISPOSAL LOCATION. ALL EXISTING SOILS REUSED FOR FILL SHALL CONFORM TO ALL APPLICABLE SECTIONS OF VTRANS SPECIFICATIONS SECTION 203-EXCAVATION & EMBANKMENTS OR ENGINEER APPROVED EQUAL. CONTRACTOR SHALL REVIEW SOIL INVESTIGATION REPORT AND SOIL LOGS PRIOR TO BID. ANY SOIL REUSED AS FILL UNDER ROADS AND APPLICABLE CONCRETE SIDEWALKS SHALL PASS A SUBGRADE PROOF ROLL WITH A LOADED TANDEM. FILL SOILS THAT DO NOT PASS A SUBGRADE PROOF ROLL SHALL BE REMOVED AND REPLACED AT THE CONTRACTOR'S EXPENSE.
11. THE ABOVE NOTE (NOTE 10) DOES NOT INCLUDE TOPSOIL. CONTRACTOR SHALL REUSE THE TOPSOIL AS NEEDED FOR THE PROJECT'S CONSTRUCTION. ANY ADDITIONAL TOPSOIL IS THE PROPERTY OF THE PROJECT OWNER. IF NOT USED DURING CONSTRUCTION, THE CONTRACTOR SHALL DISCUSS ANY REMAINING TOPSOIL WITH THE PROPERTY OWNER. CONTRACTOR SHALL PLACE REMAINING TOPSOIL IN A LOCATION DETERMINED BY THE PROPERTY OWNER OR REMOVE IT FROM THE PROPERTY.
12. ALL PASSING SIEVE, PROCTOR, AND COMPACTION TESTING EXPENSES SHALL BE PAID BY THE CONTRACTOR. TESTING COORDINATION, ALL OTHER REQUIRED TESTING, AND EXPENSES FOR FAILED TESTS SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
13. THE CONTRACTOR SHALL CONTACT THE GREEN MOUNTAIN POWER (GMP) AND OR VERMONT ELECTRIC COOPRIOR TO ANY WORK IN THE VICINITY OF THE EXISTING ELECTRIC CONDUITS.
14. THIS PROJECT WILL REQUIRE COVERAGE UNDER AN STATE OF VERMONT GENERAL CONSTRUCTION STORMWATER DISCHARGE PERMIT. THE CONTRACTOR WILL FOLLOW THE PERMIT AS WELL AS THE RULES, REGULATIONS, AND DIRECTION OUTLINED IN THE STATE OF VERMONT "LOW RISK HANDBOOK FOR EROSION PREVENTION AND SEDIMENT CONTROL" FROM FEBRUARY 2020. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING, MAINTAINING AND REMOVING ALL EROSION AND SEDIMENT CONTROL DEVICES SHOWN ON THE PLANS OR DETAILS AND, TO THE MAXIMUM EXTENT PRACTICAL, TO MINIMIZE POTENTIAL CONTAMINATION OF STORMWATER RUNOFF FROM THE CONSTRUCTION ACTIVITIES.
15. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL "AS-BUILT" MEASUREMENT AND DRAFTING REQUIREMENTS AS OUTLINED ON THE DETAIL SHEETS. ALL TRENCH EXCAVATIONS SHALL REMAIN OPEN UNTIL ALL AS-BUILT SURVEY SHOTS HAVE BEEN TAKEN. PROGRESS RECORD DRAWINGS SHALL BE SUBMITTED TO THE ENGINEER AS INDICATED IN THE RECORD DRAWING SPECIFICATIONS.
16. SEE EROSION PREVENTION AND SEDIMENT CONTROL AND LOGISTICS PLANS FOR LOCATIONS OF STAGING / STORAGE AREAS.
17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SIGNAGE AND CONSTRUCTION BARRIER/SAFETY FENCING NECESSARY FOR PROVIDING SAFE VEHICULAR AND PEDESTRIAN ACCESS THROUGH OR AROUND THE SITE DURING CONSTRUCTION. CONTRACTOR SHALL COORDINATE THIS WITH THE TOWN OF BOLTON AND THE TOWN'S DEPARTMENT OF PUBLIC WORKS.
18. DEFINITION OF "PRECONSTRUCTION EXCAVATION" FOR THESE CONTRACT DOCUMENTS SHALL BE: THE SITE CONTRACTOR SHALL EXPOSE UTILITIES AND OBTAIN ALL NECESSARY INFORMATION, INCLUDING BUT NOT LIMITED TO, INVERT ELEVATION, SIZE, DEPTH, PIPE TYPE, JOINT LOCATION, ETC. CONTRACTOR SHALL TRANSIT SURVEY THE LOCATION AND ELEVATIONS OF THE UTILITY. CONTRACTOR SHALL PROVIDE THE ENGINEER WITH SKETCHES INDICATING HORIZONTAL AND VERTICAL INFORMATION OF PIPE OR CONDUIT TYPE AND SIZE, CROSS-SECTION INFORMATION, CONCRETE ENCASEMENT INFORMATION (TOP AND BOTTOM ELEVATIONS, WIDTH, ETC.), JOINT LOCATION, ETC. OF EACH REQUIRED EXISTING UNDERGROUND UTILITY. ACCURACY OF HORIZONTAL LOCATION IS WITHIN 1 FOOT, AND ACCURACY OF VERTICAL ELEVATION IS WITHIN 0.02 FT. (1/4"). COORDINATE ALL EXCAVATION WITH CITY, OWNER, AND ENGINEER. PRECONSTRUCTION EXCAVATIONS SHALL OCCUR PRIOR TO ORDERING STRUCTURES AND PRIOR TO UTILITY CONSTRUCTION TO FACILITATE REDESIGN AND/OR DESIGN CONFIRMATION.
19. THE LOCATION OF THE PRECONSTRUCTION EXCAVATION SYMBOLS DOES NOT NECESSARILY INDICATE THE LOCATION OF THE BURIED UTILITY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO FIND AND EXPOSE THE UTILITY.
20. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS OF IMPORTING AND PLACING TOPSOIL AND/OR COMPOST NECESSARY TO COMPLETE THE PROJECT. CONTRACTOR SHALL TEST TOPSOIL FOR APPROVAL BY THE OWNER AND ENGINEER.
10. ALL SEWER AND STORM PIPES SHALL BE PVC SDR 35 UNLESS OTHERWISE NOTED. ALL NEW SANITARY AND STORM PIPES SHALL BE LAID WITH A LASER TO ELEVATION AND SLOPE AS SHOWN ON THE PLANS.
11. CORE AND BOOT ALL EXISTING STRUCTURES UNLESS OTHERWISE NOTED.
12. ALL NEW CATCH BASINS AND SANITARY SEWER MANHOLE MUST HAVE ONE 6" PRECAST CONCRETE GRADE RING.
13. ALL WATERLINE PIPE SHALL BE DUCTILE IRON CLASS 52 OR C900 PVC. ALL BENDS AND FITTINGS SHALL HAVE POURED IN PLACE THRUST BLOCKS, MIXED ONSITE CONCRETE IS NOT ALLOWED.
14. TEMPORARY GROUNDWATER, STORMWATER, AND SEWER BY-PASS PUMPING AND/OR DIVERSION IS THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL NECESSARY PUMPS AND EQUIPMENT TO PERFORM THE WORK. OVERNIGHT PUMPING IS NOT ALLOWED.
15. ALL SIDEWALKS SHALL HAVE 2% MAXIMUM CROSS SLOPE. ALL RAMPS AND STAIRS SHALL HAVE A LANDING AT THE BOTTOM WITH A MAXIMUM SLOPE OF 2% FOR 5 FEET.
16. CONTRACTOR TO PIN CONCRETE SIDEWALK/SLABS TO ALL CONTACT POINTS WITH STAIRS, BUILDING, BIKE SLAB, RETAINING WALLS, ETC.
17. CONTRACTOR SHALL MAINTAIN FULL OCCUPANCY AND FIRE DEPARTMENT ACCESS TO ALL SURROUNDING BUILDINGS. COORDINATE ALL TEMPORARY ACCESS WITH THE MUNICIPALITY.
18. BURIED NATURAL GAS IS SHOWN FOR ALIGNMENT PURPOSES ONLY. CONTACT VERMONT GAS SYSTEMS FOR DESIGN AND DETAILS OF NEW GAS LINE. SEE ADDITIONAL NOTES ON C-1.01 AND C-1.02.
19. REMOVAL OF ALL EROSION CONTROL IS THE RESPONSIBILITY OF THE CONTRACTOR.
20. AT THE END OF THE PROJECT, CLEAN THE SUMPS OF ALL NEW AND EXISTING CATCH BASINS AND STORM MANHOLES WITHIN THE PROJECT LIMITS.
21. ELECTRICAL AND LIGHTING ARE SHOWN FOR ILLUSTRATIVE/COORDINATION PURPOSES ONLY. REFER TO ELECTRICAL PLANS AND SPECIFICATIONS FOR DESIGN.
22. SEE LANDSCAPE AND/OR STRUCTURAL PLANS FOR ALL RETAINING WALLS, UTILITY PADS, STAIRS, AND EXTERIOR CONCRETE AT DOORS.
23. REFER TO PLUMBING, MECHANICAL AND/OR FIRE PROTECTION PLANS FOR WATER, SEWER AND STORM DESIGN WITHIN FIVE FEET OF THE BUILDING.

EPSC GENERAL NOTES:

1. EROSION PREVENTION AND SEDIMENT CONTROL (EPSC) PRACTICES SHALL BE IMPLEMENTED IN ALL AREAS WHERE THERE IS AN INCREASED RISK OF EROSION, AND WHERE THERE IS POTENTIAL FOR DISCHARGE OF STORMWATER RUNOFF (EITHER DIRECT OR INDIRECT) TO A WATER BODY.
2. EPSC MEASURES SHALL BE INSTALLED PRIOR TO ANY EARTH DISTURBING ACTIVITIES WITHIN A GIVEN DRAINAGE AREA WITH THE EXCEPTION OF LAND DISTURBANCE THAT MAY RESULT FROM ACCESSING THE AREA(S) WITH EQUIPMENT IN WHICH EPSC MEASURES ARE TO BE INSTALLED. THIS EXCEPTION INCLUDES LAND DISTURBANCE THAT MAY RESULT FROM ACCESS OF EQUIPMENT THAT IS NEEDED FOR:EXPLORATION AND/OR EPSC MEASURE INSTALLATION PHASES OF THE PROJECT, TEMPORARY SEDIMENT BASINS, TEMPORARY SEDIMENT TRAPS, PERIMETER DIKES, TEMPORARY SEDIMENT BARRIERS, AND OTHER TEMPORARY MEASURES INTENDED TO TRAP SEDIMENT SHALL BE CONSTRUCTED AS A FIRST STEP IN ANY LAND DISTURBING ACTIVITY AND SHALL BE MADE FUNCTIONAL BEFORE UPSLOPE LAND DISTURBANCE TAKES PLACE WITH THE EXCEPTION OF THOSE ACTIVITIES STATED ABOVE. EARTH DISTURBANCE INCLUDES STUMPING AND GRUBBING OF CLEARED AREAS.
3. EPSC MEASURES SHALL BE INSTALLED PURSUANT TO THE EPSC PLAN, THE 2020 STATE OF VERMONT LOW RISK SITE HANDBOOK FOR EROSION PREVENTION AND SEDIMENT CONTROL, THE 2020 VERMONT EROSION PREVENTION AND SEDIMENT CONTROL STANDARDS AND SPECIFICATIONS, AND/OR ANY OTHER RELEVANT PROJECT PERMITS.
4. ALL PROPOSED CHANGES SHALL BE APPROVED BY THE ON-SITE PLAN COORDINATOR (OSPC) OR HIS/HER DESIGNEE PRIOR TO IMPLEMENTATION.
5. LOGGING ACTIVITIES SHALL BE CONDUCTED IN ACCORDANCE WITH ACCEPTABLE MANAGEMENT PRACTICES FOR MAINTAINING WATER QUALITY ON LOGGING JOBS IN VERMONT (AMPS, 2006).
6. PERMISSION MUST BE GRANTED BY VT DEC PRIOR TO USE OF ANY SUPPORT ACTIVITIES OCCURRING OUTSIDE OF THE APPROVED PROJECT BOUNDARIES.
7. ALL PARTIES ASSOCIATED WITH CONSTRUCTION ACTIVITIES WHO MEET EITHER OF THE FOLLOWING TWO CRITERIA OF "PRINCIPAL OPERATOR" MUST OBTAIN COVERAGE UNDER THE CONSTRUCTION STORMWATER DISCHARGE PERMIT FOR THE PROJECT PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES BY THAT OPERATOR:

A. THE PARTY HAS OPERATIONAL CONTROL OVER CONSTRUCTION PLANS AND SPECIFICATION, INCLUDING BUT NOT LIMITED TO THE ABILITY TO MAKE MODIFICATIONS TO THOSE PLANS AND SPECIFICATIONS; OR

B. THE PARTY HAS CONTINUOUS DAY-TO-DAY OPERATIONAL CONTROL OF THOSE ACTIVITIES AT THE PROJECT THAT ARE NECESSARY TO ENSURE COMPLIANCE WITH AN EPSC PLAN FOR THE SITE OR OTHER PERMIT CONDITIONS (E.G., THEY ARE AUTHORIZED TO DIRECT WORKERS AT A SITE TO CARRY OUT ACTIVITIES REQUIRED BY THE EPSC PLAN OR COMPLY WITH OTHER PERMIT CONDITIONS).
8. EXISTING VEGETATION SHALL BE PROTECTED AND MAINTAINED TO THE EXTENT PRACTICABLE.
9. A VEGETATED BUFFER SHALL BE MAINTAINED FOR WATER BODIES WHERE FEASIBLE (E.G., WETLANDS AND STREAMS).
10. TO THE EXTENT PRACTICABLE, SURFACE FLOW SHALL BE DIVERTED AWAY FROM EXPOSED SOILS VIA DIVERSION BERMS, EARTH DIKES, PERIMETER DIKES/SWALES, TEMPORARY SWALES, WATER BARS, AND/OR CHECK DAMS.
11. RESOURCE AREAS (E.G., WETLANDS, STREAMS, RTE PLANT SPECIES) SHALL BE FLAGGED PRIOR TO ANY CONSTRUCTION RELATED ACTIVITIES OCCURRING WITHIN CLOSE PROXIMITY TO THOSE AREAS.
12. EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT VIOLATE WATER QUALITY STANDARDS OR CONTRIBUTE TO EROSION. DEWATERING DETAILS SHALL BE REVIEWED AND APPROVED BY OSPC PRIOR TO USE.
13. CONCENTRATED RUNOFF SHALL NOT FLOW DOWN STEEP SLOPES UNLESS CONTAINED WITHIN AN ADEQUATE TEMPORARY OR PERMANENT CHANNEL (SEE DETAILS), FLUME, OR SLOPE DRAIN STRUCTURE.
14. UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA:

A. NO MORE THAN 500 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.

B. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES, WHERE FEASIBLE, BUT NOT IN RESOURCE AREAS.
8. WHERE FEASIBLE, ALL SEDIMENT REMOVED FROM SEDIMENT CONTROL PRACTICES AS PART OF MAINTENANCE SHALL BE DISPOSED OF IN AN AREA THAT IS AT LEAST ONE OF THE FOLLOWING, WITH IMMEDIATE STABILIZATION FOLLOWING DISPOSAL OF MATERIAL:

A. LESS THAN 5% SLOPE

B. AT LEAST 100 FEET FROM ANY DOWNSLOPE WATER BODY OR CONVEYANCE TO A WATER BODY, INCLUDING A DITCH

C. VEGETATED
9. DISTURBED AREAS BORDERING OR DRAINING TO EXISTING ROADS SHALL HAVE AN APPROPRIATE SEDIMENT BARRIER (E.G., SILT FENCE) SPANNING THE EDGE OF THE DISTURBANCE TO PREVENT WASHING OF SEDIMENT ONTO ROADWAYS OR INTO ROAD DITCHES.
10. IN ADVANCE OF PREDICTED RAINFALL OR SNOWMELT, ALL EPSC MEASURES THAT ARE LOCATED IN ACTIVE AREAS OF EARTH DISTURBANCE SHALL BE INSPECTED AND REPAIRED, AS NEEDED. IF NECESSARY, THIS SHALL INCLUDE TEMPORARY STABILIZATION OF ALL DISTURBED SOILS ON THE SITE IN ADVANCE OF THE ANTICIPATED RUNOFF PERIOD.
11. DUST CONTROL SHALL BE HANDLED VIA WATER APPLICATION TO ROADWAYS AND OTHER AREAS WHERE DUST MAY BE GENERATED.

GENERAL GRADING AND SITE WORK NOTES

1. ALL AREA DISTURBED AND ALL AREAS WITHIN THE CLEARING LIMITS SHALL BE GRADED AND COVERED WITH A MINIMUM OF 4" OF LOAM TOPSOIL. THE AREAS TO BE LOAMED SHALL BE FREE AND CLEAR OF ROOTS, WASTE MATERIAL AND OTHER DELETERIOUS MATERIAL. TOPSOIL SHALL BE SPREAD AND LIGHTLY COMPACTED TO A DEPTH OF 6". TOPSOIL SHALL BE APPROVED BY THE ENGINEER. ALL SIDE SLOPES ARE TO BE LOAMED.
2. ALL TURF ESTABLISHMENT SHALL BE IN ACCORDANCE WITH SECTION 651 OF THE VT STANDARD SPECIFICATIONS 2018 AND THE MUNICIPALITY SPECIFICATIONS. MULCHING SHALL FOLLOW SEEDING BY NO MORE THAN 24 HOURS.
3. ALL CUT SLOPES SHALL BE NO STEEPER THAN 2:0H ON 1:0V. ALL FILL SLOPES SHALL BE NO STEEPER THAN 2:0H ON 1:0V.
4. THE CONTRACTOR SHALL NOT DISTURB ANY GROUND BETWEEN OCTOBER 15TH BETWEEN APRIL 15TH WINTER MONTHS, UNLESS APPROVED BY THE ENGINEER.
5. TEMPORARY SILT FENCE SHALL BE ERECTED PRIOR TO ANY CLEARING OR CONSTRUCTION. FENCING MAY BE ERECTED IN PHASES, BUT IN NO CASE SHALL GROUND DISTURBANCE PROCEED FENCING. SPECIAL AREAS MAY BE DESIGNATED BY THE OWNER FOR PRESERVATION OF EXISTING TREES. THESE AREAS SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO INSURE NO DAMAGE IS DONE TO DESIGNATED TREES.
6. EXISTING PLANTINGS ARE LOCATED IN GENERAL AREAS AS SHOWN ON THIS PLAN. CONTRACTOR SHALL PROTECT PLANTINGS SO AS NOT TO DAMAGE THESE OR THEIR ROOT SYSTEMS.
7. SLOPE STABILITY BASED UPON UNSATURATED SOIL CONDITIONS. IF DURING CONSTRUCTION SATURATED SOILS ARE ENCOUNTERED, CONTACT THE ENGINEER IMMEDIATELY.

ALL CONNECTIONS TO MUNICIPAL WATER UTILITIES INSTALLED ON THE PROJECT TO BE OBSERVED BY THE ENGINEER AND THE AUTHORIZED REPRESENTATIVE OF THE UTILITY; TOWN OF COLCHESTER AND COLCHESTER FIRE DISTRICT PRIOR TO BACKFILLING THE UTILITY BEING INSTALLED. THE ENGINEER SHALL BE NOTIFIED 48 HOURS BEFORE THE WORK IS PLANNED TO BEGIN. ALL DETAILS ARE SUBJECT TO THE MOST RECENT REVISIONS OF THE COLCHESTER PUBLIC WORKS SPECIFICATIONS AND DETAILS FOR THE INSTALLATION OF WATER LINES AND APPURTENANCES. PROJECT SHALL FOLLOW ALL DETAILS IN THIS PLAN SET, COLCHESTER DPW SPECIFICATIONS, AND THE COLCHESTER FIRE DISTRICT SPECIFICATIONS. THE MOST STRINGENT DETAILS WILL APPLY.

WATER & SEWER CONSTRUCTION NOTES

1. THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL CONSTRUCTION OF WATER MAIN, STORM AND SANITARY SEWER SYSTEMS AS SHOWN ON THE PLANS. THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL NECESSARY ADAPTERS, FITTINGS, ETC. TO MAKE CONNECTIONS TO THE EXISTING AND PROPOSED UNITS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK SHOWN OR IMPLIED ON THE PLANS AND/OR REFERENCED IN THE SPECIFICATIONS AND PERMITS. THE CONTRACTOR SHALL SUBMIT, FOR APPROVAL BY THE ENGINEER, ALL TYPES OF MATERIALS AND PRODUCTS USED.
2. THE CONTRACTOR SHALL COORDINATE ALL WORK ON THE WATER SUPPLY SYSTEM WITH THE OWNER, THE TOWN OF BOLTON, BOLTON PUBLIC WORKS, BOLTON VALLEY COMMUNITY WATER & SEWER (CWD), AND THE CIVIL ENGINEER. ALL WATER INSTALLATION WORK AND WATER DISTRIBUTION MATERIALS MUST COMPLY WITH THE CURRENT BOLTON PUBLIC WORK SPECIFICATIONS.
3. THESE PLANS ARE NOT RESPONSIBLE FOR DESIGN OF WATER AND SEWER SERVICES WITHIN 5 FEET OF THE BUILDING. THE SITE CONTRACTOR SHALL BE RESPONSIBLE FOR EXTENDING THE SERVICES TO THE PLUMBING AND/OR FIRE SYSTEM CONNECTION WITHIN THE BUILDING. SEE PLUMBING ENGINEER, MECHANICAL ENGINEER AND/OR FIRE PROTECTION PLANS FOR SCOPE, DESIGN AND SPECIFICATIONS WITHIN 5 FT. OF THE BUILDING.
4. CONTRACTOR SHALL PROVIDE ALL NECESSARY FITTINGS AND APPURTENANCES TO COMPLETE THE WATERLINE CONSTRUCTION WORK. THIS INCLUDES TEMPORARY FITTINGS AND GAUGES NECESSARY TO SAFELY COMPLETE THE FLUSHING ACTIVITIES REQUIRED PRIOR TO MAKING CONNECTIONS WITH BUILDING PLUMBING.
5. THE PROJECT SHALL BE CONSTRUCTED, COMPLETED, MAINTAINED, AND OPERATED IN ACCORDANCE WITH THE APPROVED PLANS. NO CHANGES SHALL BE MADE IN THE PROJECT WITH OUT THE WRITTEN APPROVAL OF THE TOWN, CWD, AND THE CIVIL ENGINEER. A COPY OF THE FINAL APPROVED PLANS SHALL BE SUBMITTED TO CWD AND THE TOWN PRIOR TO CONSTRUCTION OF THE WATER SYSTEM IMPROVEMENTS.
6. THE TOWN AND CWD SHALL BE NOTIFIED IN ADVANCE TO INSPECT ALL MECHANICAL JOINTS FITTINGS, MAIN LINE TAPS, APPURTENANCES, THRUST BLOCKS, WATER LINE CROSSINGS, AND TESTING PRIOR TO OCCURRENCE OR BACKFILLING.
7. ALL DOMESTIC SERVICES AND FIRE SPRINKLER SYSTEMS THAT ARE CONNECTED TO THE PUBLIC WATER SYSTEM SHALL BE PROTECTED WITH A BACKFLOW PREVENTION ASSEMBLY, AND AN APPROPRIATE THERMAL EXPANSION SYSTEM. THE MECHANICAL CONTRACTOR SHALL COORDINATE APPROVED BACKFLOW PREVENTION WITH THE TOWN AND CWD.

WATER MAINS

1. APPLIES TO NEW DOMESTIC WATER MAINS AND SERVICES.
2. THE PIPE FOR WATER MAIN SHALL BE CL52 DUCTILE IRON, ALL D.I. PIPE SHALL BE POLYETHYLENE ENCASED. DUCTILE IRON FITTINGS SHALL CONFORM TO AWWA C110, 350 POUNDS WORKING PRESSURE. VALVES SHALL BE MANUFACTURED TO MEET ALL REQUIREMENTS OF AWWA SPECIFICATION C509 OR C515. FOUR-INCH AND SIX-INCH PIPE SHALL HAVE NO LESS THAN 2 BRASS WEDGES INSTALLED AT EACH JOINT. EIGHT-INCH AND 10" PIPE SHALL HAVE NO LESS THAN 3 WEDGES INSTALLED AT EACH JOINT.
3. ALL PIPE SHALL BE INSTALLED IN ACCORDANCE WITH AWWA C600. THE PIPE SHALL BE KEPT FREE OF FOREIGN MATTER AND DEBRIS DURING INSTALLATION. WHEN THE PROCESS OF PIPE LAYING HAS STOPPED, ANY OPEN ENDS OF PIPE SHALL BE PLUGGED. THERE SHALL BE A MINIMUM OF 6'-0" COVER OVER ALL PIPE AND SERVICE LINES. ANY PIPE DEFLECTION SHALL NOT EXCEED FIFTY (50%) PERCENT OF RECOMMENDED MANUFACTURER'S MAXIMUM DEFLECTION. BACKFILL MATERIALS AND PROCEDURES SHALL BE AS DETAILED ON THE DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL SHEETING AND/OR SHORING NECESSARY TO COMPLY WITH OSHA - VOSHA REGULATIONS.
4. THE TESTING OF THE WATER MAIN SHALL CONSIST OF THE TESTING OF ALL INSTALLED PIPE, SERVICES AND HYDRANTS IN ACCORDANCE WITH AWWA C600. THE TESTING SHALL CONSIST OF A PRESSURE TEST AND LEAKAGE TEST. ALL TESTING SHALL BE DONE WITH POTABLE WATER AND IN THE PRESENCE OF THE ENGINEER, REPRESENTATIVES FROM THE MUNICIPALITY AND THE MUNICIPALITY PUBLIC WORKS. THE PRESSURE TEST CONSISTS OF MAINTAINING A MINIMUM INTERNAL PIPE PRESSURE OF 200 PSI FOR TWO (2) HOURS. THE TESTING ALLOWANCE SHALL BE DEFINED AS THE MAXIMUM QUANTITY OF MAKEUP WATER THAT IS ADDED INTO A PIPELINE UNDERGOING HYDROSTATIC PRESSURE TESTING, OR ANY VALVED SECTION THEREOF, IN ORDER TO MAINTAIN PRESSURE WITHIN +/- 5 PSI OF THE SPECIFIED TEST PRESSURE (AFTER THE PIPELINE HAS BEEN FILLED WITH WATER AND THE AIR HAS BEEN EXPELLED). NO PIPE INSTALLATION WILL BE ACCEPTED IF THE QUANTITY OF MAKEUP WATER IS GREATER THAN THAT DETERMINED BY THE FOLLOWING FORMULA:

$$\frac{L}{148,000} = \frac{SD}{P}$$

L = TESTING ALLOWANCE (MAKEUP WATER), IN GALLONS PER HOUR

S = LENGTH OF PIPE TESTED, IN FEET

D = NOMINAL PIPE DIAMETER, IN INCHES

P = AVERAGE TEST PRESSURE DURING THE HYDROSTATIC TEST, IN POUNDS PER SQUARE INCH (GAUGE)
5. CHLORINATING OF THE SYSTEM SHALL BE ACCOMPLISHED AFTER THE WATER MAIN HAS BEEN SUCCESSFULLY PRESSURE TESTED AND THOROUGHLY FLUSHED. DISINFECTING SHALL BE IN ACCORDANCE WITH AWWA C-651. THE DISINFECTING PROCESS SHALL BE DEEMED ACCEPTABLE ONLY AFTER TWO CONSECUTIVE SETS OF ACCEPTABLE SAMPLES, TAKEN FROM THE FLUSHED AND DISINFECTED MAIN 24 HOURS APART, SHOWS NO EVIDENCE OF BACTERIOLOGICAL CONTAMINATION. FOR PROPER DISINFECTION USE MINIMUM 25 MG/L CHLORINE CONCENTRATION FOR 24 HOURS. THE CONCENTRATION MUST REMAIN ABOVE 10 MG/L. TABLET DISINFECTING IS NOT ACCEPTABLE. DECHLORINATION SHALL BE REQUIRED WHILE FLUSHING THE ORIGINAL CHLORINE FROM THE NEW LINE. COORDINATE WITH THE THE MUNICIPALITY AND THE MUNICIPALITY PUBLIC WORKS REGARDING THE DISPOSAL OF THE HIGHLY CHLORINATED WATER FLUSHED FROM THE NEW WATERLINE.
6. THE WATER MAIN SHALL BE THOROUGHLY FLUSHED WITH A MINIMUM FLOW VELOCITY OF 2.5 FT/S TO FLUSH FOREIGN MATERIALS OUT OF THE VALVES AND HYDRANTS. AT LEAST 48 HOURS PRIOR TO WATERLINE FLUSHING, THE CONTRACTOR SHALL CONTACT THE OWNERS, MUNICIPALITY FIRE DEPARTMENT, THE DISTRICT WATER SUPPLY COMPANY, AND THE ENGINEER.

SANITARY SEWER

1. ALL SEWER LINES AND MANHOLES SHALL BE THOROUGHLY TESTED BY THE CONTRACTOR IN ACCORDANCE WITH THE ENVIRONMENTAL PROTECTION RULES (11/06/2023).
2. ALL SANITARY MANHOLES SHALL BE VACUUM TESTED IN THE PRESENCE OF THE ENGINEER. THE STRUCTURE SHALL BE TESTED PRIOR TO BACKFILL WITH THE LOWEST SEAM EXPOSED. TEST PROCEDURES AND PRESSURE SHALL BE DETERMINED JOINTLY BY THE LOCAL APPROVAL AGENCY AND THE ENGINEER. FAILURE OF ANY VACUUM TEST SHALL NECESSITATE REPAIR AND/OR REPLACEMENT OF THE STRUCTURE AND RETEST. WATER TESTING MANHOLES IS NOT ACCEPTABLE.
3. ALL SANITARY MAINS SHALL BE AIR TESTED IN THE PRESENCE OF THE ENGINEER. AT A MINIMUM, THE TEST PRESSURE SHALL BE 4 POUNDS PER SQUARE INCH AT THE HIGHEST POINT ALONG THE TEST FOR 4 MINUTES.
4. UTILITY TESTING. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SCHEDULING SANITARY TESTING AT A MINIMUM OF 24 HOURS PRIOR TO THE TEST. BASED ON AVAILABILITY OF ENGINEER'S STAFF, THE ENGINEER SHALL ACCOMMODATE THE TESTING SCHEDULE WITHIN 24 HOURS OF THE CONTRACTOR REQUESTED TEST DATE/TIME.
5. THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE ENGINEER IF PRE-SCHEDULED TESTING AND/OR WATER/SEWER CONSTRUCTION IS CANCELED. IF CONTRACTOR DOES NOT CONTACT ENGINEER AND ENGINEER VISITS THE SITE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENGINEER'S FEES/MILEAGE FOR SITE VISIT.

ADDITIONAL NOTES AND TESTING REQUIREMENTS

1. IN ADDITION TO THE ABOVE REQUIREMENTS AND APPLIES TO WATER AND SANITARY SEWER.
2. ALL WATER LINES AND SEWER LINES SHALL BE THOROUGHLY TESTED BY THE CONTRACTOR IN ACCORDANCE WITH THE ENVIRONMENTAL PROTECTION RULES (11/06/2023) AND THE CHAPTER 21 WATER SUPPLY RULES (03/17/2020) (THE MORE STRINGENT RULE SHALL APPLY).
3. ALL PRIVATE OR MUNICIPAL WATERLINES SHALL BE TESTED BY THE CONTRACTOR IN ACCORDANCE WITH THE PROCEDURES OUTLINED IN AWWA C600 AND/OR NFPA 24.
4. NO WATER MAIN SHALL BE CLOSER THAN TEN (10) FEET TO ANY SANITARY SEWER OR SANITARY MANHOLE AND FIVE (5) FEET TO ANY CATCH BASIN OR STORM SEWER LINE. PROVIDE MINIMUM OF 18" VERTICAL SEPARATION BETWEEN WATER MAIN AND STORM/SANITARY SEWER CROSSING.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION AS-BUILTS TO SERVICE LOCATIONS, AND ANY WATER MAIN FITTINGS. AS-BUILTS SHALL BE RECORDED IN ACCORDANCE WITH THE OUTLINED PROCEDURES.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING ENGINEER AT LEAST 24 HOURS PRIOR TO STARTING CONSTRUCTION ON ANY PORTION OF THE EXTERIOR WATER OR SANITARY SYSTEMS. THIS NOTIFICATION REQUIREMENT SHALL CONTINUE TO THE COMPLETION OF THE WATER AND SANITARY SYSTEMS.
7. UTILITY TESTING. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SCHEDULING WATER AND SANITARY TESTING, WITH THE ENGINEER AND MUNICIPALITY PUBLIC WORKS, AT A MINIMUM OF 24 HOURS PRIOR TO THE TEST. BASED ON AVAILABILITY OF ENGINEER'S STAFF, THE ENGINEER SHALL ACCOMMODATE THE TESTING SCHEDULE WITHIN 24 HOURS OF THE CONTRACTOR REQUESTED TEST DATE/TIME.
8. THE CONTRACTOR SHALL PRE-TEST WATER FOR 2 HOURS. THE CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY IF PRE-TEST FAILED.
9. THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE ENGINEER IF PRE-SCHEDULED TESTING AND/OR WATER/SEWER CONSTRUCTION IS CANCELED. IF CONTRACTOR DOES NOT CONTACT ENGINEER AND ENGINEER VISITS THE SITE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENGINEER'S FEES/MILEAGE FOR SITE VISIT.
10. THE CONTRACTOR SHALL COORDINATE WATER/SEWER CONSTRUCTION WITH THE MUNICIPALITY. THE CONTRACTOR SHALL LEAVE THRUST BLOCKS AND OTHER REQUIRED SECTIONS OF NEW LINE EXPOSED UNTIL MUNICIPALITY HAS INSPECTED AND APPROVED IT.

HAZELETT
STRIP-CASTING
CORPORATION

COLCHESTER, VT



164 Main Street, Suite 201
Colchester, Vermont 05446
P: (802) 878-0375
www.krebsdandlansing.com

STAMP:

Project:

THE 'H'
AT
MALLETTS BAY

180 & 166 W. Lakeshore Drive
Colchester, Vermont

Project No.	23314
Scale	N.T.S.
Drawn by	SWH
Checked by	
Date	03/03/25

Revisions		
No.	Date	Description

Drawing Title
CIVIL DETAILS

Drawing No.

CD-1


ROAD CONSTRUCTION NOTES

- ALL REFERENCES TO ROAD SHALL APPLY TO PARKING AREAS AS WELL.
- NEW ROAD SHALL BE CONSTRUCTED TO THE LINE AND GRADE SHOWN ON THE DRAWINGS. THE ROAD AND UTILITY LOCATIONS SHALL BE AS TYPICALLY DETAILED UNLESS OTHERWISE SHOWN.
- ALL ROAD AND PARKING CONSTRUCTION SHALL BE COMPLETED IN ACCORDANCE WITH THE VERMONT AGENCY OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION" 2018, HEREAFTER CALLED VERMONT HIGHWAY SPECIFICATIONS, SPECIFICATIONS FOUND ON THESE PLANS, AND CITY/TOWN SPECIFICATIONS. IN CASE OF CONFLICT, THE MORE STRINGENT SPECIFICATION SHALL APPLY AS DETERMINED BY THE ENGINEER. ALL GRAVEL AND STORM SEWER STRUCTURES SHALL BE APPROVED BY TOWN ENGINEER.
- THE CONTRACTOR SHALL FOLLOW VERMONT HIGHWAY SPECIFICATIONS (2018) SECTION 203.11 FOR PLACING AND SPREADING EMBANKMENTS.
- FILL MATERIAL FOR ROAD EMBANKMENT SHALL BE APPROVED BY THE ENGINEER. FILL SHALL BE PLACED IN 12" LIFTS, WETTED AND COMPACTED WITH SATISFACTORY COMPACTION EQUIPMENT TO 95% OF MAXIMUM DENSITY (STANDARD PROCTOR).
- ROAD IN FILL SECTIONS SHALL BE PLACED AND COMPACTED A MINIMUM OF 3 FEET ABOVE TOP OF ANY UTILITY TO BE INSTALLED BEFORE TRENCH IS EXCAVATED FOR PIPE PLACEMENT. IN TRENCHES AND CUT SECTIONS, THE CONTRACTOR SHALL PROVIDE ALL NECESSARY SHEETING, SHORING AND BRACING TO MAINTAIN COMPLIANCE WITH ALL OSHA/VOSHA REGULATIONS.
- METHODS FOR CONSTRUCTION OF SUBGRADE SHALL CONFORM TO VERMONT HIGHWAY SPECIFICATIONS (2018) 203.12 OR AS DETERMINED BY THE ENGINEER.
- ANY SUBGRADE OR SUBBASE DISTURBED BY CONTRACTOR, OR RENDERED UNSUITABLE BY CONSTRUCTION MACHINERY, SHALL BE REMOVED AND REPLACED WITH APPROVED GRANULAR BACKFILL AT THE CONTRACTOR'S EXPENSE. THE SUBGRADE SHALL BE COMPACTED TO ATTAIN AT LEAST 95% OF THE MAXIMUM DENSITY (STANDARD PROCTOR)

BEFORE PLACING ROAD OR EMBANKMENT MATERIALS.


- THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION OF COMPACTION IN THE ROAD AND UTILITY TRENCHES.
- SAND FILL SHALL CONFORM TO VERMONT HIGHWAY SPECIFICATIONS (2018) 703.03, TABLE 703.03A. GRANULAR BORROW SHALL CONFORM TO THE VERMONT HIGHWAY SPECIFICATIONS 703.04 GRANULAR BORROW, TABLE 703.04A.
- GRAVEL SUBBASE FOR PAVEMENT SHALL CONFORM TO VERMONT HIGHWAY SPECIFICATIONS (2018) 704.05, TABLE 704.05A, COARSE.
- LEVELING COURSE SHALL CONFORM TO VERMONT HIGHWAY SPECIFICATIONS (2018) 704.05, TABLE 704.05A, FINE. SHOULDERS SHALL CONFORM TO SECTION 704.12, AGGREGATE FOR SHOULDERS.
- BITUMINOUS CONCRETE PAVEMENT SHALL CONFORM TO VERMONT HIGHWAY SPECIFICATIONS (2018) SECTION 404 AND 406. BINDER COURSE SHALL BE TYPE II, AND FINISH WEARING COURSE SHALL BE TYPE III OR IV. BASE COURSE PAVING TO BE PLACED FIRST YEAR, SURFACE COURSE TO BE PLACED THE SECOND OR THIRD YEAR, DETERMINED BY THE ENGINEER.
- EMBANKMENT FILL FOR ROAD AND PARKING SHALL BE A SIEVE SPECIFICATION AS FOLLOWS:

SIEVE	% FINER
4"	100
2"	85-100
4	60-100
200	12 MAXIMUM
- IF PROOF ROLL FAILS, CONTRACTOR SHALL REMOVE THE SITE SOIL AND REPLACE IT WITH SAND WITH THE ABOVE SPEC. UNTIL A PROOF ROLE CAN BE PLACED WITHOUT FAILING. ENGINEER WILL JUDGE PASS/FAILURE OF PROOF ROLE, THIS WILL BE PERFORMED WITHOUT FURTHER COSTS TO THE OWNER.



NOTES


- SET UP AND MAINTAIN SIGNS AND OTHER SAFETY CONTROL DEVICES.
- RESHAPE HOLE PATCH AREA BY CUTTING WITH A CONCRETE SAW INTO SQUARE OR RECTANGULAR SHAPE AND CUT SIDE FACED VERTICALLY. RESHAPE DOWNWARD SOLID MATERIAL AND AROUND HOLE TO SOUND PAVEMENT.
- BACKFILL TRENCH IN 6" LIFTS AND COMPACT EACH TO 95% OF MAXIMUM DENSITY OF OPTIMUM MOISTURE CONTENT AS DETERMINED BY ASTM D698 STANDARD PROCTOR.
- REMOVE ALL LOOSE MATERIAL AND THOROUGHLY SWEEP THE HOLE AREA, CLEAN ANY MUD AND STANDING WATER.
- APPLY LIQUID ASPHALT TRACK TO VERTICAL FACES IN UNIFORM MANNER. DO NOT PUDDLE TRACK COAT ON BOTTOM HOLE.
- FILL TOP OF HOLE WITH TYPE IV BITUMINOUS CONCRETE AND COMPACT IN LIFTS NO MORE THAN 2" THICK. EACH LIFT SHOULD BE THOROUGHLY COMPACTED WITH A VIBRATORY PLAT COMPACTOR OR A PORTABLE ROLLER. EXPERIENCE HAS SHOWN THAT 15 TO 20 PASSES WITH THE VIBRATORY ROLLER AND MIX TEMPERATURE ABOVE 250 F (121 C) ARE NECESSARY TO ENSURE GOOD COMPACTION. HAND TAMP SHOULD ONLY BE USED FOR SMALL AREAS LESS THAN 1 S.F.
- CLEAN UP AREA. DO NOT LEAVE EXCESS FILL OR EXCAVATED MATERIAL ON THE PAVEMENT. REMOVE SAFETY SIGNS.



NEW CONCRETE CONSTRUCTION JOINT/CONTROL JOINT DETAIL

N.T.S.

WHEN IN THE TOWN RIGHT OF WAY (R.O.W.), CONTRACTOR SHALL BE NOTIFY THE TOWN 48 HOURS BEFORE THE WORK IS PLANNED TO BEGIN. ALL DETAILS ARE SUBJECT TO THE MOST RECENT REVISION OF THE TOWN OF COLCHESTER DPW STANDARDS AND SPECIFICATIONS. THE MOST STRINGENT DETAILS WILL APPLY.



GRAVEL NOTES

- THE CONTRACTOR TO TAKE SIEVE ANALYSIS OF GRAVEL AS SOON IT ARRIVES ON SITE.
- TRAVEL OVER GRAVEL WITH ANY VEHICLE TRACKING SOIL PRIOR TO PLACEMENT OF PAVEMENT IS PROHIBITED.
- IF GRAVEL IS CONTAMINATED AFTER PLACEMENT, THE SITE CONTRACTOR SHALL BE RESPONSIBLE REMOVAL OF ALL CONTAMINATED GRAVEL AND PAYING FOR ALL RECOMMENDED SIEVE ANALYSIS AS DETERMINED BY THE ENGINEER.

NOTES FOR CONCRETE CURB

- BROOM FINISH CONCRETE, ALL JOINTS TO BE TOOL FINISHED, EXPANSION/CONTRACTION JOINTS EVERY 20' WITH 1/2" JOINT FILLER, SCORE 1/3 TOTAL DEPTH AT 10' INTERVALS
- APPLY 2 COATS OF SPECHEM CURESHIELD CURE/SEAL COMPOUND TO ALL CONCRETE SURFACES, PER THE MANUFACTURER'S SPECIFICATIONS.
- CONCRETE MAY NOT BE POURED IF FROST IS PRESENT OR THAWING IN THE SUBGRADE, IF THE TEMPERATURE IS 40 F OR LESS, OR DURING UNSEASONABLE WEATHER CONDITIONS.
- CONCRETE CURB RADII LESS THAN 200 FT SHALL BE FORMED WITH FLEXIBLE FORMS. ALL


- CONCRETE USED IN THE CONSTRUCTION OF CONCRETE CURB SHALL BE AIR ENTRAINED AND MADE WITH PORTLAND CEMENT. THE CONCRETE SHALL MEET SECTION 541 OF THE STATE OF VERMONT STANDARD SPECIFICATION FOR CLASS A CONCRETE AND HAVE 28 DAY COMPRESSIVE STRENGTH OF 4,000 PSI.
- JOINT FILLER SHALL BE RESILIENT NON-EXTRUDING CELLULAR FIBER JOINT, UNIFORMLY SATURATED WITH ASPHALT, OFFERING A MINIMUM OF 70% RECOVERY AFTER COMPRESSION.
 - THE ENGINEER SHALL BE CONTACTED AT LEAST 24 HOURS PRIOR TO FORMING CONCRETE CURB TO REVIEW LAYOUT.

PAVEMENT MARKING NOTES

- TYPICAL TOWN OF BOLTON PARKING SPACE IS 9'-0" CENTER OF LINE TO CENTER OF LINE MARKED WITH 4" WIDE YELLOW OR WHITE PAINT.
- ADA SPACE IS YELLOW/WHITE STENCIL, YELLOW/WHITE TRIM. COORDINATE EXACT REQUIREMENTS WITH TOWN OF BOLTON.
- PAINT FOR PAVEMENT MARKINGS SHALL BE HYDROPHAST WATERBORNE TRAFFIC PAINT BY FRANKLIN PAINT COMPANY. IT SHALL BE REFLECTIVE, VOC COMPLIANT FAST DRYING, 100% ACRYLIC WATERBORNE TRAFFIC PAINT. PAINT FOR STOP BARS AND CROSSWALKS SHALL BE WHITE ALL OTHER LINE STRIPING SHALL BE YELLOW. CONFIRM PAINT COLOR WITH TOWN OF BOLTON AND OWNER.
- TRAFFIC PAINT SHALL BE APPLIED WITH A UNIFORM THICKNESS AND AT A RATE SUCH THAT NO PAVEMENT IS VISIBLE AFTER DRYING. ADDITIONAL PAINT APPLICATION WILL BE REQUIRED IF UNDERLYING PAVEMENT IS VISIBLE.

TYPICAL ROAD CROSS SECTION DETAILS - WITH CONCRETE CURBS AND WITHOUT CURBS

N.T.S.




NOTES

- TYPICAL GRASS SWALE CROSS SECTION. SEE PLAN VIEW FOR LOCATIONS.
- SWALE TO HAVE 2' WIDE FLAT BOTTOM OR WIDER. TYPICAL SIDE SLOPES TO BE 2:1.
- APPLY SEED AND MULCH. APPLY UNIFORMLY OVER AREA.
- CROSS-SECTION SHALL BE EXCAVATED TO NEAT LINES AND GRADES. OVER-EXCAVATED AREAS SHALL BE BACKFILLED WITH MOIST SOIL COMPACTED TO DENSITY OF SURROUNDING MATERIAL.
- ALL EARTH REMOVED AND NOT NEEDED IN CONSTRUCTION SHALL BE SPREAD OR DISPOSED OF IN APPROVED UPLAND AREA (PER OSPC) SUCH THAT IT DOES NOT INTERFERE WITH FUNCTIONING OF SWALE. ALL EXCAVATED SOIL SHALL REMAIN ON SITE.

GRASS SWALE CROSS SECTION

N.T.S.



NOTES

- STONE-LINED SWALES TO BE USED ON SLOPES _5% DESIGNED FOR VELOCITIES LESS THAN 10 FEET PER SECOND.
- USE RIP RAP STONE. PROVIDE QUARRY GRADATION TO ENGINEER FOR APPROVAL.
- SIDE SLOPES NOT TO EXCEED 2:1.
- STONE LINING THICKNESS SHALL BE 1.5 X MAX. STONE SIZE PLUS THE THICKNESS OF FILTER OR BEDDING.
- ALL DISTURBED AREAS SHALL BE STABILIZED AND OTHERWISE PROTECTED AGAINST SOIL EROSION.

STONE SWALE CROSS SECTION

N.T.S.

HAZELETT STRIP-CASTING CORPORATION

COLCHESTER, VT



164 Main Street, Suite 201
Colchester, Vermont 05446

P: (802) 878-0375
www.krebsandlansing.com

STAMP:

Project:

THE 'H' AT MALLETT'S BAY

180 & 166 W. Lakeshore Drive
Colchester, Vermont

Project No.

23314

Scale

N.T.S.

Drawn by

SWH

Checked by

Date

03/03/25

Revisions

No. Date Description

Drawing Title

CIVIL DETAILS

Drawing No.

CD-3

THE PIPE AND FITTINGS FOR SANITARY SEWER SHALL MEET THE REQUIREMENTS OF ASTM SPECIFICATION D3034 FOR 4" - 15" SDR 35 AND F679 FOR 18" - 27". ALL PIPE SHALL BE LAID TO THE LINE AND GRADE SHOWN ON THE PLANS.

THE PIPE FOR GRAVITY SANITARY SEWER SHALL BE AS SHOWN ON THE PLANS AND DETAILED BELOW:

- ALL PIPE SHALL BE LAID TO THE LINE AND GRADE AS SHOWN ON THE PLANS.
- PVC SDR 35 - POLYVINYL CHLORIDE PIPE - PIPE SHALL CONFORM TO ASTM SPECIFICATION D-3034 OR F679, (PVC) SEWER PIPE AND FITTINGS, SDR35.
- PIPE WITH RECYCLED CONTENT IS NOT ACCEPTABLE.

PVC SDR 35 SANITARY AND STORM PIPES SHALL BE INSTALLED SO THAT THE INITIAL DEFLECTION SHALL BE LESS THAN 5%.

PVC SDR 35 PIPE SHALL NOT BE INSTALLED WHEN THE TEMPERATURE DROPS BELOW 32 °F OR GOES ABOVE 100 °F UNLESS PRIOR APPROVAL IS OBTAINED FROM THE ENGINEER. EXTRA CARE IS REQUIRED WHEN HANDLING PVC PIPE DURING COLD WEATHER. PVC PIPE SHALL NOT BE STORED OUTSIDE AND EXPOSED TO PROLONGED PERIODS OF SUNLIGHT AS PIPE DISCOLORATION AND REDUCTION IN PIPE IMPACT STRENGTH WILL OCCUR. IF PVC PIPE IS TO BE STORED ON SITE FOR 1 MONTH OR LONGER IT SHALL BE COVERED WITH CANVAS OR OTHER OPAQUE MATERIAL.

THE INSTALLED GRAVITY SANITARY SEWER PIPE SHALL BE LOW PRESSURE AIR TESTED IN THE PRESENCE OF THE ENGINEER. AFTER CLEANING THE PIPE, THE PIPE SECTION (MANHOLE TO MANHOLE) SHALL BE TESTED ACCORDING TO THE PROCEDURES OUTLINED IN THE STATE OF VERMONT WASTEWATER SYSTEM AND POTABLE WATER SUPPLY RULES, EFFECTIVE APRIL 12, 2019.

UPON COMPLETION OF CONSTRUCTION OF A FORCE MAIN, THE LINE SHALL BE PRESSURE AND LEAKAGE TESTED IN ACCORDANCE WITH THE FOLLOWING PROCEDURE.

AFTER THE PIPE HAS BEEN LAID, ALL NEWLY LAID PIPE OR ANY VALVED SECTION THEREOF SHALL BE SUBJECTED TO A HYDROSTATIC PRESSURE OF AT LEAST 1.5 X THE HIGHEST WORKING PRESSURE IN THE SECTION.

- TEST PRESSURE RESTRICTIONS. TEST PRESSURE SHALL:
 - 1. NOT BE LESS THAN 50 PSI AT THE HIGHEST POINT ALONG THE TEST SECTION.
 - 2. NOT EXCEED PIPE OR THRUST RESTRAINT DESIGN PRESSURES.
 - 3. BE AT LEAST 2 HOURS IN DURATION.
 - 4. NOT VARY BY MORE THAN 5 PSI
 - 5. NOT EXCEED TWICE THE RATED PRESSURE OF THE VALVES WHEN PRESSURE BOUNDARY OF THE TEST SECTION INCLUDES CLOSED GATE VALVES.

PRESSURIZATION. EACH VALVED SECTION OF PIPE SHALL BE FILLED WITH WATER SLOWLY AND THE SPECIFIED TEST PRESSURE, BASED ON THE ELEVATION OF THE LOWEST POINT OF THE LINE OR SECTION UNDER TEST AND CORRECTED TO THE ELEVATION OF THE TEST GAUGE, SHALL BE APPLIED BY MEANS OF A PUMP CONNECTED TO THE PIPE.

AIR REMOVAL. BEFORE APPLYING THE SPECIFIED TEST PRESSURE, AIR SHALL BE EXPELLED COMPLETELY FROM THE PIPE AND VALVES.

EXAMINATION ALL EXPOSED PIPE, FITTINGS, VALVES, AND JOINTS SHALL BE EXAMINED CAREFULLY DURING THE TEST. ANY DAMAGED OR DEFECTIVE PIPE, FITTINGS, OR VALVES, THAT ARE DISCOVERED FOLLOWING THE PRESSURE TEST SHALL BE REPAIRED OR REPLACED WITH SOUND MATERIAL AND THE TEST SHALL BE REPEATED.

A LEAKAGE TEST SHALL BE CONDUCTED CONCURRENTLY WITH THE PRESSURE TEST.

LEAKAGE DEFINED, LEAKAGE SHALL BE DEFINED AS THE QUANTITY OF WATER THAT MUST BE SUPPLIED INTO THE NEWLY LAID PIPE, OR ANY VALVED SECTION THEREOF, TO MAINTAIN PRESSURE WITHIN 5 PSI OF THE SPECIFIED TEST PRESSURE AFTER THE AIR IN THE PIPELINE HAS BEEN EXPELLED AND THE PIPE HAS BEEN FILLED WITH WATER.

ALLOWABLE LEAKAGE. NO PIPE INSTALLATION WILL BE ACCEPTED IF LEAKAGE IS GREATER THAN THAT DETERMINED BY THE FOLLOWING FORMULA:

L IS THE ALLOWABLE LEAKAGE, IN GALLONS PER HOUR; N IS THE NUMBER OF JOINTS IN THE LENGTH OF PIPELINE TESTED; D IS THE NOMINAL DIAMETER OF THE PIPE, IN INCHES; AND P IS THE AVERAGE TEST PRESSURE DURING THE LEAKAGE TEST, IN POUNDS PER SQUARE INCH GAGE.

SECTIONS WHICH FAIL THE PRESSURE/LEAKAGE TEST SHALL BE REPAIRED AND RETESTED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER.

- ALL SEWER LINES (MAIN LINES AND SERVICES) AND MANHOLES SHALL BE THOROUGHLY TESTED BY THE CONTRACTOR IN ACCORDANCE WITH THE ENVIRONMENTAL PROTECTION RULES (09/29/07).
- ALL GRAVITY SANITARY MAINS SHALL BE AIR TESTED IN THE PRESENCE OF THE ENGINEER. AT A MINIMUM, THE TEST PRESSURE SHALL BE 4 POUNDS PER SQUARE INCH AT THE HIGHEST POINT ALONG THE TEST FOR 4 MINUTES.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE ENGINEER AND THE LOCAL MUNICIPALITY PUBLIC WORKS DEPARTMENT AT LEAST 24 HOURS PRIOR TO STARTING CONSTRUCTION ON ANY PORTION OF THE PUBLIC CONNECTIONS TO WATER OR SANITARY SYSTEMS. THIS NOTIFICATION REQUIREMENT SHALL CONTINUE TO THE COMPLETION OF THE SANITARY SYSTEMS.
- THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE ENGINEER IF PRE-SCHEDULED TESTING AND/OR SEWER CONSTRUCTION IS CANCELED. IF CONTRACTOR DOES NOT CONTACT ENGINEER AND ENGINEER VISITS THE SITE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENGINEER'S FEES/MILEAGE FOR SITE VISIT.
- MAINTAIN A MINIMUM OF 18" VERTICAL SEPARATION BETWEEN WATER MAIN AND STORM/SANITARY SEWER CROSSING.
- UTILITY TESTING. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SCHEDULING SANITARY TESTING AT A MINIMUM OF 24 HOURS PRIOR TO THE TEST. BASED ON AVAILABILITY OF ENGINEER'S STAFF, THE ENGINEER SHALL ACCOMMODATE THE TESTING SCHEDULE WITHIN 24 HOURS OF THE CONTRACTOR REQUESTED TEST DATE/TIME.
- THE CONTRACTOR SHALL PRE-TEST UTILITY PIPING PRIOR TO CONTACTING THE ENGINEER. THE CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY IF PRE-TEST FAILED.

EXISTING ALLOCATION = 4,482 GALLONS/DAY (GPD)
(PER WW-C0671 FOR A 166 SEAT RESTAURANT SERVING 2 MEALS/DAY))

$$48 \text{ SEATS} \times 27 \text{ GPD (2 MEALS/DAY)} = 1296 \text{ GPD}$$

60 PARTICIPANTS X 4 GPD/PARTICIPANT = 240 GPD


1 MASSAGE THERAPIST X 32 GPD = 32 GPD

MAIN BUILDING


46 TOTAL SLEEPING SPACES X 50 GPD = 2300 GPD

6 SLEEPING SPACES X 50 GPD = 300 GPD

TOTAL PROPOSED DESIGN FLOW = 4,340 GPD



COLCHESTER, VT



STAMP:

Project:

180 & 166 W. Lakeshore Drive
Colchester, Vermont


Revisions		
No.	Date	Description

Drawing Title

CIVIL DETAILS

Drawing No

CD-4



PUMP STATION DESIGN CRITERIA

The wastewater disposal system is designed for domestic sanitary waste only for 4,340 gallons per day.

Design Flow = 4,340 gallons/day

Use dupe pumps in 8 foot diameter wetwell.

Volume of wetwell per foot = 376 gallons/foot

Dose of 32 cycles/day for 30 min. retention time based on 16 hour day

Volume of minimum dose = 4,340 gallons/32 cycles = 135.6 gallons/cycle

Height of pump cycle = $\frac{135.6 \text{ gallons/cycle}}{376 \text{ gallons/foot}} = 0.36 \text{ feet/cycle}$


Provide 0.4 feet/cycle

SYSTEM CURVE FOR PUMP SELECTION						
FLOWRATE (GPM)	VELOCITY (FT/SEC)	STATIC HEAD (FT)	FRICTION LOSS (FT)	MINOR LOSS (FT)	DISCHARGE HEAD (FT)	TOTAL DYNAMIC HEAD (FT)
60	2.38	20.0	1.69	10.0	2.31	34.0
75	2.97	20.0	2.57	10.0	2.31	34.9
90	3.57	20.0	3.61	10.0	2.31	35.9

- PUMP SPECIFICATIONS**
- DIAMETER OF FORCE MAIN = 3 INCH
 - LENGTH OF FORCE MAIN = ±260 FEET

STATIC HEAD = 20± FEET
PRESSURE HEAD TO BE MAINTAINED = 2.3 FEET
MINOR LOSSES FOR ALL FIXTURES AND FITTINGS = 10.0 FEET


- CONTROL PANEL REQUIREMENTS:**
- PANELS SHALL BE NEMA 4 (LOCKABLE) AND HOLDING TANK PANELS SHALL BE EXPLOSION PROOF.
 - TANK PANEL SHALL INCLUDE (AT A MINIMUM) THE FOLLOWING EQUIPMENT:
 - FUSED DISCONNECT FOR MAIN POWER FEED
 - INDIVIDUAL CIRCUIT BREAKERS
 - UL508 STAMP AND APPROVAL
 - INTRINSICALLY SAFE RELAYS
 - AUXILIARY CONTACTS TO CONNECT TO SECURITY SYSTEM
 - AUTO DIALER FUNCTION
 - AUDIBLE ALARM AND THREE LIGHTS ON TOP OF CONTROL PANEL
 - YELLOW LIGHT FOR 75% FULL - LIGHT FLASHES ON ELECTRIC PANEL TO INDICATE TANK IS 75% FULL
 - RED LIGHT - AUDIBLE ALARM AND RED LIGHT FLASHES TO INDICATE THE TANK IS FULL.
 - COORDINATE WITH ELECTRICIAN TO VERIFY ELECTRIC SERVICE.
 - CONTROL PANEL AND FLOAT CONTROL ALARM SYSTEM SHALL BE TESTED IN THE PRESENCE OF THE OWNER'S REPRESENTATIVE TO DEMONSTRATE THAT ALL EQUIPMENT IS FULLY OPERATIONAL



- ELECTRICAL REQUIREMENTS:**
- ALL MATERIALS AND EQUIPMENT SHALL MEET THE STANDARDS OF THE NATIONAL ELECTRICAL MANUFACTURER'S ASSOCIATION AND UNDERWRITERS LABORATORIES, INC., AND SHALL BEAR THEIR LABEL WHEREVER STANDARDS HAVE BEEN ESTABLISHED AND LABEL SERVICE IS AVAILABLE.
 - INSTALLATION OF ELECTRIC SYSTEMS AND CONTROLS SHALL BE IN CONFORMANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRIC CODE, LOCAL ORDINANCES AND REGULATIONS PRESCRIBED BY THE LOCAL POWER COMPANY.
 - ALL ELECTRICAL COMPONENTS FOR THE HOLDING TANK SHALL MEET CLASS I, DIVISION 1, GROUP C & D EXPLOSION PROOF REQUIREMENTS.
 - COMPLETED ELECTRIC WORK PERFORMED SHALL COMPLY WITH THE LATEST EDITION OF THE NATIONAL ELECTRIC CODE UNDERWRITERS LABORATORIES REGULATIONS AND ALL MUNICIPAL, STATE AND OTHER PUBLIC OR PRIVATE AUTHORITIES HAVING JURISDICTION. THE CONTRACTOR IS RESPONSIBLE FOR ACQUIRING ALL NECESSARY PERMITS. ALL EQUIPMENT AND WORKMANSHIP SHALL BE GUARANTEED TO BE FREE FROM MECHANICAL AND ELECTRICAL DEFECTS FOR A PERIOD OF ONE YEAR FROM THE DAY OF FINAL ACCEPTANCE. ANY REPLACEMENT OF PARTS OR ADJUSTMENTS, INCLUDING LABOR MADE NECESSARY BY SUCH DEFECTS AND ADJUSTMENTS, SHALL BE RECTIFIED WITHOUT COST TO THE OWNER.
 - ALL WIRES SHALL MEET THE REQUIREMENTS OF THE NATIONAL ELECTRIC CODE AND SHALL BE COLOR-CODED AS INDICATED ON THE WIRING DIAGRAM. ALL WIRING OUTSIDE THE PANEL SHALL BE IN CONDUIT, ALL CONDUIT FOR HOLDING TANKS SHALL MEET CLASS 1, DIVISION 1, GROUP C & D EXPLOSION PROOF REQUIREMENTS.

ELECTRIC SERVICE DETAIL FOR NEW PUMP STATION

N.T.S.



Emergency Storage Calculations

Minimum volume of emergency storage using Design Flow and 16 hour delivery:

Volume = $\frac{4,340 \text{ gallons/day}}{16 \text{ hours/day}} \times 4 \text{ hours} = 1,085 \text{ gallons}$

Emergency storage will be in Pump Station

Height of emergency storage required in wet well = 1,085 gal

Volume of wetwell per foot = 376 gallons/foot

3' of emergency storage in wet well = $3' \times 376 \text{ gal/ft} = 1,128 \text{ gallons}$

Total Emergency Storage Provided = 1,128gal

NOTES

- THE STRUCTURE IS TO BE A PACKAGE PUMP STATION W/ EXTERIOR VALVE VAULT. PLANS FOR THE PUMP STATION SHALL BE APPROVED BY THE ENGINEER PRIOR TO CONSTRUCTION.
- THE SUBMERSIBLE PUMPS SHALL BE ASSEMBLED AND TESTED AT THE FACTORY.
- THE CONTRACTOR SHALL PROVIDE THE DESIGN FOR FLOATION PREVENTION, APPROVED BY THE ENGINEER, PRIOR TO CONSTRUCTION.
- THE STATION SHALL INCLUDE ALL NECESSARY CONTROLS, ALARMS, SWITCHES, FITTINGS, POWER SERVICE, AND SUPPLY ALL APPURTENANCES NECESSARY TO MAKE THE STATION COMPLETE AND OPERABLE.
- ALL ELECTRICAL EQUIPMENT SHALL COMPLY WITH LOCAL AND NATIONAL ELECTRICAL CODE REQUIREMENTS.
- ANY MODIFICATIONS TO PUMP STATION DESIGN OR LOCATION MUST BE APPROVED BY THE ENGINEER AND OTHER PERMITTING AUTHORITIES.
- THE CONTRACTOR SHALL USE SCHEDULE 80 PVC WITH SOLVENT WELD JOINTS FOR ALL PIPING INSIDE PUMP STATION AND VALVE PIT. ALL PENETRATIONS AND JOINTS SHALL HAVE WATERTIGHT SEALS.

PUMP STATION TESTING NOTES

THE CONTRACTOR SHALL TEST BOTH THE PUMP STATION WETWELL AND THE VALVE PIT FOR WATERTIGHTNESS PRIOR TO BACKFILL. THE WATERTIGHTNESS TEST SHALL CONFORM TO THE ENVIRONMENTAL PROTECTION RULES, CHAPTER 1, WASTEWATER SYSTEM AND POTABLE WATER SUPPLY (CURRENT EDITION) SECTION 1-1010. THIS TEST SHALL BE WITNESSED BY THE ENGINEER AND SHALL BE PERFORMED AS FOLLOWS:

- AFTER THE STRUCTURE HAS BEEN ASSEMBLED IN PLACE, ALL LIFTING HOLES AND EXTERIOR JOINTS SHALL BE FILLED AND POINTED WITH AN APPROVED NON-SHRINKING MORTAR. ALL PIPES AND OTHER OPENINGS INTO THE STRUCTURE SHALL BE SUITABLY PLUGGED AND THE PLUGS PLACED TO PREVENT BLOWOUT.
- 1-1010(b) When required to be tested for watertightness by a permit, tanks shall be tested using the ASTM for testing of tanks or the following:
 - For concrete tanks, complete one of the following tests:
 - Using a water pressure test, seal the tank and risers, fill with water to the top of the risers, and let stand for 24 hours. Refill the tank. The tank is considered watertight if the water level is held for 1 hour.
 - Using a vacuum test, seal the empty tank and risers and apply a vacuum to 2 inches (50 mm) of mercury. The tank is considered watertight if 90 percent of the vacuum is held for 2 minutes.
- IF THE STRUCTURE FAILS THE TEST IT SHALL BE THOROUGHLY CLEANED AND RESEALED, FROM THE OUTSIDE, AND RETESTED AT THE CONTRACTORS EXPENSE.

PUMP STATION MAINTENANCE NOTES

- AT LEAST ONCE A YEAR THE PUMP STATION AND TANKS SHOULD BE OPENED AND SETTLED SOLIDS REMOVED AS NECESSARY AND CHECKED FOR LEVELNESS. THOROUGHLY CLEAN ANY COMPONENTS WITH SOLIDS BUILDUP AND CHECK FOR SOURCE OF SOLIDS.
- TOXIC OR HAZARDOUS MATERIALS SHOULD, IN GENERAL, NOT BE DISPOSED OF IN SEPTIC SYSTEMS. THESE SUBSTANCES MAY PASS THROUGH THE SYSTEM IN AN UNALTERED STATE AND CONTAMINATE GROUNDWATER OR REMAIN IN THE SEPTAGE AND SUBSEQUENTLY CONTAMINATE THE SOIL.
- A CONTINUOUS LOG OF INSPECTIONS AND OBSERVATIONS SHALL BE KEPT. THE LOG SHALL NOTE ALL CLEANING AND OTHER REQUIRED MAINTENANCE.

**HAZELETT
STRIP-CASTING
CORPORATION**

COLCHESTER, VT



164 Main Street, Suite 201
Colchester, Vermont 05446
P: (802) 878-0375
www.krebsandlansing.com

STAMP:

Project:

**THE 'H'
AT
MALLETTS BAY**

180 & 166 W. Lakeshore Drive
Colchester, Vermont


Project No.	23314
Scale	N.T.S.
Drawn by	SWH
Checked by	
Date	03/03/25

Revisions		
No.	Date	Description

Drawing Title
CIVIL DETAILS


Drawing No.

CD-5




GRAVEL WETLAND DETAIL
N.T.S.


Gravel Wetland Elevation Schedule					
Gravel Wetland	Bottom of Pond & Top of Wetland Cell Elev. (ft) (ELEV. XX in Detail)	Planned Static Water Elev. (ft)	Top Smaller Stone Elev. (ft)	Transition from Small to Large Stone Elev. (ft)	Bottom of Stone & Bottom of Gravel Cell Elev. (ft)
1	126.00	125.67	125.33	125.00	122.33




GRAVEL WETLAND CLEANOUT DETAIL
N.T.S.



STORM TRENCH DETAIL
N.T.S.



HDPE END SECTION DETAIL
N.T.S.



STORMWATER OUTFALL DETAIL
N.T.S.

GRAVEL WETLAND PLANTING SOIL CHARACTERISTICS

PARAMETER	VALUE
PH RANGE	6.0 to 7.0
SOIL (LOW HYDRAULIC CONDUCTIVITY (0.1-0.01 FT/DAY) WITH SOIL TEXTURE CONFORMING TO HYDROLOGIC SOIL GROUP D.)	
SIEVE SIZE	PERCENT PASSING BY WEIGHT
NO. 16	100%
NO. 40	85-100%
NO. 60	40-60%
NO. 200	5-10%

GRAVEL WETLAND SOIL SHALL CONFORM TO THE "BIORETENTION AND GRAVEL WETLAND SOIL MEDIA TESTING GUIDANCE" DOCUMENT PREPARED BY THE UNIVERSITY OF VERMONT, SEA GRANT LAKE CHAMPLAIN, AND WATERSHED CONSULTING

- THE GRAVEL WETLAND SOIL SHALL BE TESTED IN ACCORDANCE WITH THE PHOSPHORUS TESTING PROCEDURE BELOW. PHOSPHORUS TESTING IS REQUIRED FOR THE UPPER MEDIA LAYER OF THE GRAVEL WETLAND SOIL. FINAL MIXES MUST HAVE A PHOSPHORUS SATURATION RATIO (PSR) LESS THAN OR EQUAL TO 0.10 AND SHALL BE TESTED IN ACCORDANCE WITH THE FOLLOWING PROTOCOL:
1. SAMPLES ARE TO BE AIR DRIED AND SIEVED THROUGH 2MM PRIOR TO TESTING.
 2. AIR-DRIED, SIEVED SOIL SAMPLES ARE TO THEN BE EXTRACTED WITH THE MEHLICH-3 SOLUTION (0.2 M CH₃COOH, 0.25 M NH₄NO₃, 0.015 M HNO₃, 0.001 M EDTA) BY SHAKING A SOIL-SOLUTION SUSPENSION FOR 5 MINUTES AT A 1:10 RATIO (SOIL MASS IN GRAMS: SOLUTION VOLUME IN ML), FOLLOWED BY FILTERING TO REMOVE PARTICLES (PORE SIZE OF 2 UM IS RECOMMENDED, MAX PORE SIZE = 8 UM).
 3. EXTRACTS FROM THE MEHLICH-3 PROCEDURE ARE TO BE ANALYZED FOR P, FE, AND AL BY ICP-OES.
 4. THE PHOSPHORUS SATURATION RATIO (PSR) IS CALCULATED AS FOLLOWS:

$$PSR = \frac{\left(\frac{P_{M3}}{31}\right)}{\left(\frac{Fe_{M3}}{56}\right) + \left(\frac{Al_{M3}}{27}\right)}$$

WHERE,


- P_{M3} = MEHLICH-3 P IN MG P PER KG DRY SOIL
- Fe_{M3} = MEHLICH-3 FE IN MG FE PER KG DRY SOIL
- Al_{M3} = MEHLICH-3 AL IN MG AL PER KG DRY SOIL

MEHLICH-3 EXTRACTIONS FOLLOW THE ABOVE PROTOCOL. OTHER SOIL EXTRACTIONS, OR EXTRACTIONS USED TO QUANTIFY TOTAL ELEMENTS, ARE NOT ACCEPTABLE FOR THIS REQUIREMENT.

IN CASES WHERE INGREDIENT MIXING HAS NOT YET OCCURRED, INGREDIENTS CAN BE MIXED AT THE INTENDED VOLUMETRIC PROPORTIONS IN A SMALL BATCH (AT LEAST ONE QUART IN VOLUME) FOR TESTING PURPOSES. IF THIS SMALL BATCH TESTING APPROACH IS TAKEN, THE FINAL MATERIAL TO BE USED DURING INSTALLATION MUST BE RETESTED TO CONFIRM ACCEPTABLE PSR.

SOIL SAMPLES FOR P, FE, AND AL ANALYSIS VIA MEHLICH-3 EXTRACTION CAN BE SUBMITTED TO THE AGRICULTURAL AND ENVIRONMENTAL TESTING LABORATORY (AETL) LOCATED AT UVM. PLAN TO ALLOW 3-4 WEEKS FOR ANALYSIS.

HOW TO TAKE A SOIL SAMPLE [GO.UVM.EDU/SOIL-SAMPLING]
SUBMITTING A SOIL SAMPLE [GO.UVM.EDU/UVM-SOIL-LAB]



- NOTES FOR TRASH RACK
1. TRASH RACK TO BE CENTERED OVER OPENING.
 2. STEEL TO CONFORM TO ASTM A-36.
 3. ALL SURFACES TO BE COATED WITH ZRC COLD GALVANIZING COMPOUND AFTER WELDING.
 4. TRASH RACK TO BE FASTENED TO THE WALL WITH 1/2" MASONRY ANCHORS. TRASH RACK TO BE REMOVABLE.

Figure D.1. Trash Rack Protection for Low Flow Orifice

TRASH RACK DETAIL
N.T.S.

HAZELETT
STRIP-CASTING
CORPORATION

COLCHESTER, VT

KREBS & LANSING
CONSULTING ENGINEERS

164 Main Street, Suite 201
Colchester, Vermont 05446

P: (802) 878-0375
www.krebsandlansing.com

STAMP:

Project:
**THE 'H'
AT
MALLETTS BAY**
180 & 166 W. Lakeshore Drive
Colchester, Vermont

Project No. 23314
Scale N.T.S.
Drawn by SWS/SMH
Checked by
Date 02/14/25

Revisions	No.	Date	Description


Drawing Title
CIVIL DETAILS

Drawing No.

CD-6

STORMWATER MAINTANCE NOTES

- A. GRASS-LINED SWALE: LOCATED ALONG ALL DRIVEWAYS.
1. INSPECT REGULARLY FOR ACCUMULATION OF SEDIMENT OR DEBRIS, PARTICULARLY AFTER LARGE STORM EVENTS.
 2. INSPECT AND REPAIR ANY EROSION AND RE-SEED BARE SPOTS AS NEEDED.
 3. REMOVE SEDIMENT AND RESHAPE SWALE WHEN 6 INCHES OF SEDIMENT HAS ACCUMULATED.
- B. GRAVEL WETLANDS:
1. INSPECT FOR PROLONGED STANDING WATER AFTER RAIN EVENTS. INSPECT GRATES AND OBSERVATION PORTS.
 2. INSPECT FOR EROSION, ACCUMULATED SEDIMENT, AND ENSURE PLANTS ARE HEALTHY. REMOVE SEDIMENT AND REPLACE PLANTS AS NECESSARY.
 3. INSPECT OUTLET STRUCTURE TO ENSURE GOOD REPAIR AND NO CLOGGING.
- E. STONE SPLASH PADS/WEIRS: LOCATED AT POND PIPE OUTLETS AND FOREBAY OVERFLOWS INTO GRAVEL WETLANDS.
1. INSPECT REGULARLY FOR SIGNS OF EROSION OR DISPLACEMENT OF STONE. REPAIR AS NEEDED.
 2. INSPECT FOR DEBRIS/TRASH ACCUMULATION AND REMOVE AS NEEDED.
 3. MONITOR FOR EVIDENCE OF CONCENTRATED FLOW CHANNELS OR EROSION AT OUTLET. LEVEL STONE IF NEEDED TO RESTORE EVEN FLOW DISTRIBUTION.



POST-CONSTRUCTION SOIL DEPTH AND QUALITY NOTES

SOIL RETENTION: RETAIN, IN AN UNDISTURBED STATE, THE DUFF LAYER AND NATIVE TOPSOIL TO THE MAXIMUM EXTENT PRACTICABLE.

SOIL QUALITY: ALL AREAS SUBJECT TO THE STANDARD SHALL DEMONSTRATE THE FOLLOWING:

A TOPSOIL LAYER WITH A MINIMUM ORGANIC MATTER CONTENT OF 4% DRY WEIGHT IN PLANTING BEDS AND TURF AREAS. THE TOPSOIL LAYER SHALL HAVE A MINIMUM DEPTH OF 4 INCHES, EXCEPT WHERE TREE ROOTS LIMIT THE DEPTH OF INCORPORATION OF AMENDMENTS NEEDED TO MEET THE CRITERIA.

- COMPOST AND OTHER MATERIALS SHALL BE USED THAT MEET THE FOLLOWING REQUIREMENTS:
- THE COMPOST OR OTHER MATERIALS SHALL HAVE A CARBON TO NITROGEN RATIO BELOW 25:1.
 - COMPOST SHALL MEET THE DEFINITION OF "COMPOST" IN THE AGENCY'S SOLID WASTE MANAGEMENT RULES OR SHALL MEET THE CONTAMINANT STANDARDS IN THE VERMONT SOLID WASTE MANAGEMENT RULES. 6-1104(G)(6-7), 6-1105(E)(6-9), AND 6-1106(E)(7-9). COMPOST OR OTHER ORGANIC MATERIALS MAY BE AMENDED TO MEET THE FOREGOING REQUIREMENTS.
 - EXCEPTIONAL QUALITY BIOSOLIDS (EO BIOSOLIDS) MAY BE USED AS A SOIL AMENDMENT, AT A MAXIMUM PROPORTION OF 35% OF THE TOTAL SOIL VOLUME, AND SHALL BE WELL MIXED WITH EXISTING SOIL BEFORE OR DURING APPLICATION.
 - THE RESULTING SOIL SHALL BE CONDUCIVE TO THE TYPE OF VEGETATION TO BE ESTABLISHED.

THE SOIL QUALITY REQUIREMENTS SHALL BE MET BY USING ONE OR A COMBINATION OF THE FOLLOWING METHODS:


- OPTION 1: LEAVE UNDISTURBED NATIVE VEGETATION AND SOIL, AND PROTECT FROM COMPACTION DURING CONSTRUCTION. FAILURE TO ESTABLISH AND MAINTAIN EXCLUSIONARY CONTROLS AROUND THESE AREAS DURING THE CONSTRUCTION PHASE MAY TRIGGER THE REQUIREMENT TO RESTORE SOILS PER ONE OF THE FOLLOWING OPTIONS.
- OPTION 2: AMEND EXISTING SITE TOPSOIL OR SUBSOIL IN PLACE.
 - a. SCARIFY OR TILL SUBSOILS TO 4 INCHES OF DEPTH OR TO DEPTH NEEDED TO ACHIEVE A TOTAL DEPTH OF 8 INCHES OF UNCOMPACTED SOIL AFTER CALCULATED AMOUNT OF AMENDMENT IS ADDED. EXCEPT FOR WITHIN THE DRIP LINE OF EXISTING TREES, THE ENTIRE SURFACE SHALL BE DISTURBED BY SCARIFICATION;
 - b. AMEND SOIL TO MEET ORGANIC CONTENT REQUIREMENTS:
 1. PRE-APPROVED RATE: PLACE 1 INCH OF COMPOSTED MATERIAL WITH AN ORGANIC MATTER CONTENT BETWEEN 40 AND 65% AND ROTOTILL INTO 3 INCHES OF SOIL, OR
 2. CALCULATED RATE: PLACE CALCULATED AMOUNT OF COMPOSTED MATERIAL OR APPROVED ORGANIC MATERIAL AND ROTOTILL INTO DEPTH OF SOIL NEEDED TO ACHIEVE 4 INCHES OF SETTLED SOIL AT 4% ORGANIC CONTENT. *CONTRACTOR TO PROVIDE CALCULATION AND SITE SKETCH INDICATING AREAS USED FOR CALCULATIONS.
 - c. RAKE BEDS TO SMOOTH AND REMOVE SURFACE ROCKS LARGER THAN 2 INCHES IN DIAMETER; AND
 - d. WATER OR ROLL TO COMPACT SOIL IN TURF AREAS TO 85% OF MAXIMUM DRY DENSITY.
- OPTION 3: REMOVE AND STOCKPILE EXISTING TOPSOIL DURING GRADING.
 - a. STOCKPILE SOIL ON SITE IN A DESIGNATED CONTROLLED AREA, AT LEAST 50 FEET FROM SURFACE WATERS, WETLANDS, FLOODPLAINS, OR OTHER CRITICAL RESOURCE AREAS;
 - b. SCARIFY OR TILL SUBGRADE TO A DEPTH OF 4 INCHES. EXCEPT FOR WITHIN THE DRIP LINE OF EXISTING TREES, THE ENTIRE SURFACE SHALL BE DISTURBED BY SCARIFICATION;
 - c. STOCKPILED TOPSOIL SHALL ALSO BE AMENDED, IF NEEDED, TO MEET THE ORGANIC CONTENT REQUIREMENTS:
 1. PRE-APPROVED RATE: COMPOST SHALL BE INCORPORATED WITH AN ORGANIC MATTER CONTENT BETWEEN 40 AND 65% INTO THE TOPSOIL AT A RATIO 1:3, OR
 2. CALCULATED RATE: INCORPORATE COMPOSTED MATERIAL OR APPROVED ORGANIC MATERIAL AT A CALCULATED RATE TO ACHIEVE 4 INCHES OF SETTLED SOIL AT 4% ORGANIC CONTENT.*
 - d. REPLACE STOCKPILED TOPSOIL PRIOR TO PLANTING, SCREEN TOPSOIL, AND;
 - e. RAKE TO LEVEL, AND REMOVE SURFACE ROCKS LARGER THAN 2 INCHES IN DIAMETER.
 - f. OPTION 4: IMPORT TOPSOIL MIX, OR OTHER MATERIALS FOR MIXING, INCLUDING COMPOST, OF SUFFICIENT ORGANIC CONTENT AND DEPTH.
 - g. SCARIFY OR TILL SUBGRADE TO A DEPTH OF 4 INCHES. EXCEPT FOR WITHIN THE DRIP LINE OF EXISTING TREES, THE ENTIRE SURFACE SHALL BE DISTURBED BY SCARIFICATION;
 - h. PLACE 4 INCHES OF IMPORTED TOPSOIL MIX ON SURFACE. THE IMPORTED TOPSOIL MIX SHALL CONTAIN 4% ORGANIC MATTER. SOILS USED IN THE MIX SHALL BE SAND OR SANDY LOAM AS DEFINED BY THE USDA; SHOP DRAWING SUBMITTAL IS REQUIRED. FIND USDA SIEVE FOR SAND AND SANDY LOAM.
 - i. RAKE BEDS TO SMOOTH AND REMOVE SURFACE ROCKS LARGER THAN 2 INCHES IN DIAMETER;
 - j. WATER OR ROLL TO COMPACT SOIL IN TURF AREAS TO 85% OF MAXIMUM DRY DENSITY.

SOIL MANAGEMENT

- IDENTIFIES AREAS ON THE SITE SUBJECT TO THE STANDARD;
- SOIL DEPTH AND QUALITY SHALL BE ESTABLISHED TOWARDS THE END OF CONSTRUCTION AND ONCE ESTABLISHED, PROTECTED FROM COMPACTION, SUCH AS FROM LARGE MACHINERY, VEHICLE TRAFFIC, AND FROM EROSION;
- AFTER SOIL AMENDMENTS AND PLACEMENT IS COMPLETE, AND PRIOR TO SEEDING AND MULCHING, CONTRACTOR SHALL PERFORM VERIFICATION SAMPLING IN LOCATIONS INDICATED ON SAMPLING PLAN. VERIFICATION SAMPLING SHALL INCLUDE NINE, 8 INCH DEEP (MIN) TEST HOLES PER ACRE OF AREA SUBJECT TO THE STANDARD. TEST HOLES SHALL BE EXCAVATED USING ONLY A SHOVEL DRIVEN SOLELY BY INSPECTOR'S WEIGHT AND SHALL BE AT LEAST 50 FEET APART FROM EACH OTHER.
- A DENSE AND VIGOROUS VEGETATIVE COVER SHALL BE ESTABLISHED OVER TURF AREAS.



ADDITIONAL SOILS RESTORATION

1. SOIL DEPTH AND QUALITY SHALL BE ESTABLISHED TOWARDS THE END OF CONSTRUCTION, AND ONCE ESTABLISHED, BE PROTECTED FROM COMPACTION.
2. THE CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF THE POST CONSTRUCTION SOIL DEPTH AND QUALITY.
3. VERIFICATION SHALL BE VIA A SAMPLING SCHEME THAT INCLUDES NINE 8" DEEP TEST HOLES PER ACRE OF AREA SUBJECT TO THE STANDARD.
4. TEST HOLES SHALL BE EXCAVATED USING ONLY A SHOVEL DRIVEN SOLELY BY THE INSPECTOR'S WEIGHT AND SHALL BE AT LEAST 50 FEET APART FROM EACH OTHER.
5. ALL DISTURBED AREAS WITHIN THE PROJECT LIMITS (LOD) ARE SUBJECT TO THE POST-CONSTRUCTION SOIL DEPTH AND QUALITY STANDARD
6. THERE IS NO PROPOSED EXCAVATION OR RE-GRADING ANTICIPATED WITHIN THE SOLAR ARRAY BEYOND WHAT IS NECESSARY FOR SETTING POSTS AND INSTALLING CONDUIT. IT IS ANTICIPATED THAT SOME GROUND DISTURBANCE WILL OCCUR WITHIN THE ARRAY FROM FREQUENT TRACKING OF EQUIPMENT. THE CONTRACTOR AND ENGINEER SHALL EVALUATE GROUND DISTURBANCE WITHIN THE SOLAR ARRAY AND EITHER:
 - CONFIRM THAT SOILS HAVE NOT BEEN EXCESSIVELY COMPACTED VIA TEST PITS AND PHOTO DOCUMENTATION
 - IMPLEMENT THE MEASURES OUTLINED IN THE "POST CONSTRUCTION SOIL DEPTH & QUALITY STANDARD" IF EXCESSIVE COMPACTION HAS OCCURRED.



EARTH EMBANKMENT CONSTRUCTION NOTES

1. THE AREA WITHIN THE EMBANKMENT AND 15 FEET BEYOND SHALL BE CLEARED AND GRUBBED (EXCEPT IN THE WETLAND BUFFER). ORGANICS AND MATERIALS DEEMED UNSUITABLE BY THE ENGINEER (SUCH AS LOOSE, FROZEN, DISTURBED SOILS, DEBRIS, VEGETATION, TREE STUMPS, OVER SATURATED AND UNSTABLE SOILS) SHALL BE REMOVED AND A FIRM STABLE SUBGRADE SHALL BE PREPARED ON UNDISTURBED SOILS. ALL SUBGRADE SOILS SHALL BE OBSERVED BY THE ENGINEER. EXCAVATION SHALL BE PERFORMED IN A MANNER TO LIMIT DISTURBANCE AND LOOSENING OF THE SUBGRADE.
2. SCHEDULE AND COORDINATE EXCAVATION AND BACKFILL WORK WITH A DRY WEATHER FORECAST TO PREVENT OPEN EXCAVATIONS AND ACCUMULATION OF STORMWATER RUNOFF.
3. THE ENGINEER SHALL BE PRESENT TO OBSERVE THE SUBGRADE SOILS PRIOR TO PLACING THE SELECT EMBANKMENT FILL SOILS. PRIOR TO BACKFILL THE SUBGRADE SHALL BE PROOF-ROLL COMPACTED, IN THE PRESENCE OF THE ENGINEER, USING A SMOOTH DRUM ROLLER IN STATIC MODE AND/OR WITH BUCKET DOWN PRESSURE AS DIRECTED BY THE ENGINEER. THE ENGINEER SHALL BE CONTACTED WITH AT LEAST 48 HOURS NOTICE TO SCHEDULE SUBGRADE PREPARATION AND PROOF COMPACTION.
4. SELECT SOIL SHALL BE USED FOR CONSTRUCTION OF THE CUT-OFF TRENCH AND EARTH EMBANKMENT. THE SOIL SHALL MEET THE UNIFIED SOIL CLASSIFICATION SYSTEM DESIGNATION FOR EITHER CLAYEY SAND (SC) OR SILTY CLAYS (CL) WITH A LOW TO MEDIUM PLASTICITY. A MINIMUM OF TWO UNIFIED SOIL CLASSIFICATION TESTS SHALL BE PERFORMED ON STOCKPILE SOIL SAMPLES FOR APPROVAL. THE SOIL SHALL HAVE NO ROCKS LARGER THAN 2", FROZEN LUMPS, ORGANICS, OR OTHER DELETERIOUS MATERIALS.
5. ALL SELECT EMBANKMENT SOILS SHALL BE PLACED IN 6" LIFTS. SOIL SHALL BE COMPACTED TO 95% OF THE STANDARD PROCTOR.
6. IT IS IMPORTANT THAT THE EXISTING SUBGRADE AND SELECT SOILS BE PROTECTED DURING CONSTRUCTION IN ACCORDANCE WITH THE FOLLOWING REQUIREMENTS:
 - 6.1. TO THE MAXIMUM EXTENT POSSIBLE WORK SHALL BE PLANNED SO SUBGRADE SOILS AND THE EMBANKMENT SOILS ARE NOT EXPOSED TO PRECIPITATION.
 - 6.2. PRIOR TO EXCAVATING, POTENTIAL SOURCES OF SURFACE WATER SHALL BE DIRECTED AWAY FROM THE EXCAVATIONS.
 - 6.3. PLACEMENT OF SELECT EMBANKMENT FILL SOILS SHALL NOT BE PLACED DURING A RAIN EVENT.
 - 6.4. PRIOR TO PERIODS OF FORECASTED RAIN, THE SELECT SOILS SHALL BE GRADED TO DRAIN AND ROLLED SMOOTH WITH A DRUM ROLL COMPACTOR.
 - 6.5. SOIL THAT IS NOT PROTECTED AND BECOMES WEAKENED BY PRECIPITATION SHALL BE REMOVED AND DISPOSED OF AT NO COST TO THE OWNER.
7. THE GRAVEL FILTER LAYER FOR THE EMERGENCY SPILLWAY SHALL BE PLACED WITH THE FOLLOWING REQUIREMENTS:
 - 7.1. MINIMUM 6" SEPARATION BETWEEN PREPARED/ACCEPTED SUBGRADE AND IN PLACE STONE FILL. SEE BELOW FOR MATERIAL SPECIFICATION. THIS LAYER WILL BE PLACED IN A SINGLE 6" LIFT COMPACTED TO 90% STANDARD PROCTOR. THE GRAVEL FILTER MATERIAL SHALL NOT BE FROZEN AND SHALL NOT BE PLACED ON FROZEN SUBGRADE.
 - 7.2. PLACEMENT OF STONE FILL SHALL NOT OCCUR UNTIL FULL COMPACTED THICKNESS OF GRANULAR FILTER HAS BEEN PLACED.
8. THE STONE FILL FOR THE EMERGENCY SPILLWAY SHALL BE PLACED BY METHODS THAT AVOID SEGREGATION AND SHALL BE PLACED TO THE REQUIRED THICKNESS, IN LIFTS RESULTING IN A WELL GRADED HOMOGENOUS MASS WITH A RELATIVELY LOW VOID RATIO AND TIGHTLY INTEGRATED WITH PRIOR LIFTS. GRAVEL FILTER MATERIAL SHALL BE PLACED AND "WASHED IN" WITH WATER TO MINIMIZE VOIDS IN THE STONE FILL. STONE FILL SHALL NOT BE PLACED ON FROZEN MATERIAL.



NOTES

1. ALL ROOF DRAINS WHICH OUTLET INTO CATCH BASIN, SHALL BE DESIGNED BY THE MECHANICAL ENGINEER TO OVERFLOW ROOF SCUPPERS WITHOUT FAILING WITHIN THE BUILDING. ALL ROOF DRAIN INVERTS WILL SIT A MINIMUM OF 12" ABOVE THE INVERT OUT OF CATCH BASIN.

HAZELETT
STRIP-CASTING
CORPORATION

COLCHESTER, VT



164 Main Street, Suite 201
Colchester, Vermont 05446
P: (802) 878-0375
www.krebsandlansing.com

STAMP:

Project:

THE 'H'
AT
MALLETTS BAY

180 & 166 W. Lakeshore Drive
Colchester, Vermont

Project No.	23314
Scale	N.T.S.
Drawn by	SWH
Checked by	
Date	03/03/25


Revisions	No.	Date	Description

Drawing Title

CIVIL DETAILS

Drawing No.

CD-7




- NOTES**
- WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES WIRE FENCE REINFORCEMENT REQUIRED WITHIN 100 FT UPSLOPE OF RECEIVING WATERS.
 - FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH ITIES SPACED 24" AT THE TOP AND MID SECTION.
 - WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY 6" AND FOLDED. FILTER CLOTH SHALL BE MIRAFI 100X OR APPROVED EQUIVALENT.
 - PREFABRICATED UNITS SHALL BE GEOFAB, ENVIOFENCE OR EQUIVALENT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION, MAINTENANCE, AND REMOVAL OF SILT FENCE IN ALL LOCATIONS SHOWN ON THE PLANS.
 - MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN SEDIMENT REACHES HALF OF FABRIC HEIGHT. REMOVE SILT FENCE AFTER SUCCESSFUL ESTABLISHMENT OF VEGETATION.
 - OTHER MEASURES MAY BE USED TO REINFORCE SILT FENCE IN PLACE OF WIRE MESH, CONTRACTOR WILL APPROVE ALL MEASURES WITH ENGINEER PRIOR TO USE.
 - IF SILT FENCE IS INSTALLED WHEN GROUND IS FROZEN, A GRAVEL, SAND OR WATTLE BALLAST MUST BE USED.
 - CONTRACTOR MAY USE (VI) WIRE BACK SILT FENCE (IVI PRODUCT 940-3610-B48-W6H) OR EQUIVALENT.
 - SILT FENCE SHALL BE INSTALLED ALONG CONTOURS.
 - SILT FENCE SHALL NOT BE LOCATED IN AREAS OF CONCENTRATED FLOW.
 - DRAINAGE AREA SHALL BE $\frac{1}{4}$ ACRE PER 100 LINEAR FEET OF SILT FENCE.


**TYPICAL TEMPORARY
REINFORCED SILT FENCE**
N.T.S.

PERIMETER EROSION CONTROL SCHEDULE		
DISTANCE FROM RECEIVING WATER AND ALL WATER RESOURCE AREAS (WRA)	SLOPE	ACCEPTABLE EPSC MEASURE
100 FEET	ALL	REINFORCED SILT FENCE, TWO ROWS OF NONREINFORCED SILT FENCE OR ROW OF WATTLE INSIDE OF NONREINFORCED SILT FENCE
100 FEET	ALL	NONREINFORCED SILT FENCE OR WATTLE PER SPECIFICATIONS BELOW

- NOTES**
- AT A MINIMUM, EPSC MEASURES MEET VT DEC STANDARDS AND SPECIFICATIONS FOR EROSION PREVENTION AND SEDIMENT CONTROL OR PREVIOUSLY APPROVED INTERCHANGEABLE PRACTICES.
 - PERIMETER CONTROLS SHALL BE UTILIZED IN SMALL AREAS 1 ACRE. IN AREAS 1 ACRE, TEMPORARY SEDIMENT TRAPS OR TEMPORARY SEDIMENT BASINS ARE TO BE UTILIZED.
 - PERIMETER CONTROLS SHALL BE INSTALLED ON DOWNSLOPE SIDE OF PLANNED EARTH DISTURBANCE.
 - PERIMETER CONTROLS SHALL BE INSTALLED PRIOR TO ANY EARTH DISTURBING ACTIVITIES WITHIN UPSLOPE CONTRIBUTING AREA.
 - SILT FENCE SHALL NOT BE USED AS CONSTRUCTION DEMARCATION.
 - SILTSOXX CAN BE USED AS A SILT FENCE ALTERNATIVE, WITH PRIOR APPROVAL OF THE ENGINEER. SEE DETAIL.
 - IF SILT FENCE IS INSTALLED WHEN GROUND IS FROZEN, A GRAVEL, SHOT ROCK, OR SAND BALLAST MUST BE USED.




TYPICAL TEMPORARY SILT FENCE
N.T.S.




- NOTES**
- CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION, MAINTENANCE, AND REMOVAL OF SILTSOXX IN ALL LOCATIONS SHOWN ON THE PLANS. SILTSOXX MAY BE LEFT IN PLACE IF THE CONTRACTOR SEEDS AND MULCHES SILTSOXX FOR GROWTH POST CONSTRUCTION.
 - MAINTENANCE SHALL BE PERFORMED AS NEEDED AND ADDITIONAL SILTSOXX WILL BE ADDED WHEN SEDIMENT REACHES HALF OF PRODUCT HEIGHT.
 - WHEN INSTALLING LENGTHS OF SILTSOXX, LENGTHS WILL OVERLAP BY MINIMUM 18" WHEN TRANSITIONING TO A NEW LENGTH OF SILTSOXX.
 - CONTRACTOR SHALL REFER TO ALL MANUFACTURES SPECIFICATIONS AND DETAILS.
 - SILTSOXX CAN ONLY BE USED IN A GRASS LINED SWALE, MAY NOT BE USED IN STONE LINED SWALES.
 - SILTSOXX CHECK DAM CAN ONLY BE USED IN CHANNELS WITH SLOPES LESS THAN 5%.
 - SILTSOXX IS A SPECIFIC MANUFACTURER, OTHER MANUFACTURERS WITH EQUAL PRODUCTS MAY BE USED IF APPROVED BY ENGINEER.

TYPICAL SILTSOXX CHECK DAM DETAIL
N.T.S.


- NOTES**
- ACCEPTABLE EPSC MEASURE DETAILS ARE PROVIDED BELOW.
 - AT A MINIMUM, EPSC MEASURES MEET VT DEC STANDARDS AND SPECIFICATIONS FOR EROSION PREVENTION AND SEDIMENT CONTROL OR PREVIOUSLY APPROVED INTERCHANGEABLE PRACTICES.
 - LIMITS OF DISTURBANCE (OR "CONSTRUCTION DEMARCATION") SHALL BE INSTALLED PRIOR TO ANY EARTH DISTURBING ACTIVITIES.
 - BARRIER TAPE/ROPE: FOR USE WHERE PROPOSED DISTURBANCE BORDERS NON-WOODED, VEGETATED AREAS MORE THAN 100 FT FROM THE NEAREST WATER RESOURCE (STREAM, BROOK, LAKE, POND, WETLAND, ETC.). BARRIER TAPE IS HIGH VISIBILITY FIBERGLASS TAPE, MINIMUM 3" IN WIDTH COMMONLY USED IN 8K+ AREAS FOR DEMARCATING CLOSED AREAS. BARRIER TAPE AND ROPE SHOULD BE ATTACHED TO STAKES, AT A MINIMUM HEIGHT OF 4 FT FROM THE GROUND.
 - MINIMUM 1 TO 2 ROWS OF MESH BARRIER TAPE TO BE INSTALLED ALONG CONSTRUCTION PERIMETER.
 - EACH ROW OF BARRIER TAPE TO BE 3" WIDE MINIMUM.
 - BARRIER TAPE TO BE ORANGE.
 - SECURE BARRIER TAPE TO STAKES OR EXISTING TREE TRUNKS WITH BOTTOM ROW AT 4' DISTANCE FROM GROUND SURFACE (MINIMUM).
 - MAINTAIN AND REPLACE AS NEEDED. REMOVE AT COMPLETION OF PROJECT PER OSPC.
 - IN EVENT THE OSPC DETERMINES BARRIER TAPE IS NOT SUFFICIENT, REPLACE WITH ORANGE CONSTRUCTION FENCE OR SNOW FENCE.



**TYPICAL CONSTRUCTION
LIMIT BARRIER**
N.T.S.




TYPICAL SILT FENCE "J-HOOK" CONSTRUCTION
N.T.S.




- NOTES**
- CONTRACTOR SHALL STABILIZE CONSTRUCTION ENTRANCE AS REQUIRED TO PREVENT TRACKING OF SEDIMENT OFF-SITE.
 - CONTRACTOR TO USE MIRAFI 500X UNDER STONE FOR TEMPORARY CONSTRUCTION ROADS.
 - CRUSHED STONE SHALL BE ADDED OR REPLACED WHEN 80% OF THE VOIDS ARE FILLED WITH SEDIMENT.
 - STONE SIZE SHALL BE 1-4".
 - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCE SHALL BE PIPED BENEATH ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES IS ALLOWED.


STABILIZED CONSTRUCTION ENTRANCE
N.T.S.



STONE CHECK DAM
N.T.S.



TYPICAL SILTSOXX SEDIMENT CONTROL
N.T.S.



- NOTES**
- CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION, MAINTENANCE, AND REMOVAL OF SILTSOXX IN ALL LOCATIONS SHOWN ON THE PLANS.
 - MAINTENANCE SHALL BE PERFORMED AS NEEDED AND ADDITIONAL SILTSOXX WILL BE ADDED WHEN SEDIMENT REACHES HALF OF PRODUCT HEIGHT.
 - WHEN INSTALLING LENGTHS OF SILTSOXX, LENGTHS WILL OVERLAP BY MINIMUM 2' WHEN TRANSITIONING TO A NEW LENGTH OF WATTLE.
 - CONTRACTOR SHALL REFER TO ALL MANUFACTURES SPECIFICATIONS AND DETAILS.
 - SILTSOXX IS A SPECIFIC MANUFACTURER, OTHER MANUFACTURERS WITH EQUAL PRODUCTS MAY BE USED IF APPROVED BY ENGINEER.

SILTSOXX INLET PROTECTION
N.T.S.

- NOTES**
- STONE WILL BE PLACED ON A FILTER FABRIC FOUNDATION TO THE LINES, GRADES AND LOCATIONS SHOWN IN THE PLAN.
 - SET SPACING OF CHECK DAMS TO ASSUME THAT THE ELEVATIONS OF THE CREST OF THE DOWNSTREAM DAM IS AT THE SAME ELEVATION OF THE TOE OF THE UPSTREAM DAM.
 - EXTEND THE STONE A MINIMUM OF 1.5 FEET BEYOND THE DITCH BANKS TO PREVENT CUTTING AROUND THE DAM.
 - PROTECT THE CHANNEL DOWNSTREAM OF THE LOWEST CHECK DAM FROM SCOUR AND EROSION WITH STONE OR LINER AS APPROPRIATE.
 - ENSURE THAT CHANNEL APPURTENANCES SUCH AS CULVERT ENTRANCES BELOW CHECK DAMS ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM DISPLACED STONES.

SEEDING SPECIFICATIONS

PERMANENT SEED MIX SHALL BE USED AS EARLY AS PRACTICABLE BETWEEN 5/15 AND 9/15 AND SHALL MEET THE FOLLOWING CRITERIA:		
SEED	% WEIGHT	
RED FESCUE	50%	
SHEEP FESCUE	25%	
RED TOP	5%	
WHITE CLOVER	10%	
ANNUAL RYE	10%	

TEMPORARY SEED MIX SHALL BE USED BETWEEN 9/16 AND 5/14 AND SHALL MEET THE FOLLOWING CRITERIA:		
SEED	% WEIGHT	%GERMINATION
WINTER RYE	80% MIN.	85% MIN.
RED FESCUE (CREEPING)	4% MIN.	80% MIN.
PERENNIAL RYE GRASS	3% MIN.	90% MIN.
RED CLOVER	3% MIN.	90% MIN.
OTHER CROP GRASS	0.5% MAX.	
NOXIOUS WEED SEED	0.5% MAX.	
INERT MATTER	1% MAX.	

HAZELETT STRIP-CASTING CORPORATION

COLCHESTER, VT



STAMP:

Project: THE 'H' AT MALLETTS BAY

180 & 166 W. Lakeshore Drive
Colchester, Vermont

Project No.	23314
Scale	N.T.S.
Drawn by	SWH
Checked by	
Date	03/03/25

Revisions		
No.	Date	Description

Drawing Title EPSC DETAILS

Drawing No.

CD-8

CONSTRUCTION STORMWATER
DISCHARGE PERMIT INFORMATION



1. THIS PROJECT PROPOSES GREATER THAN 1 ACRE OF SOIL DISTURBANCE ON SITE. THE PROJECT WILL FOLLOW THIS CONSTRUCTION GENERAL PERMIT 3-9020.
2. THE PROPOSED PROJECT HAS BEEN SCORED USING THE STATE OF VERMONT APPENDIX-A RISK EVALUATION. THE PROJECT IS SCORED "MODERATE RISK" BASED ON THE EVALUATIONS CRITERIA.
3. THE MAXIMUM AREA OF EARTH DISTURBANCE AT ANY ONE TIME SHALL NOT EXCEED **5 ACRES**.
4. ALL AREAS OF EARTH DISTURBANCE ASSOCIATED WITH THIS PROJECT MUST BE STABILIZED WITHIN 14-DAYS OF INITIAL DISTURBANCE. AFTER THIS INITIAL 14-DAY PERIOD, ALL EARTH DISTURBANCE AREAS ASSOCIATED MUST BE STABILIZED ON A DAILY BASIS, WITH THE FOLLOWING EXCEPTIONS:
 - I. STABILIZATION IS NOT REQUIRED IF WORK IS TO CONTINUE WITHIN THE AREA WITHIN THE NEXT 24 HOURS AND THERE IS NO PRECIPITATION FORECAST FOR THE NEXT 24 HOURS.
 - II. STABILIZATION IS NOT REQUIRED IF THE WORK IS OCCURRING IN A SELF-CONTAINED EXCAVATION (I.E., NO OUTLET FOR STORMWATER) WITH A DEPTH OF 2 FEET OR GREATER (E.G., UNDERGROUND LINE INSTALLATION).
5. PROJECT DOES PROPOSE WINTER CONSTRUCTION.
6. ALL TEMPORARY EPSC MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY EPSC MEASURES ARE NO LONGER NEEDED, UNLESS OTHERWISE AUTHORIZED AND APPROVED IN WRITING BY THE OWNER.
7. SOIL STABILIZATION SHALL BE ACHIEVED BY SEED AND MULCH, HYDROSEEDING WITH MULCH TACKIFIER, SOD, STONE, AND/OR ROLLED EROSION CONTROL PRODUCTS (E.G., EROSION CONTROL BLANKET). MULCH SHALL BE COMPRISED OF STRAW, HAY, COMPOST, WOODCHIPS, WOOD STUMP GRINDINGS, AND/OR EROSION CONTROL MIX.
8. APPROPRIATE SEED MIX SHALL BE APPLIED TO DESIGNATED AREAS PER THIS EPSC PLAN AND SEED SPECIFICATIONS.

TEMPORARY & FINAL STABILIZATION NOTES

1. ALL AREAS OF EARTH DISTURBANCE ASSOCIATED WITH THIS PROJECT MUST BE STABILIZED WITHIN 14 DAYS OF INITIAL DISTURBANCE. AFTER THIS INITIAL 14-DAY PERIOD, ALL EARTH DISTURBANCE AREAS ASSOCIATED MUST BE STABILIZED ON A DAILY BASIS, WITH THE FOLLOWING EXCEPTIONS:
 - I. STABILIZATION IS NOT REQUIRED IF WORK IS TO CONTINUE WITHIN THE AREA WITHIN THE NEXT 24 HOURS AND THERE IS NO PRECIPITATION FORECAST FOR THE NEXT 24 HOURS.
 - II. STABILIZATION IS NOT REQUIRED IF THE WORK IS OCCURRING IN A SELF-CONTAINED EXCAVATION (I.E., NO OUTLET FOR STORMWATER) WITH A DEPTH OF 2 FEET OR GREATER (E.G., UNDERGROUND LINE INSTALLATION).
2. THE MAXIMUM AREA OF EARTH DISTURBANCE AT ANY ONE TIME SHALL NOT EXCEED **5 ACRES**.
3. SOIL STABILIZATION SHALL BE ACHIEVED BY SEED AND MULCH (SEE DETAILS). HYDROSEEDING WITH MULCH TACKIFIER, SOD, STONE, AND/OR ROLLED EROSION CONTROL PRODUCTS (E.G., EROSION CONTROL BLANKET; SEE DETAIL). MULCH SHALL BE COMPRISED OF STRAW, HAY, COMPOST, WOODCHIPS, WOOD STUMP GRINDINGS, AND/OR EROSION CONTROL MIX (SEE DETAIL).
4. APPROPRIATE SEED MIX SHALL BE APPLIED TO DESIGNATED AREAS PER THIS EPSC PLAN AND SEED SPECIFICATIONS (SEE DETAILS). FOR AN AREA TO BE STABILIZED FOR WINTER BY VEGETATED COVER, SEEDING MUST BE COMPLETED BY SEPTEMBER 15.
5. AREAS TO BE STABILIZED FOR WINTER THAT DO NOT HAVE ESTABLISHED VEGETATION BY OCTOBER 15 SHALL BE STABILIZED BY ANCHORED MULCH AT THE WINTER APPLICATION RATE, OR OTHER APPROVED STABILIZATION MEASURES (E.G., ROLLED EROSION CONTROL PRODUCT; SEE DETAIL). DORMANT SEEDING WITH WINTER RYE IS RECOMMENDED (SEE DETAIL).
6. ALL TEMPORARY EPSC MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY EPSC MEASURES ARE NO LONGER NEEDED, UNLESS OTHERWISE AUTHORIZED AND APPROVED IN WRITING BY THE OWNER.
7. FOLLOWING TEMPORARY OR PERMANENT STABILIZATION, MAINTENANCE SHALL BE PERFORMED AS NECESSARY TO ENSURE CONTINUED STABILIZATION.
8. EXCEPT AS NOTED BELOW, ALL AREAS OF DISTURBANCE SHALL BE SEEDED AND STABILIZED WITH EPSC MEASURES (E.G., MULCH, EROSION CONTROL MIX, ROCK RIP RAP, OR ROLLED EROSION CONTROL PRODUCT), INCLUDING AREAS WHERE CONSTRUCTION HAS BEEN SUSPENDED OR SECTIONS COMPLETED. THE FOLLOWING SHALL ALSO APPLY:
 - A. FOR ACTIVE CONSTRUCTION AREAS SUCH AS BORROW OR STOCKPILE AREAS, ROADWAY IMPROVEMENTS, AND AREAS WITHIN 50 FEET OF A BUILDING UNDER CONSTRUCTION, A PERIMETER SEDIMENT CONTROL SYSTEM (E.G., SILT FENCE) SHALL BE INSTALLED AND MAINTAINED TO CONTAIN SOIL. EXPOSED DISTURBED AREAS ADJACENT TO A CONVEYANCE THAT PROVIDES RAPID OFFSITE DISCHARGE OF SEDIMENT (E.G., A CUT SLOPE AT AN ENTRANCE) SHALL BE COVERED WITH PLASTIC OR GEOTEXTILE TO PREVENT SOIL LOSS UNTIL THE AREA CAN BE STABILIZED. STABILIZED CONSTRUCTION ENTRANCES SHALL BE MAINTAINED TO CONTROL EQUIPMENT AND VEHICLES FROM TRACKING MATERIAL OFF SITE.
 - B. PERMANENT SEEDING SHALL ONLY BE UNDERTAKEN IN THE SPRING SEASON FROM APRIL THROUGH MAY AND IN LATE SUMMER AND EARLY FALL UNTIL SEPTEMBER 15. SUMMER PLANTING MAY BE CONDUCTED IF ADEQUATE WATERING IS PROVIDED. DURING THE PEAK SUMMER MONTHS AND IN THE FALL AFTER SEPTEMBER 15, AN APPROPRIATE TEMPORARY SEEDING MUST BE IMPLEMENTED. TEMPORARY SUMMER PLANTING MAY SUFFICE FOR PERMANENT SEEDING IF ADEQUATE NATURAL RAINFALL ALLOWS FOR VIGOROUS GROWTH DURING THE MID SUMMER PERIOD. THE CONTRACTOR'S SCOPE OF WORK SHALL INCLUDE RETURN TO THE SITE THE SPRING FOLLOWING CONSTRUCTION TO PERFORM ANY FURTHER SEEDING THAT MAY BE REQUIRED AND TO REMOVE ANY REMAINING EROSION CONTROL MEASURES THAT ARE NO LONGER NEEDED.
- D. TEMPORARY SEDIMENT TRAPPING DEVICES (E.G., SILT FENCE) SHALL NOT BE REMOVED UNTIL PERMANENT STABILIZATION IS ESTABLISHED IN ALL CONTRIBUTORY DRAINAGE AREAS. SIMILARLY, STABILIZATION SHALL BE ESTABLISHED PRIOR TO CONVERTING SEDIMENT TRAPS AND/OR SEDIMENT BASINS INTO PERMANENT (POST-CONSTRUCTION) STORMWATER MANAGEMENT PRACTICES.
- E. STABILIZATION MEASURES SHALL BE APPLIED TO BARE EARTH SURFACES WITH SEED AND ANCHORED STRAW MULCH, OR OTHER APPROVED STABILIZATION MEASURES (E.G., ROLLED EROSION CONTROL PRODUCT) AS SOON AS POSSIBLE AFTER DISTURBANCE.


*EPSC" - EROSION PREVENT & SEDIMENT CONTROL
*OSPC" - ON-SITE PLAN COORDINATOR

ALLOW DISTURBED SEDIMENT TO FILL BEHIND SILT SOXX, ADD AN ADDITIONAL SILT SOXX TO TOP IF SOIL BEHIND EXCEEDS THE HEIGHT OF THE SILT SOXX. POST CONSTRUCTION LEAVE IN PLACE ADD AN ADDITIONAL SILT SOXX BEHIND CONSTRUCTION, SEED AND MULCH OVER WHOLE AREA



SILT SOXX OR CONSTRUCTED WATER BAR DETAIL

N.T.S.




NOTE: WHEN USING CELL-0-SEED DO NOT SEED PREPARED AREA. CELL-0-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.

NOTE: BLANKET SHALL BE USED ON SLOPES 3:1 OR STEEPER

NOTE:
NO LOOSE SOIL CONDITIONS, THE USE OF STABLE OR STAKE LENGTHS GREATER THAN 4' (15cm) MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.

1649 HOBERRY 41 NORTH EVANVILLE, INDIANA 47225
USA 1-800-772-2040 CANADA 1-800-448-2040
www.norgreen.com



NOTE:
A. PERMANENT STAKE SPACING SHOULD BE ALTERED TO:
1. DISTURBED AND SEAR: 12" (30cm) MAX. SPACING
2. PROTECTED AREAS: 18" (45cm) MAX. SPACING
3. CRITICAL POINTS: 24" (60cm) MAX. SPACING
4. CRITICAL POINTS: 24" (60cm) MAX. SPACING
5. CRITICAL POINTS: 24" (60cm) MAX. SPACING
6. CRITICAL POINTS: 24" (60cm) MAX. SPACING
7. CRITICAL POINTS: 24" (60cm) MAX. SPACING
8. CRITICAL POINTS: 24" (60cm) MAX. SPACING
9. CRITICAL POINTS: 24" (60cm) MAX. SPACING
10. CRITICAL POINTS: 24" (60cm) MAX. SPACING
11. CRITICAL POINTS: 24" (60cm) MAX. SPACING
12. CRITICAL POINTS: 24" (60cm) MAX. SPACING
13. CRITICAL POINTS: 24" (60cm) MAX. SPACING
14. CRITICAL POINTS: 24" (60cm) MAX. SPACING
15. CRITICAL POINTS: 24" (60cm) MAX. SPACING
16. CRITICAL POINTS: 24" (60cm) MAX. SPACING
17. CRITICAL POINTS: 24" (60cm) MAX. SPACING
18. CRITICAL POINTS: 24" (60cm) MAX. SPACING
19. CRITICAL POINTS: 24" (60cm) MAX. SPACING
20. CRITICAL POINTS: 24" (60cm) MAX. SPACING
21. CRITICAL POINTS: 24" (60cm) MAX. SPACING
22. CRITICAL POINTS: 24" (60cm) MAX. SPACING
23. CRITICAL POINTS: 24" (60cm) MAX. SPACING
24. CRITICAL POINTS: 24" (60cm) MAX. SPACING
25. CRITICAL POINTS: 24" (60cm) MAX. SPACING
26. CRITICAL POINTS: 24" (60cm) MAX. SPACING
27. CRITICAL POINTS: 24" (60cm) MAX. SPACING
28. CRITICAL POINTS: 24" (60cm) MAX. SPACING
29. CRITICAL POINTS: 24" (60cm) MAX. SPACING
30. CRITICAL POINTS: 24" (60cm) MAX. SPACING
31. CRITICAL POINTS: 24" (60cm) MAX. SPACING
32. CRITICAL POINTS: 24" (60cm) MAX. SPACING
33. CRITICAL POINTS: 24" (60cm) MAX. SPACING
34. CRITICAL POINTS: 24" (60cm) MAX. SPACING
35. CRITICAL POINTS: 24" (60cm) MAX. SPACING
36. CRITICAL POINTS: 24" (60cm) MAX. SPACING
37. CRITICAL POINTS: 24" (60cm) MAX. SPACING
38. CRITICAL POINTS: 24" (60cm) MAX. SPACING
39. CRITICAL POINTS: 24" (60cm) MAX. SPACING
40. CRITICAL POINTS: 24" (60cm) MAX. SPACING
41. CRITICAL POINTS: 24" (60cm) MAX. SPACING
42. CRITICAL POINTS: 24" (60cm) MAX. SPACING
43. CRITICAL POINTS: 24" (60cm) MAX. SPACING
44. CRITICAL POINTS: 24" (60cm) MAX. SPACING
45. CRITICAL POINTS: 24" (60cm) MAX. SPACING
46. CRITICAL POINTS: 24" (60cm) MAX. SPACING
47. CRITICAL POINTS: 24" (60cm) MAX. SPACING
48. CRITICAL POINTS: 24" (60cm) MAX. SPACING
49. CRITICAL POINTS: 24" (60cm) MAX. SPACING
50. CRITICAL POINTS: 24" (60cm) MAX. SPACING
51. CRITICAL POINTS: 24" (60cm) MAX. SPACING
52. CRITICAL POINTS: 24" (60cm) MAX. SPACING
53. CRITICAL POINTS: 24" (60cm) MAX. SPACING
54. CRITICAL POINTS: 24" (60cm) MAX. SPACING
55. CRITICAL POINTS: 24" (60cm) MAX. SPACING
56. CRITICAL POINTS: 24" (60cm) MAX. SPACING
57. CRITICAL POINTS: 24" (60cm) MAX. SPACING
58. CRITICAL POINTS: 24" (60cm) MAX. SPACING
59. CRITICAL POINTS: 24" (60cm) MAX. SPACING
60. CRITICAL POINTS: 24" (60cm) MAX. SPACING
61. CRITICAL POINTS: 24" (60cm) MAX. SPACING
62. CRITICAL POINTS: 24" (60cm) MAX. SPACING
63. CRITICAL POINTS: 24" (60cm) MAX. SPACING
64. CRITICAL POINTS: 24" (60cm) MAX. SPACING
65. CRITICAL POINTS: 24" (60cm) MAX. SPACING
66. CRITICAL POINTS: 24" (60cm) MAX. SPACING
67. CRITICAL POINTS: 24" (60cm) MAX. SPACING
68. CRITICAL POINTS: 24" (60cm) MAX. SPACING
69. CRITICAL POINTS: 24" (60cm) MAX. SPACING
70. CRITICAL POINTS: 24" (60cm) MAX. SPACING
71. CRITICAL POINTS: 24" (60cm) MAX. SPACING
72. CRITICAL POINTS: 24" (60cm) MAX. SPACING
73. CRITICAL POINTS: 24" (60cm) MAX. SPACING
74. CRITICAL POINTS: 24" (60cm) MAX. SPACING
75. CRITICAL POINTS: 24" (60cm) MAX. SPACING
76. CRITICAL POINTS: 24" (60cm) MAX. SPACING
77. CRITICAL POINTS: 24" (60cm) MAX. SPACING
78. CRITICAL POINTS: 24" (60cm) MAX. SPACING
79. CRITICAL POINTS: 24" (60cm) MAX. SPACING
80. CRITICAL POINTS: 24" (60cm) MAX. SPACING
81. CRITICAL POINTS: 24" (60cm) MAX. SPACING
82. CRITICAL POINTS: 24" (60cm) MAX. SPACING
83. CRITICAL POINTS: 24" (60cm) MAX. SPACING
84. CRITICAL POINTS: 24" (60cm) MAX. SPACING
85. CRITICAL POINTS: 24" (60cm) MAX. SPACING
86. CRITICAL POINTS: 24" (60cm) MAX. SPACING
87. CRITICAL POINTS: 24" (60cm) MAX. SPACING
88. CRITICAL POINTS: 24" (60cm) MAX. SPACING
89. CRITICAL POINTS: 24" (60cm) MAX. SPACING
90. CRITICAL POINTS: 24" (60cm) MAX. SPACING
91. CRITICAL POINTS: 24" (60cm) MAX. SPACING
92. CRITICAL POINTS: 24" (60cm) MAX. SPACING
93. CRITICAL POINTS: 24" (60cm) MAX. SPACING
94. CRITICAL POINTS: 24" (60cm) MAX. SPACING
95. CRITICAL POINTS: 24" (60cm) MAX. SPACING
96. CRITICAL POINTS: 24" (60cm) MAX. SPACING
97. CRITICAL POINTS: 24" (60cm) MAX. SPACING
98. CRITICAL POINTS: 24" (60cm) MAX. SPACING
99. CRITICAL POINTS: 24" (60cm) MAX. SPACING
100. CRITICAL POINTS: 24" (60cm) MAX. SPACING
101. CRITICAL POINTS: 24" (60cm) MAX. SPACING
102. CRITICAL POINTS: 24" (60cm) MAX. SPACING
103. CRITICAL POINTS: 24" (60cm) MAX. SPACING
104. CRITICAL POINTS: 24" (60cm) MAX. SPACING
105. CRITICAL POINTS: 24" (60cm) MAX. SPACING
106. CRITICAL POINTS: 24" (60cm) MAX. SPACING
107. CRITICAL POINTS: 24" (60cm) MAX. SPACING
108. CRITICAL POINTS: 24" (60cm) MAX. SPACING
109. CRITICAL POINTS: 24" (60cm) MAX. SPACING
110. CRITICAL POINTS: 24" (60cm) MAX. SPACING
111. CRITICAL POINTS: 24" (60cm) MAX. SPACING
112. CRITICAL POINTS: 24" (60cm) MAX. SPACING
113. CRITICAL POINTS: 24" (60cm) MAX. SPACING
114. CRITICAL POINTS: 24" (60cm) MAX. SPACING
115. CRITICAL POINTS: 24" (60cm) MAX. SPACING
116. CRITICAL POINTS: 24" (60cm) MAX. SPACING
117. CRITICAL POINTS: 24" (60cm) MAX. SPACING
118. CRITICAL POINTS: 24" (60cm) MAX. SPACING
119. CRITICAL POINTS: 24" (60cm) MAX. SPACING
120. CRITICAL POINTS: 24" (60cm) MAX. SPACING
121. CRITICAL POINTS: 24" (60cm) MAX. SPACING
122. CRITICAL POINTS: 24" (60cm) MAX. SPACING
123. CRITICAL POINTS: 24" (60cm) MAX. SPACING
124. CRITICAL POINTS: 24" (60cm) MAX. SPACING
125. CRITICAL POINTS: 24" (60cm) MAX. SPACING
126. CRITICAL POINTS: 24" (60cm) MAX. SPACING
127. CRITICAL POINTS: 24" (60cm) MAX. SPACING
128. CRITICAL POINTS: 24" (60cm) MAX. SPACING
129. CRITICAL POINTS: 24" (60cm) MAX. SPACING
130. CRITICAL POINTS: 24" (60cm) MAX. SPACING
131. CRITICAL POINTS: 24" (60cm) MAX. SPACING
132. CRITICAL POINTS: 24" (60cm) MAX. SPACING
133. CRITICAL POINTS: 24" (60cm) MAX. SPACING
134. CRITICAL POINTS: 24" (60cm) MAX. SPACING
135. CRITICAL POINTS: 24" (60cm) MAX. SPACING
136. CRITICAL POINTS: 24" (60cm) MAX. SPACING
137. CRITICAL POINTS: 24" (60cm) MAX. SPACING
138. CRITICAL POINTS: 24" (60cm) MAX. SPACING
139. CRITICAL POINTS: 24" (60cm) MAX. SPACING
140. CRITICAL POINTS: 24" (60cm) MAX. SPACING
141. CRITICAL POINTS: 24" (60cm) MAX. SPACING
142. CRITICAL POINTS: 24" (60cm) MAX. SPACING
143. CRITICAL POINTS: 24" (60cm) MAX. SPACING
144. CRITICAL POINTS: 24" (60cm) MAX. SPACING
145. CRITICAL POINTS: 24" (60cm) MAX. SPACING
146. CRITICAL POINTS: 24" (60cm) MAX. SPACING
147. CRITICAL POINTS: 24" (60cm) MAX. SPACING
148. CRITICAL POINTS: 24" (60cm) MAX. SPACING
149. CRITICAL POINTS: 24" (60cm) MAX. SPACING
150. CRITICAL POINTS: 24" (60cm) MAX. SPACING
151. CRITICAL POINTS: 24" (60cm) MAX. SPACING
152. CRITICAL POINTS: 24" (60cm) MAX. SPACING
153. CRITICAL POINTS: 24" (60cm) MAX. SPACING
154. CRITICAL POINTS: 24" (60cm) MAX. SPACING
155. CRITICAL POINTS: 24" (60cm) MAX. SPACING
156. CRITICAL POINTS: 24" (60cm) MAX. SPACING
157. CRITICAL POINTS: 24" (60cm) MAX. SPACING
158. CRITICAL POINTS: 24" (60cm) MAX. SPACING
159. CRITICAL POINTS: 24" (60cm) MAX. SPACING
160. CRITICAL POINTS: 24" (60cm) MAX. SPACING
161. CRITICAL POINTS: 24" (60cm) MAX. SPACING
162. CRITICAL POINTS: 24" (60cm) MAX. SPACING
163. CRITICAL POINTS: 24" (60cm) MAX. SPACING
164. CRITICAL POINTS: 24" (60cm) MAX. SPACING
165. CRITICAL POINTS: 24" (60cm) MAX. SPACING
166. CRITICAL POINTS: 24" (60cm) MAX. SPACING
167. CRITICAL POINTS: 24" (60cm) MAX. SPACING
168. CRITICAL POINTS: 24" (60cm) MAX. SPACING
169. CRITICAL POINTS: 24" (60cm) MAX. SPACING
170. CRITICAL POINTS: 24" (60cm) MAX. SPACING
171. CRITICAL POINTS: 24" (60cm) MAX. SPACING
172. CRITICAL POINTS: 24" (60cm) MAX. SPACING
173. CRITICAL POINTS: 24" (60cm) MAX. SPACING
174. CRITICAL POINTS: 24" (60cm) MAX. SPACING
175. CRITICAL POINTS: 24" (60cm) MAX. SPACING
176. CRITICAL POINTS: 24" (60cm) MAX. SPACING
177. CRITICAL POINTS: 24" (60cm) MAX. SPACING
178. CRITICAL POINTS: 24" (60cm) MAX. SPACING
179. CRITICAL POINTS: 24" (60cm) MAX. SPACING
180. CRITICAL POINTS: 24" (60cm) MAX. SPACING
181. CRITICAL POINTS: 24" (60cm) MAX. SPACING
182. CRITICAL POINTS: 24" (60cm) MAX. SPACING
183. CRITICAL POINTS: 24" (60cm) MAX. SPACING
184. CRITICAL POINTS: 24" (60cm) MAX. SPACING
185. CRITICAL POINTS: 24" (60cm) MAX. SPACING
186. CRITICAL POINTS: 24" (60cm) MAX. SPACING
187. CRITICAL POINTS: 24" (60cm) MAX. SPACING
188. CRITICAL POINTS: 24" (60cm) MAX. SPACING
189. CRITICAL POINTS: 24" (60cm) MAX. SPACING
190. CRITICAL POINTS: 24" (60cm) MAX. SPACING
191. CRITICAL POINTS: 24" (60cm) MAX. SPACING
192. CRITICAL POINTS: 24" (60cm) MAX. SPACING
193. CRITICAL POINTS: 24" (60cm) MAX. SPACING
194. CRITICAL POINTS: 24" (60cm) MAX. SPACING
195. CRITICAL POINTS: 24" (60cm) MAX. SPACING
196. CRITICAL POINTS: 24" (60cm) MAX. SPACING
197. CRITICAL POINTS: 24" (60cm) MAX. SPACING
198. CRITICAL POINTS: 24" (60cm) MAX. SPACING
199. CRITICAL POINTS: 24" (60cm) MAX. SPACING
200. CRITICAL POINTS: 24" (60cm) MAX. SPACING
201. CRITICAL POINTS: 24" (60cm) MAX. SPACING
202. CRITICAL POINTS: 24" (60cm) MAX. SPACING
203. CRITICAL POINTS: 24" (60cm) MAX. SPACING
204. CRITICAL POINTS: 24" (60cm) MAX. SPACING
205. CRITICAL POINTS: 24" (60cm) MAX. SPACING
206. CRITICAL POINTS: 24" (60cm) MAX. SPACING
207. CRITICAL POINTS: 24" (60cm) MAX. SPACING
208. CRITICAL POINTS: 24" (60cm) MAX. SPACING
209. CRITICAL POINTS: 24" (60cm) MAX. SPACING
210. CRITICAL POINTS: 24" (60cm) MAX. SPACING
211. CRITICAL POINTS: 24" (60cm) MAX. SPACING
212. CRITICAL POINTS: 24" (60cm) MAX. SPACING
213. CRITICAL POINTS: 24" (60cm) MAX. SPACING
214. CRITICAL POINTS: 24" (60cm) MAX. SPACING
215. CRITICAL POINTS: 24" (60cm) MAX. SPACING
216. CRITICAL POINTS: 24" (60cm) MAX. SPACING
217. CRITICAL POINTS: 24" (60cm) MAX. SPACING
218. CRITICAL POINTS: 24" (60cm) MAX. SPACING
219. CRITICAL POINTS: 24" (60cm) MAX. SPACING
220. CRITICAL POINTS: 24" (60cm) MAX. SPACING
221. CRITICAL POINTS: 24" (60cm) MAX. SPACING
222. CRITICAL POINTS: 24" (60cm) MAX. SPACING
223. CRITICAL POINTS: 24" (60cm) MAX. SPACING
224. CRITICAL POINTS: 24" (60cm) MAX. SPACING
225. CRITICAL POINTS: 24" (60cm) MAX. SPACING
226. CRITICAL POINTS: 24" (60cm) MAX. SPACING
227. CRITICAL POINTS: 24" (60cm) MAX. SPACING
228. CRITICAL POINTS: 24" (60cm) MAX. SPACING
229. CRITICAL POINTS: 24" (60cm) MAX. SPACING
230. CRITICAL POINTS: 24" (60cm) MAX. SPACING
231. CRITICAL POINTS: 24" (60cm) MAX. SPACING
232. CRITICAL POINTS: 24" (60cm) MAX. SPACING
233. CRITICAL POINTS: 24" (60cm) MAX. SPACING
234. CRITICAL POINTS: 24" (60cm) MAX. SPACING
235. CRITICAL POINTS: 24" (60cm) MAX. SPACING
236. CRITICAL POINTS: 24" (60cm) MAX. SPACING
237. CRITICAL POINTS: 24" (60cm) MAX. SPACING
238. CRITICAL POINTS: 24" (60cm) MAX. SPACING
239. CRITICAL POINTS: 24" (60cm) MAX. SPACING
240. CRITICAL POINTS: 24" (60cm) MAX. SPACING
241. CRITICAL POINTS: 24" (60cm) MAX. SPACING
242. CRITICAL POINTS: 24" (60cm) MAX. SPACING
243. CRITICAL POINTS: 24" (60cm) MAX. SPACING
244. CRITICAL POINTS: 24" (60cm) MAX. SPACING
245. CRITICAL POINTS: 24" (60cm) MAX. SPACING
246. CRITICAL POINTS: 24" (60cm) MAX. SPACING
247. CRITICAL POINTS: 24" (60cm) MAX. SPACING
248. CRITICAL POINTS: 24" (60cm) MAX. SPACING
249. CRITICAL POINTS: 24" (60cm) MAX. SPACING
250. CRITICAL POINTS: 24" (60cm) MAX. SPACING
251. CRITICAL POINTS: 24" (60cm) MAX. SPACING
252. CRITICAL POINTS: 24" (60cm) MAX. SPACING
253. CRITICAL POINTS: 24" (60cm) MAX. SPACING
254. CRITICAL POINTS: 24" (60cm) MAX. SPACING
255. CRITICAL POINTS: 24" (60cm) MAX. SPACING
256. CRITICAL POINTS: 24" (60cm) MAX. SPACING
257. CRITICAL POINTS: 24" (60cm) MAX. SPACING
258. CRITICAL POINTS: 24" (60cm) MAX. SPACING
259. CRITICAL POINTS: 24" (60cm) MAX. SPACING
260. CRITICAL POINTS: 24" (60cm) MAX. SPACING
261. CRITICAL POINTS: 24" (60cm) MAX. SPACING
262. CRITICAL POINTS: 24" (60cm) MAX. SPACING
263. CRITICAL POINTS: 24" (60cm) MAX. SPACING
264. CRITICAL POINTS: 24" (60cm) MAX. SPACING
265. CRITICAL POINTS: 24" (60cm) MAX. SPACING
266. CRITICAL POINTS: 24" (60cm) MAX. SPACING
267. CRITICAL POINTS: 24" (60cm) MAX. SPACING
268. CRITICAL POINTS: 24" (60cm) MAX. SPACING
269. CRITICAL POINTS: 24" (60cm) MAX. SPACING
270. CRITICAL POINTS: 24" (60cm) MAX. SPACING
271. CRITICAL POINTS: 24" (60cm) MAX. SPACING
272. CRITICAL POINTS: 24" (60cm) MAX. SPACING
273. CRITICAL POINTS: 24" (60cm) MAX. SPACING
274. CRITICAL POINTS: 24" (60cm) MAX. SPACING
275. CRITICAL POINTS: 24" (60cm) MAX. SPACING
276. CRITICAL POINTS: 24" (60cm) MAX. SPACING
277. CRITICAL POINTS: 24" (60cm) MAX. SPACING
278. CRITICAL POINTS: 24" (60cm) MAX. SPACING
279. CRITICAL POINTS: 24" (60cm) MAX. SPACING
280. CRITICAL POINTS: 24" (60cm) MAX. SPACING
281. CRITICAL POINTS: 24" (60cm) MAX. SPACING
282. CRITICAL POINTS: 24" (60cm) MAX. SPACING
283. CRITICAL POINTS: 24" (60cm) MAX. SPACING
284. CRITICAL POINTS: 24" (60cm) MAX. SPACING
285. CRITICAL POINTS: 24" (60cm) MAX. SPACING
286. CRITICAL POINTS: 24" (60cm) MAX. SPACING
287. CRITICAL POINTS: 24" (60cm) MAX. SPACING
288. CRITICAL POINTS: 24" (60cm) MAX. SPACING
289. CRITICAL POINTS: 24" (60cm) MAX. SPACING
290. CRITICAL POINTS: 24" (60cm) MAX. SPACING
291. CRITICAL POINTS: 24" (60cm) MAX. SPACING
292. CRITICAL POINTS: 24" (60cm) MAX. SPACING
293. CRITICAL POINTS: 24" (60cm) MAX. SPACING
294. CRITICAL POINTS: 24" (60cm) MAX. SPACING
295. CRITICAL POINTS: 24" (60cm) MAX. SPACING
296. CRITICAL POINTS: 24" (60cm) MAX. SPACING
297. CRITICAL POINTS: 24" (60cm) MAX. SPACING
298. CRITICAL POINTS: 24" (60cm) MAX. SPACING
299. CRITICAL POINTS: 24" (60cm) MAX. SPACING
300. CRITICAL POINTS: 24" (60cm) MAX. SPACING
301. CRITICAL POINTS: 24" (60cm) MAX. SPACING
302. CRITICAL POINTS: 24" (60cm) MAX. SPACING
303. CRITICAL POINTS: 24" (60cm) MAX. SPACING
304. CRITICAL POINTS: 24" (60cm) MAX. SPACING
305. CRITICAL POINTS: 24" (60cm) MAX. SPACING
306. CRITICAL POINTS: 24" (60cm) MAX. SPACING
307. CRITICAL POINTS: 24" (60cm) MAX. SPACING
308. CRITICAL POINTS: 24" (60cm) MAX. SPACING
309. CRITICAL POINTS: 24" (60cm) MAX. SPACING
310. CRITICAL POINTS: 24" (60cm) MAX. SPACING
311. CRITICAL POINTS: 24" (60cm) MAX. SPACING
312. CRITICAL POINTS: 24" (60cm) MAX. SPACING
313. CRITICAL POINTS: 24" (60cm) MAX. SPACING
314. CRITICAL POINTS: 24" (60cm) MAX. SPACING
315. CRITICAL POINTS: 24" (60cm) MAX. SPACING
316. CRITICAL POINTS: 24" (60cm) MAX. SPACING
317. CRITICAL POINTS: 24" (60cm) MAX. SPACING
318. CRITICAL POINTS: 24" (60cm) MAX. SPACING
319. CRITICAL POINTS: 24" (60cm) MAX. SPACING
320. CRITICAL POINTS: 24" (60cm) MAX. SPACING
321. CRITICAL POINTS: 24" (60cm) MAX. SPACING
322. CRITICAL POINTS: 24" (60cm) MAX. SPACING
323. CRITICAL POINTS: 24" (60cm) MAX. SPACING
324. CRITICAL POINTS: 24" (60cm) MAX. SPACING
325. CRITICAL POINTS: 24" (60cm) MAX. SPACING
326. CRITICAL POINTS: 24" (60cm) MAX. SPACING
327. CRITICAL POINTS: 24" (60cm) MAX. SPACING
328. CRITICAL POINTS: 24" (60cm) MAX. SPACING
329. CRITICAL POINTS: 24" (60cm) MAX. SPACING
330. CRITICAL POINTS: 24" (60cm) MAX. SPACING
331. CRITICAL POINTS: 24" (60cm) MAX. SPACING
332. CRITICAL POINTS: 24" (60cm) MAX. SPACING
333. CRITICAL POINTS: 24" (60cm) MAX. SPACING
334. CRITICAL POINTS: 24" (60cm) MAX. SPACING
335. CRITICAL POINTS: 24" (60cm) MAX. SPACING
336. CRITICAL POINTS: 24" (60cm) MAX. SPACING
337. CRITICAL POINTS: 24" (60cm) MAX. SPACING
338. CRITICAL POINTS: 24" (60cm) MAX. SPACING
339. CRITICAL POINTS: 24" (60cm) MAX. SPACING
340. CRITICAL POINTS: 24" (60cm) MAX. SPACING
341. CRITICAL POINTS: 24" (60cm) MAX. SPACING
342. CRITICAL POINTS: 24" (60cm) MAX. SPACING
343. CRITICAL POINTS: 24" (60cm) MAX. SPACING
344. CRITICAL POINTS: 24" (60cm) MAX. SPACING
345. CRITICAL POINTS: 24" (60cm) MAX. SPACING
346. CRITICAL POINTS: 24" (60cm) MAX. SPACING
347. CRITICAL POINTS: 24" (60cm) MAX. SPACING
348. CRITICAL POINTS: 24" (60cm) MAX. SPACING
349. CRITICAL POINTS: 24" (60cm) MAX. SPACING
350. CRITICAL POINTS: 24" (60cm) MAX. SPACING
351. CRITICAL POINTS: 24" (60cm) MAX. SPACING
352. CRITICAL POINTS: 24" (60cm) MAX. SPACING
353. CRITICAL POINTS: 24" (60cm) MAX. SPACING
354. CRITICAL POINTS: 24" (60cm) MAX. SPACING
355. CRITICAL POINTS: 24" (60cm) MAX. SPACING
356. CRITICAL POINTS: 24" (60cm) MAX. SPACING
357. CRITICAL POINTS: 24" (60cm) MAX. SPACING
358. CRITICAL POINTS: 24" (60cm) MAX. SPACING
359. CRITICAL POINTS: 24" (60cm) MAX. SPACING
360. CRITICAL POINTS: 24" (60cm) MAX. SPACING
361. CRITICAL POINTS: 24" (60cm) MAX. SPACING
362. CRITICAL POINTS: 24" (60cm) MAX. SPACING
363. CRITICAL POINTS: 24" (60cm) MAX. SPACING
364. CRITICAL POINTS: 24" (60cm) MAX. SPACING
365. CRITICAL POINTS: 24" (60cm) MAX. SPACING
366. CRITICAL POINTS: 24" (60cm) MAX. SPACING
367. CRITICAL POINTS: 24" (60cm) MAX. SPACING
368. CRITICAL POINTS: 24" (60cm) MAX. SPACING
369. CRITICAL POINTS: 24" (60cm) MAX. SPACING
370. CRITICAL POINTS: 24" (60cm) MAX. SPACING
371. CRITICAL POINTS: 24" (60cm) MAX. SPACING
372. CRITICAL POINTS: 24" (60cm) MAX. SPACING
373. CRITICAL POINTS: 24" (60cm) MAX. SPACING
374. CRITICAL POINTS: 24" (60cm) MAX. SPACING
375. CRITICAL POINTS: 24" (60cm) MAX. SPACING
376. CRITICAL POINTS: 24" (60cm) MAX. SPACING
377. CRITICAL POINTS: 24" (60cm) MAX. SPACING
378. CRITICAL POINTS: 24" (60cm) MAX. SPACING
379. CRITICAL POINTS: 24" (60cm) MAX. SPACING
380. CRITICAL POINTS: 24" (60cm) MAX. SPACING
381. CRITICAL POINTS: 24" (60cm) MAX. SPACING
382. CRITICAL POINTS: 24" (60cm) MAX. SPACING
383. CRITICAL POINTS: 24" (60cm) MAX. SPACING
384. CRITICAL POINTS: 24" (60cm) MAX. SPACING
385. CRITICAL POINTS: 24" (60cm) MAX. SPACING
386. CRITICAL POINTS: 24" (60cm) MAX. SPACING
387. CRITICAL POINTS: 24" (60cm) MAX. SPACING
388. CRITICAL POINTS: 24" (60cm) MAX. SPACING
389. CRITICAL POINTS: 24" (60cm) MAX. SPACING
390. CRITICAL POINTS: 24" (60cm) MAX. SPACING
391. CRITICAL POINTS: 24" (60cm) MAX. SPACING
392. CRITICAL POINTS: 24" (60cm) MAX. SPACING
393. CRITICAL POINTS: 24" (60cm) MAX. SPACING
394. CRITICAL POINTS: 24" (60cm) MAX. SPACING
395. CRITICAL POINTS: 24" (60cm) MAX. SPACING
396. CRITICAL POINTS: 24" (60cm) MAX. SPACING
397. CRITICAL POINTS: 24" (60cm) MAX. SPACING
398. CRITICAL POINTS: 24" (60cm) MAX. SPACING
399. CRITICAL POINTS: 24" (60cm) MAX. SPACING
400. CRITICAL POINTS: 24" (60cm) MAX. SPACING
401. CRITICAL POINTS: 24" (60cm) MAX. SPACING
402. CRITICAL POINTS: 24" (60cm) MAX. SPACING
403. CRITICAL POINTS: 24" (60cm) MAX. SPACING
404

HAZELETT INN (THE "H") PARKING WORKSHEET**Values taken from Colchester Regulations Section O, Table 10-2****PROPOSED PROJECT****RESTAURANT**

- 22 Spaces/1,000 SF GFA
- Area = 2,000 SF GFA
- $22 * 2.0 = 44$ spaces

Meeting Space (Use "Community Center")

- 0.33 Spaces/Permitted occupancy
- $60 \text{ occupants} * 0.33 = 20$ spaces

Spa (Use "Personal or Business Service")**Note: Space is only for "H" guests, not the public.**

- 2 spaces/treatment station
- 1 station = 2 spaces

Guest Rooms (Use "Bed and Breakfast")

- 1.5 per guest bedroom plus 2 spaces
- Presume 20 rooms
- $(20 * 1.5) + 2 = 32$ spaces

TOTAL SPACES REQUIRED FOR NEW PROJECT

- $44 + 20 + 2 + 32 = \underline{\underline{98 \text{ spaces}}}$
- Spaces provided = 73 spaces

EXISTING SITE

- 0.5 spaces/1000 GFA + 1 space/employee
- 150 employees = 150 spaces
- $(84,000 \text{ s.f.}/1000) * 0.5 = 42$ spaces
- Total required spaces = 192 spaces
- Total existing spaces = 216 spaces

FULL BUILDOUT

- Required = $192 + 98 = \underline{\underline{289 \text{ spaces}}}$
- Proposed = $216 + 73 = \underline{\underline{289 \text{ spaces}}}$

Planting Schedule: Trees

Trees (deciduous)									
Quantity									
Inside Lake Setback	Outside Lake Setback	Code	Scientific Name	Common Name	Native Range	Size	Unit Price	Subtotal	Installed
1	0	AR	ACER rubrum	Red Maple	VT	4" cal	\$ 382	\$ 382	\$ 1,146.00
11	1	BP	BETULA populifolia 'Whitespire'	Gray Birch	Northeast	3" cal	\$ 317	\$ 3,804	\$ 11,412.00
1	0	SN	SALIX nigra	Black Willow	VT	10'	\$ 192	\$ 192	\$ 576.00
0	3	NS	NYSSA sylvatica	Tupelo	VT	3" cal	\$ 414	\$ 1,242	\$ 3,726.00
0	3	OV	OSTRYA virginiana	American Hophornbeam	VT	2" cal	\$ 207	\$ 621	\$ 1,863.00
0	1	QR	QUERCUS rubra	Red Oak	VT	3"	\$ 373	\$ 373	\$ 1,119.00
1	5	TA	TILIA americana	Basswood	VT	3"	\$ 295	\$ 1,770	\$ 5,310.00
0	5	GT	GLEDITSIA tricanthos var. inermis 'Shademaster'	Shademaster Thornless Honey	Southeast	3" cal	\$ 317	\$ 1,585	\$ 4,755.00
0	5	BN	BETULA nigra 'Cully'	Cully' River Birch	VT	3" cal	\$ 317	\$ 1,585	\$ 4,755.00
0	4	AF	ACER x freemanii 'Autumn Blaze'	Autumn Blaze Hybrid Maple	VT	3" cal	\$ 295	\$ 1,180	\$ 3,540.00
0	2	CeO	CELTIS occidentalis	Hackberry	VT	3" cal	\$ 338	\$ 676	\$ 2,028.00
2	7	ASGM	ACER saccharum 'Green Mountain'	Green Mountain Sugar Maple	VT	3" cal	\$ 317	\$ 2,853	\$ 8,559.00
1	0	AP	ACER pensylvanicum	Striped Maple	VT	2" cal	\$ 202	\$ 202	\$ 606.00
6	0	PV	PRUNUS virginiana	Chokecherry	VT	4" Cal	\$ 371	\$ 2,226	\$ 6,678.00
2	5	CCG	CRATAEGUS crus-galli inermis 'Cruzam'	Crusader Thornless Cockspur	VT	2"	\$ 177	\$ 1,239	\$ 3,717.00
Total qty:	25	41						Subtotal	\$ 59,790.00

Evergreen trees and shrubs

Quantity									
Inside Lake Setback	Outside Lake Setback	Code	Scientific Name	Common Name	Native Range	Size	Unit Price	Subtotal	Installed
1	12	AB	ABIES balsamea	Balsam Fir	VT	6'	\$ 165	\$ 2,145	\$ 6,435.00
0	4	PG	PICEA glauca	White Spruce	VT	5'	\$ 135	\$ 540	\$ 1,620.00
1	5	JV	JUNIPERUS virginiana	Eastern Red Cedar	VT	6'	\$ 165	\$ 990	\$ 2,970.00
6	0	TO	THUJA occidentalis	White Cedar	VT	10'	\$ 389	\$ 2,334	\$ 7,002.00
0	7	TON	THUJA occidentalis 'Nigra'	Dark American Arborvitae	VT	8'	\$ 266	\$ 1,862	\$ 5,586.00
0	5	TxH	TAXUS x 'Hicksii'	Hick's Yew	Not Native	30"	\$ 59	\$ 294	\$ 881.25
0	9	PJM	RHODODENDRON 'PJM Elite'	PJM Rhododendron	Not Native	36"	\$ 84	\$ 758	\$ 2,274.75
6	3	IG	ILEX glabra 'Shamrock'	Inkberry Holly	New England	#7	\$ 82	\$ 738	\$ 2,214.00
0	12	TOS	THUJA occidentalis 'Smaragd'	Emerald Green Arborvitae	VT	8'	\$ 266	\$ 3,192	\$ 9,576.00
0	22	JS	JUNIPERUS 'Sea Green'	Sea Green Juniper	Not Native	30"	\$ 49	\$ 1,078	\$ 3,234.00
0	2	TCP	TSUGA canadensis 'Pendula'	Dwarf Weeping Hemlock	VT	5-6' B&B	\$ 595	\$ 1,190	\$ 3,570.00
Total qty:	14	81						Subtotal	\$ 45,363.00

Planting Schedule: Shrubs and Perennials

Shrubs and Woody Groundcovers

Quantity									
Inside Lake Setback	Outside Lake Setback	Code	Scientific Name	Common Name	Native Range	Size	Unit Price	Subtotal	Installed
0	51	AU	ARCTYSTAPHYLOS uva-ursi	Bearberry	VT	6" #1	\$ 14	\$ 714	\$ 2,142.00
54	22	AM	ARONIA melanocarpa	Black Chokeberry	VT	#10	\$ 66	\$ 5,016	\$ 15,048.00
21	9	CA	CORYLUS americana	American Hazelnut	VT	36" #5	\$ 62	\$ 1,860	\$ 5,580.00
27	0	SS	SALIX exigua ssp. 'Interior'	Sandbar Willow	VT	6' B&B	\$ 119	\$ 3,213	\$ 9,639.00
18	0	SC	SAMBUCUS canadensis	Black Elderberry	VT	#3	\$ 31	\$ 558	\$ 1,674.00
99	0	VAN	VACCINIUM angustifolium 'Brunswick'	Low Sweet Blueberry	VT	#3	\$ 38	\$ 3,713	\$ 11,137.50
33	11	DL	DIERVILLA Ionicera	Bush Honeysuckle	VT	#5	\$ 48	\$ 2,112	\$ 6,336.00
23	8	SA	SYMPHORICARPOS albus	Snowberry	VT	#2	\$ 31	\$ 961	\$ 2,883.00
2	2	HV	HAMAMELIS virginiana	Witch-hazel	VT	6-7' B&B	\$ 246	\$ 984	\$ 2,952.00
4	22	HA	HYDRANGEA arborescens	Smooth Hydrangea	Southeast	#5	\$ 35	\$ 910	\$ 2,730.00
12	18	FG	FOTHERGILLA gardenii	Dwarf Witch-Alder	Southeast	4-5' B&B	\$ 300	\$ 9,000	\$ 27,000.00
20	3	VA	VIBURNUM acerifolium	Maple-leaved Viburnum	VT	#3	\$ 49	\$ 1,127	\$ 3,381.00
7	3	ST	STAPHYLEA trifolia	Bladdernut	VT	#5	\$ 70	\$ 700	\$ 2,100.00
0	3	SV	SYRINGA vulgaris 'Monge'	Dark Purple Common Lilac	Not native	6' B&B	\$ 245	\$ 735	\$ 2,205.00
0	16	STO	SPIREA tomentosa	Steeplebush	VT	2 Gal	\$ 24	\$ 384	\$ 1,152.00
0	19	PF	POTENTILLA fruticosa 'Pink Beauty'	Shrubby Cinquefoil	VT	#5	\$ 39	\$ 741	\$ 2,223.00
0	6	PO	PHYSOCARPUS opulifolius	Common Ninebark	VT	24" #5	\$ 28	\$ 168	\$ 504.00
0	24	RAG	RHUS aromatica 'Grow Low'	Grow Low Fragrant Sumac	VT	6" #1	\$ 14	\$ 336	\$ 1,008.00
24	6	CSAF	CORNUS sericea 'Arctic Fire'	Arctic Fire Dogwood	VT	#7	\$ 69	\$ 2,070	\$ 6,210.00
Total qty:	344	223						Subtotal	\$ 105,904.50

Shade Perennial Matrix (S.P.M.)

Quantity									
Inside Lake Setback	Outside Lake Setback	Code	Scientific Name	Common Name	Native Range	Size	Unit Price	Subtotal	Installed
112	274	A	CAREX pensylvanica	Pennsylvania Sedge	VT	2 qt	14.00	\$ 5,404	\$ 14,590.80
71	183	B	ATHYRIUM felix-femina	Lady Fern	VT	2 qt	14.00	\$ 3,556	\$ 9,601.20
84	146	C	DRYOPTERIS marginalis	Marginal Wood Fern	New England	2 Qt	17.00	\$ 3,910	\$ 10,557.00
79	153	D	CAREX platyphylla	Broad-leaved sedge	VT	2 Qt	17.00	\$ 3,944	\$ 10,648.80
35	67	E	CAREX blanda	Common wood sedge	Northeast	2 Qt	14.00	\$ 1,428	\$ 3,855.60
21	61	F	TIARELLA cordifolia	Foamflower	VT	1 qt	\$ 9	\$ 738	\$ 1,992.60
Total qty:	402	884						Subtotal	\$ 51,246.00

Other Perennials

Qty.		Code	Scientific Name	Common Name		Size	Unit Price	Subtotal	Installed
0	84	OC	OSMUNDA cinnamomea	Cinnamon Fern	VT	1 gal	11.00	\$ 924	\$ 2,494.80
0	11	AMT	ACHILLEA millefolium 'Salmon Beauty'	Salmon Beauty Yarrow	VT	#2	15.00	\$ 165	\$ 445.50
0	18	CAP	CLEMATIS alpina 'Pamela Jackman'	Alpine Clematis	Not native	#2	38.00	\$ 684	\$ 1,846.80
0	20	CV	COREOPSIS verticillata 'Moonbeam'	Moonbeam Tickseed	Southeast	#2	12.50	\$ 250	\$ 675.00
0	33	FGE	FESTUCA glauca 'Elijah Blue'	Blue Fescue	Not native	#1	12.00	\$ 396	\$ 1,069.20
0	71	NWL	NEPETA x faasenii ' Walker's Low'	Walker's Low Catmint	Not native	#2	13.75	\$ 976	\$ 2,635.88
0	15	CB	CALAMAGROSTIS brachytricha	Korean Feather Reed Grass	Not native	#1	\$ 12	\$ 180	\$ 486.00
Total qty:	0	252						Subtotal	\$ 9,653.18

Seed Mixes

Qty.		Code	Scientific Name	Application Rate		Unit Size	Price/unit	Subtotal	Installed
3			Vermont Wetland Hummock Mix	20lbs per acre	VT	Pound	140.00	\$ 420	\$ 500.00

3			Shortgrass Woods Edge or Savanna Seed Mix	10 lbs per acre	Northeast	1000 sf coverage	73.00	\$ 219	\$ 300.00
14			VT Native Custom Steep Slope Erosion Control Mix (10,000 sf)	60 lbs/ acre	VT	Pound	\$ 17	\$ 238	\$ 300.00
								<i>Subtotal</i>	\$ 1,100.00
.									
			Green Roof Allowance						

TOTAL\$ 273,056.68



To: Greenfield Growth Consulting
c/o Benjamin Avery

Date: January 21, 2025
Revised May 5, 2025

Memorandum

Project #: 59245.00

From: Jennifer Conley, PE, PTOE

Re: H Residential and Restaurant Traffic Impact Memorandum

Introduction

Vanasse Hangen Brustlin (VHB) has been requested to conduct a traffic impact analysis for a proposed mixed-use development located at 166 and 180 West Lakeshore Drive in Colchester, Vermont. The project aims to establish a site comprising 20 inn rooms in small cottages and a 48-seat restaurant. As part of the permitting process, a comprehensive transportation analysis is required to assess the potential impacts of the development on local traffic conditions. The following memorandum involves analyzing existing traffic volumes, projecting future trip generation, and evaluating the operational efficiency of the site driveway intersection.

Access and Circulation


The proposed project aims to enhance site access and driveway efficiency while mitigating environmental impacts. The current design includes two new curb cuts, each approximately 45 feet in width to be placed on West Lakeshore Drive. This new configuration reduces the existing three curb cuts, which total about 270 feet, to two shorter curb cuts, significantly lessening the impervious surface and preserving the site's natural slopes. The entrances and exits—located at the south and north ends of the site, respectively—align with the curb cuts on the Hazelett property across the street, supporting a streamlined and cohesive traffic flow.

The one-way driveway will lead to five parallel parking spaces in front of the main building, primarily designated for check-in and drop-offs. The main parking area is situated across the road to optimize space usage and site organization.

Additionally, the project includes enhancements to the south marina area access through a reconfigured two-way driveway, which includes a turnaround and six parking spaces. Similarly, the Hazelett employee recreation area will benefit from a revised two-way driveway, designed exclusively for drop-offs, loading, and unloading, with no permanent parking spaces.

The proposed layout of the project site is shown below in Figure 1.

Figure 1 Proposed Site Plan



Existing Conditions

To establish a baseline for assessing the traffic impact of the proposed mixed-use development, VHB collected traffic volume data at the proposed project site location. This data provides a detailed account of current traffic conditions, capturing the two-way traffic volumes along West Lakeshore Drive and traffic generated by the Hazelett property adjacent to the site.

Traffic Volume Data

Turning movement count data was collected by VHB on Tuesday, April 29, 2025, at both existing driveways to the Hazelett property on West Lakeshore Drive. Data collection was conducted over a continuous 24-hour period to capture both the AM and PM peak travel periods. The full traffic count data are provided in the appendix.

Seasonal adjustment factors were derived utilizing data from VTrans permanent count stations (D001 and D040) to ensure the field-collected data reflected typical conditions at the site throughout the year.

D001

- › 2024 DHV-30: 1,429
- › April 30, 2024, Peak Hour Volume: 1,380
- › Adjustment Factor = 1.036

D040

- › 2024 DHV-30: 1,749
- › April 30, 2024, Peak Hour Volume: 1,668
- › Adjustment Factor = 1.049

Because both continuous count stations showed similar adjustment factors, an average was taken between the two to come up with an adjustment factor for the counts (1.043).

Trip Generation

Trip generation estimates for the proposed residential units and restaurant space are calculated based on industry standards and number of dwelling units and seats respectively. Trip estimates were calculated based on rates published by the Institute of Transportation Engineers (ITE) in the 11th edition of the Trip Generation Manual for the weekday AM and PM peak hours. As such, trip generation rates were calculated using the ITE land use code (LUC) for Single-Family Detached Housing (LUC 210) and High-Turnover (Sit-Down) Restaurant (LUC 932) assuming an estimate of 20 dwelling units and 48 restaurant seats. In addition, the housing land use code selected is more conservative than using a land use for a more recreational housing style. To remain conservative, the peak hour trips of the restaurant (which may occur later than the roadway peak hour of 4:30 to 5:30 PM) were selected to be added to the peak roadway traffic presenting a worst case scenario. The total unadjusted trip generation of the site is anticipated to be 49 AM and 59 PM peak hour trips. The trip generation data is provided in Table 1 below.

Table 1 Trip Generation Summary

Peak Period	Residential (LUC 210) 20 Dwelling Units	Restaurant (LUC 932) 48 Seats	Total Trips
AM Peak Hour			
Enter	6	17	23
<u>Exit</u>	<u>15</u>	<u>11</u>	<u>26</u>
Total	21	28	49
PM Peak Hour			
Enter	15	19	34
<u>Exit</u>	<u>8</u>	<u>17</u>	<u>25</u>
Total	23	36	59

As shown above, the development is not anticipated to exceed the Vermont Agency of Transportation (VTrans) threshold of 75 peak hour trips at any intersection.

Trip Distribution and Assignment

Travel patterns of project trips to and from the proposed site are based on existing travel patterns along West Lakeshore Drive as shown in Table 2 and are based on the turning movements counts collected on April 29, 2025.

Table 2 Trip Distribution

	AM Peak Hour	PM Peak Hour
West Lakeshore Drive Westbound	40%	60%
West Lakeshore Drive Eastbound	60%	40%

All project trips are assumed to be primary trips. With no pass-by trips, all project trips are expected to start or end at the proposed driveways on West Lakeshore Drive. New vehicle trips were assigned based on the distribution above.

Traffic Analysis

The operations at the Site Driveway with West Lakeshore Drive were evaluated. Intersection capacity analyses were performed for the subject intersection in the AM and PM peak hours for the typical weekday. Level of service (LOS) and average vehicle delay were evaluated using simulations developed with Synchro/SimTraffic Version 12. Each simulation was conducted using industry standard parameters and software settings. All simulations results reported in this evaluation are the average of five modeling runs.

The term "level of service" (LOS) is used to denote the different operating conditions that occur on a given roadway segment under various traffic volume loads. It is an indicator of travel speed, delay, and freedom to maneuver. Level of service provides an index to the operational qualities of a roadway segment or an intersection. Level of service ranges from A to F, with LOS A representing free flow operating conditions and LOS F representing congested operating conditions.

For unsignalized intersections, the analysis assumes that traffic on the mainline is not affected by traffic on the side streets. Thus, the LOS designation is for the critical movement exiting the side street and is typically the left turn out of the side street or site driveway.

Table 3 Level of Service and Delay Summary – Unsignalized Intersections

Level of Service	Unsignalized Intersection Delay (sec)
A	<10.0
B	10.1 – 15.0
C	15.1 – 25.0
D	25.1 – 35.0
E	35.1 – 50.0
F	>50.0

Intersection Operations Analysis Results

The following Tables 4 and 5 summarize the traffic operation analysis results at both the site entrance and exit after occupancy. At unsignalized intersections, such as the site driveways with West Lakeshore Drive, LOS is typically focused on the delay experienced by vehicles making critical movements, such as left turns from the side street onto the main street. The results of the capacity analysis at the site entrance (Table 4) show that during both the AM and PM peak hours, eastbound and westbound approaches on West Lakeshore Drive operate at LOS A, while the northbound movement from the Hazelett property operates at a LOS C during the AM peak hour and LOS B during the PM peak hour.

Similarly, the capacity analysis at the site exit (Table 5) shows that during the AM and PM peak hours, the site exit operates at LOS B and LOS C respectively. The primary movements on West Lakeshore Drive maintain LOS A for both AM and PM peak hours.

These results indicate that all movements at the site driveway will operate efficiently. These levels are within acceptable limits for unsignalized, two-way stop-controlled intersections, and the project is not anticipated to negatively impact the adjacent roadway network.

Table 4 West Lakeshore Drive / Site Entrance Capacity Analysis Results

Approach	2025 Build		
	Delay ¹	LOS ²	Q95 ³
AM Peak Hour			
West Lakeshore Drive EB	2.0	A	47
West Lakeshore Drive WB	1.0	A	71
Hazelett Property NB	20.6	C	37
PM Peak Hour			
West Lakeshore Drive EB	2.7	A	79
West Lakeshore Drive WB	0.8	A	18
Hazelett Property NB	15.0	B	52

¹Delay expressed in seconds per vehicle

²Level of Service

³95th percentile queue length expressed in vehicle length

Table 5 West Lakeshore Drive / Site Exit Capacity Analysis Results

Approach	2025 Build		
	Delay ¹	LOS ²	Q95 ³
AM Peak Hour			
West Lakeshore Drive EB	0.6	A	0
West Lakeshore Drive WB	1.5	A	94
Hazelett Property NB	12.5	B	34
Site Exit SB	12.6	B	35
PM Peak Hour			
West Lakeshore Drive EB	0.6	A	0
West Lakeshore Drive WB	1.5	A	13
Hazelett Property NB	8.4	A	51
Site Exit SB	17.8	C	35

¹Delay expressed in seconds per vehicle

²Level of Service

³95th percentile queue length expressed in vehicle length

Conclusions

Based on the analysis, the proposed mixed-use development at 166 and 180 West Lakeshore Drive in Colchester, Vermont, is expected to have manageable impacts on local traffic conditions. Key findings from the traffic impact study are summarized below:

1. Baseline Traffic Conditions and Growth Projections:
 - VHB collected 2025 turning movement count data at both existing three-way intersections of West Lakeshore Drive and Hazelett property driveways. A seasonal adjustment factor was developed based on data from continuous VTrans count stations and applied to the measured traffic volumes to establish typical year-round volumes at the site.
2. Trip Generation Estimates:
 - Using the ITE Trip Generation Manual (11th Edition), the site was estimated to generate 49 trips during the AM peak hour and 59 trips during the PM peak hour. This is well below the Vermont Agency of Transportation's threshold of 75 peak hour trips for requiring additional analysis.
3. Intersection Capacity Analysis:
 - The site's entrance and exit intersections with West Lakeshore Drive were evaluated. The analysis showed that, under 2025 conditions with the project in place, the driveways would operate at acceptable levels of service (LOS) during both AM and PM peak hours, and trips associated with the proposed development are not anticipated to negatively impact the adjacent roadway network.



Memorandum

Appendix

Peak Hour Traffic Volumes

		Existing Conditions Volumes (Cars + Heavy Vehicles)															
		Northbound (Hazelett Driveway)				Southbound (Site)				Eastbound (W Lakeshore Dr)				Westbound (W Lakeshore Dr)			
Peak Hour		U Turns	Left	Thru	Right	U Turns	Left	Thru	Right	U Turns	Left	Thru	Right	U Turns	Left	Thru	Right
		West Driveway (Site Entrance)															
		0	0	0	1	0	0	0	0	0	0	738	4	0	23	461	0
AM	7:15 AM to 8:15 AM																
PM	4:30 PM to 5:30 PM	0	8	0	20	0	0	0	0	0	0	542	2	0	3	796	0
		East Driveway (Site Exit)															
AM	7:15 AM to 8:15 AM	0	0	0	0	0	0	0	0	0	0	740	2	0	12	479	0
PM	4:30 PM to 5:30 PM	0	4	0	17	0	0	0	0	0	0	564	0	0	2	794	0


Total
1227
1371
1233
1381

		Seasonal Adjustment Volumes (Cars + Heavy Vehicles)															
		Northbound (Hazelett Driveway)				Southbound (Site)				Eastbound (W Lakeshore Dr)				Westbound (W Lakeshore Dr)			
Peak Hour		U Turns	Left	Thru	Right	U Turns	Left	Thru	Right	U Turns	Left	Thru	Right	U Turns	Left	Thru	Right
		West Driveway (Site Entrance)															
		0	0	0	1	0	0	0	0	0	0	770	4	0	24	481	0
AM	7:15 AM to 8:15 AM																
PM	4:30 PM to 5:30 PM	0	8	0	21	0	0	0	0	0	0	565	2	0	3	830	0
		East Driveway (Site Exit)															
AM	7:15 AM to 8:15 AM	0	0	0	0	0	0	0	0	0	0	772	2	0	13	500	0
PM	4:30 PM to 5:30 PM	0	4	0	18	0	0	0	0	0	0	588	0	0	2	828	0


Seasonal adjustment factor =	1.043
------------------------------	-------

Seasonal Adjustment

AM Peak Hour




PM Peak Hour




Trip Assignment

AM Peak Hour




PM Peak Hour




2025 Build

AM Peak Hour



PM Peak Hour





Colchester Fire District No. 2

P.O. Box 4, 838 Church Road
Colchester, Vermont 05446
(802) 862-4621 Fax (802) 862-0988

Prudential Committee

K. Michael Whalen
Joseph Hart
Angela MacDonald
Charles Thackara
Brad Martin

District Administrator

Jeffrey Bessette

Administrative Assistant

Erika Albrecht

Water Operators

Jeffrey Shappy
Brian Martin

Clerk

Renee Barrett

Treasurer

Donna Hart

Assistant Treasurer

Sharon Bessette

Scott Homsted, P.E.
Krebs & Lansing Consulting Engineers, Inc.
164 Main Street
Colchester, Vermont 05446

Re. 180 West Lakeshore Drive

Dear Scott,

The District has received your request for a water allocation. The property is located at 180 West Lakeshore Drive in the Town of Colchester. This property is the former site of the Beach and Boat Motel. The proposed project will be as follows:

Dining: 48 seats x 27gpd (2 meals/day) = 1296gpd

Meeting Space: 60 participants x 4gpd = 240

Spa: 1 massage therapist x 32gpd = 32gpd
8 participants x 4gpd = 32gpd

Guest Rooms: Main Building: 1 Owner Bedroom x 140gpd = 140gpd
Cottages: 46 sleeping spaces x 50gpd = 2300gpd
Future Building: 6 sleeping spaces x 50gpd = 300 gpd

The total project will be 4340gpd

The District has approved the total allocation of 4340gpd.

If you have any questions, please call me at the District office.

Thank you, Jeff Bessette

*Our Commitment to our Customers
"Service, Quality and Reliability".*

HAZELETT INN (THE "H") WASTEWATER FLOWS WORKSHEET**EXISTING ALLOCATION = 4,482 GALLONS/DAY (gpd)**

(Per WW-C-0671 for a 166 seat restaurant serving 2 meals/day))

PROPOSED PROJECTDining

- 40 seats x 27 gpd (2 meals/day) = 1080 gpd

Meeting Space

- 60 participants x 4 gpd/participant = 240 gpd

Spa

- 1 massage therapist x 32 gpd = 32 gpd
- Only guests will use the spa, therefore no additional flows for users.

Guest Rooms

- **Main Building**
Staff Manager/Owner Bedroom = 140 gpd
- **Cottages**
54 TOTAL sleeping spaces x 50 gpd = 2700 gpd


Meals Served Only to Guests

- 54 sleeping spaces x 5 gpd = 270 gpd



TOTAL PROPOSED DESIGN FLOW = 4,462 gpd

WQv Modeling

WQv





H-Post1



Forebay

Gravel Wet#1



Routing Diagram for The-H

Prepared by Krebs & Lansing Consulting Engineers, Inc., Printed 3/3/2025
HydroCAD® 10.00 s/n 06429 © 2013 HydroCAD Software Solutions LLC

The-H

Prepared by Krebs & Lansing Consulting Engineers, Inc.
HydroCAD® 10.00 s/n 06429 © 2013 HydroCAD Software Solutions LLC

Printed 3/3/2025
Page 2

Project Notes

The H at Malletts Bay
Post Development Stormwater Model

The-H

Prepared by Krebs & Lansing Consulting Engineers, Inc.
HydroCAD® 10.00 s/n 06429 © 2013 HydroCAD Software Solutions LLC

Type II 24-hr WQv Rainfall=1.00"

Printed 3/3/2025

Page 3

Summary for Subcatchment 5S: H-Post1

Runoff = 3.19 cfs @ 12.04 hrs, Volume= 0.189 af, Depth= 0.56"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-120.00 hrs, dt= 0.05 hrs
Type II 24-hr WQv Rainfall=1.00"

Area (ac)	CN	Description
* 4.020	95	watershed area
4.020		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.2	960	0.0198	1.31		Lag/CN Method, lag CN

Subcatchment 5S: H-Post1

Hydrograph



Summary for Pond 15P: Gravel Wet#1

Inflow Area = 4.020 ac, 0.00% Impervious, Inflow Depth = 0.56" for WQv event
 Inflow = 3.19 cfs @ 12.04 hrs, Volume= 0.189 af
 Outflow = 0.13 cfs @ 14.13 hrs, Volume= 0.189 af, Atten= 96%, Lag= 125.1 min
 Primary = 0.13 cfs @ 14.13 hrs, Volume= 0.189 af

Routing by Stor-Ind method, Time Span= 5.00-120.00 hrs, dt= 0.05 hrs

Starting Elev= 125.67' Surf.Area= 5,280 sf Storage= 3,258 cf

Peak Elev= 127.23' @ 14.13 hrs Surf.Area= 9,840 sf Storage= 7,854 cf (4,596 cf above start)

Plug-Flow detention time= 771.0 min calculated for 0.114 af (60% of inflow)

Center-of-Mass det. time= 416.7 min (1,243.3 - 826.7)

Volume	Invert	Avail. Storage	Storage Description
#1	122.33'	3,168 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 7,920 cf Overall x 40.0% Voids
#2	125.33'	177 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 1,769 cf Overall x 10.0% Voids
#3	126.00'	14,045 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
		17,390 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
122.33	2,640	0	0
125.33	2,640	7,920	7,920

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
125.33	2,640	0	0
126.00	2,640	1,769	1,769

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
126.00	2,640	0	0
127.00	4,354	3,497	3,497
128.00	5,260	4,807	8,304
129.00	6,222	5,741	14,045

50% of WQv in
stone voids

Device	Routing	Invert	Outlet Devices
#1	Primary	125.67'	15.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 125.67' / 125.33' S= 0.0170 ' /' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.23 sf
#2	Device 1	125.67'	2.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	127.30'	30.0" W x 6.0" H Vert. Orifice/Grate C= 0.600

Primary OutFlow Max=0.13 cfs @ 14.13 hrs HW=127.23' (Free Discharge)


1=Culvert (Passes 0.13 cfs of 4.50 cfs potential flow)

2=Orifice/Grate (Orifice Controls 0.13 cfs @ 5.85 fps)

3=Orifice/Grate (Controls 0.00 cfs)

Pond 15P: Gravel Wet#1

Hydrograph




Summary for Pond 263P: Forebay

Volume	Invert	Avail.Storage	Storage Description
#1	123.00'	1,096 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
123.00	96	0	0
124.00	244	170	170
125.00	449	347	517
126.00	710	580	1,096


10% of WQv in
forebay

25 Year Storm
Modeling


25Yr





H-Pre1



H-Post1



Gravel Wet#1



Routing Diagram for The-H

Prepared by Krebs & Lansing Consulting Engineers, Inc., Printed 3/3/2025
HydroCAD® 10.00 s/n 06429 © 2013 HydroCAD Software Solutions LLC

The-H

Prepared by Krebs & Lansing Consulting Engineers, Inc.
HydroCAD® 10.00 s/n 06429 © 2013 HydroCAD Software Solutions LLC

Printed 3/3/2025
Page 2

Project Notes

The H at Malletts Bay
Post Development Stormwater Model

The-H

Prepared by Krebs & Lansing Consulting Engineers, Inc.

HydroCAD® 10.00 s/n 06429 © 2013 HydroCAD Software Solutions LLC

Type II 24-hr 25 year Rainfall=3.81"

Printed 3/3/2025

Page 3

Summary for Subcatchment 11S: H-Post1

Runoff = 14.34 cfs @ 12.06 hrs, Volume= 0.950 af, Depth> 2.84"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-120.00 hrs, dt= 0.05 hrs
Type II 24-hr 25 year Rainfall=3.81"

Area (ac)	CN	Description
* 4.020	91	watershed area
4.020		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.7	960	0.0198	1.09		Lag/CN Method, lag CN

Subcatchment 11S: H-Post1

Hydrograph



The-H

Prepared by Krebs & Lansing Consulting Engineers, Inc.

HydroCAD® 10.00 s/n 06429 © 2013 HydroCAD Software Solutions LLC

Type II 24-hr 25 year Rainfall=3.81"

Printed 3/3/2025

Page 4

Summary for Subcatchment 14S: H-Pre1

Runoff = 7.61 cfs @ 12.17 hrs, Volume= 0.632 af, Depth= 1.89"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-120.00 hrs, dt= 0.05 hrs
Type II 24-hr 25 year Rainfall=3.81"

Area (ac)	CN	Description
* 4.020	80	watershed area
4.020		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
23.5	1,015	0.0187	0.72		Lag/CN Method, lag CN

Subcatchment 14S: H-Pre1

Hydrograph



Summary for Pond 12P: Gravel Wet#1

Inflow Area = 4.020 ac, 0.00% Impervious, Inflow Depth > 2.84" for 25 year event
 Inflow = 14.34 cfs @ 12.06 hrs, Volume= 0.950 af
 Outflow = 7.22 cfs @ 12.22 hrs, Volume= 0.950 af, Atten= 50%, Lag= 9.8 min
 Primary = 7.22 cfs @ 12.22 hrs, Volume= 0.950 af

Routing by Stor-Ind method, Time Span= 5.00-120.00 hrs, dt= 0.05 hrs

Starting Elev= 125.67' Surf.Area= 5,280 sf Storage= 3,258 cf

Peak Elev= 128.92' @ 12.22 hrs Surf.Area= 11,423 sf Storage= 16,883 cf (13,625 cf above start)

Plug-Flow detention time= 228.6 min calculated for 0.875 af (92% of inflow)

Center-of-Mass det. time= 158.5 min (959.6 - 801.2)

Volume	Invert	Avail.Storage	Storage Description
#1	122.33'	3,168 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 7,920 cf Overall x 40.0% Voids
#2	125.33'	177 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 1,769 cf Overall x 10.0% Voids
#3	126.00'	14,045 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
		17,390 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
122.33	2,640	0	0
125.33	2,640	7,920	7,920

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
125.33	2,640	0	0
126.00	2,640	1,769	1,769

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
126.00	2,640	0	0
127.00	4,354	3,497	3,497
128.00	5,260	4,807	8,304
129.00	6,222	5,741	14,045


Device	Routing	Invert	Outlet Devices
#1	Primary	125.67'	15.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 125.67' / 125.33' S= 0.0170 ' / ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.23 sf
#2	Device 1	125.67'	2.0" Vert. Orifice/Grate C= 0.600
#3	Device 1	127.30'	30.0" W x 6.0" H Vert. Orifice/Grate C= 0.600

Primary OutFlow Max=7.19 cfs @ 12.22 hrs HW=128.91' (Free Discharge)

- 1=Culvert (Passes 7.19 cfs of 7.54 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.19 cfs @ 8.55 fps)
- 3=Orifice/Grate (Orifice Controls 7.00 cfs @ 5.60 fps)

Pond 12P: Gravel Wet#1

Hydrograph



Attachment 1: Narrative, Location Map, and Soils Map

The “H” at Mallets Bay

1. Introduction

Krebs and Lansing Consulting Engineers Inc. (K&L) are writing on behalf of Summit Properties to apply for a State Stormwater Discharge Permit pursuant to General Permit 3-9050 for the H at Mallets Bay project located on West Lakeshore Drive in Colchester.

2. Project Description

The applicant proposes a redevelopment of the Hazelett waterfront parcels located at 166 and 180 West Lakeshore Drive, entitled “The H at Mallets Bay”. This will be a hospitality project comprised of an Inn with a series of 5 cottages and a total of 20 rooms. In addition, the centerpiece of the project is a main building with a 48-seat restaurant at the main level, event space, and spa facilities. A new bathhouse will be constructed as well to enable beach users to use the facilities without having to go back the cottages/main building. New parking will be constructed across the street at 135 West Lakeshore Drive.

Stormwater treatment for the site will involve site balancing and a new Gravel Wetland #1 and a Simple Disconnection. A pre-treatment forebay will be used in conjunction with Gravel Wetland #1.

3. Existing Condition

The existing site at 166 and 180 West Lakeshore Drive is the site of a demolished hotel. There is a large curb cut along West Lakeshore Drive and existing paved parking. A driveway to the west serves as access to a small marina. A driveway to the east serves as access to the waterfront from Hazelett employees.

The site of the proposed parking and Gravel Wetland #1 is 135 West Lakeshore Drive. This site contains the existing Hazelett manufacturing facility and associated drives and parking.

Existing soil types on this portion of both sites are Belgrade and Eldridge soils. These soils are classified as type D by the U.S. Soil Conservation Service, which indicates a high degree of runoff and low infiltrative capacity.

4. Existing Stormwater System

The 166/180 West Lakeshore Drive site has no existing stormwater infrastructure other than an existing municipal storm drain that outlets on the westerly side of the property.

The 135 West Lakeshore Drive site is divided into two main watersheds. The southeastern portion of the site drains to a series of catch basins and enclosed piping prior to being directed to an existing wet pond. The northwest portion of the site drains to catch basins and piping that discharge directly to the drainage swale along West Lakeshore Drive. This swale crosses West Lakeshore Drive and discharges directly to Lake Champlain via an existing culvert.

5. Proposed Stormwater System:

The proposed stormwater collection, treatment, and detention system will site balancing and a gravel wetland, along with a simple disconnection for treatment.

The 166 and 180 West Lakeshore Drive site features a relatively steep bank down to a waterfront area. All of the waterfront is in a shoreland protection zone. To avoid disturbance associated with a large-scale stormwater management practice in the lakeshore protection area, site balancing of existing impervious surface at the 180 West Lakeshore Drive site is proposed. The following is a summary of the proposed treatment:

- Impervious area at 166 and 180 W. Lakeshore Drive = 0.66 acres
- New Impervious at 135 W. Lakeshore Drive = 0.60 acres
- Total required area to be treated = 1.26 acres
- Area of total impervious area to be treated via Gravel Wetland #1 = 2.17 acres.

Therefore, the proposed treatment exceeds what is required.

The treatment will be provided by Gravel Wetland #1. Runoff will be directed to the gravel wetland via a series of catch basins and enclosed drainage. The existing pipes outletting directly the West Lakeshore Drive swale will be intercepted with new structures and pipes to direct those flows to the gravel wetland. Pre-treatment will occur in a forebay. The gravel wetland will discharge via a controlled outlet structure and stabilized outfall.

In addition to the gravel wetland, the meandering path along the base of the slope will sheet drain across vegetated terrain in accordance with a Simple Disconnection.

- a) Description of Impervious Area: The proposed permitted area of impervious surface is 2.17 acres. All of this has been treated as new impervious surface. The new impervious surface is from building roofs, paved roads, driveways, parking, and concrete sidewalks and pads.
- b) Receiving Body: S/N001: Lake Champlain.
- c) Fish Habitat Designation for Receiving Water: Warm
- d) Description of compliance with each of the treatment standards in the 2017 VSMM including the treatment practices or waivers used to meet each of the following standards:
 - i) Post-Construction Soil Depth and Quality Standard:

This standard will be met via two options outlined in the VSMM.

Option 1: Areas outside of construction will be left undisturbed and protected from compaction during construction. This option will apply only to the far westerly portion of the site.

Option 2: Remove and stockpile existing topsoil during construction. On site soil testing indicates and existing sandy loam topsoil layer on the site ranging from 7-13 inches in depth. Given that much of the finish site

The “H” at Mallets Bay
Stormwater Narrative

will be covered in building or paving, there will be an excess of existing topsoil to re store other disturbed areas such as setbacks, vegetated islands, swales, and side-slopes. Compost will be incorporated into the existing topsoil stockpile if needed to achieve 4% organic content.

ii) Groundwater Recharge Standard:

The Groundwater Recharge standard is waived because all of the soils on-site are Type D.

iii) Water Quality Treatment Standard (WQ_v):

S/N001: WQ_v will be met for the use of Gravel Wetlands #1. The stone voids in the gravel wetland will store 50% of the WQ_v draining to each wetland. The remaining 50% WQ_v is provided by extended detention using small diameter orifices to release the remaining WQ_v over a 24- hour period. Pre-treatment is provided by a forebay. Additional WQ_v is provided via Simple Disconnection of the meandering path closest to the lakeshore.

iv) Channel Protection Standard (CP_v):

S/N001: The CP_v standard is waived because the site discharges directly to a receiving water with a drainage area of over 10 square miles.

v) Overbank Flood Protection Standard (Q_{P10}):

S/N002: The Overbank Flood Protection Standard is waived because the site discharges directly to a receiving water with a drainage area of over 10 square miles.

vi) Extreme Flood Protection Standard (Q_{P100}):

S/N002: The Extreme Flood Protection Standard is waived because the site discharges directly to a receiving water with a drainage area of over 10 square miles.

The following items are attached for review:

- **Complete NOI form**
- **Attachment 1: Narrative:** Narrative, Location Map, and Soils Map.
- **Attachment 2: Workbooks:** STP Selection Tool and Standards Compliance Workbook
- **Attachment 3: Worksheets:** STP and waiver worksheets, grouped by discharge point
- **Attachment 4: Modeling:** Runoff modeling and calculations demonstrating compliance with the applicable treatment standards.

The “H” at Mallets Bay
Stormwater Narrative

- **Attachment 5: Plans:** Pertinent plan sheets with all required information outlined in Part 7 of the Application Requirements for Operational Permit Document.
- **Payment** in the amount of \$2106.20 to “State of Vermont”.

Location Map

[Insert project specific location map here. You may download topographic map from the [Natural Resource Atlas](#). Please show the site outline, the location of the discharge point(s) and receiving waters. The scale of the location map should be between 1:20,000 and 1:40,000.]

See Attached Location Map.

Soils Map

[Insert project specific soils map here. Soils information can be found at the [Web Soil Survey](#) website. Hydrologic Soil Groups— “HSGs” shall be overlaid with site outline. Soils information can also be provided as data layer on an existing or proposed condition plan sheet (if included as a data layer on one of the plan sheets please indicate that here)]

See Attached Soils Map.



LEGEND

- Hazardous Site
- Hazardous Waste Generators
- Public Water Sources
 - Active
 - Inactive
 - Proposed
 - Active Non-Public, Previously Permitted
 - Inactive Non-Public, Previously Permitted
- Private Wells
 - GPS Located
 - Screen Digitized
 - E911 Address Matched
 - Welldriller/Clarion
 - Unknown Location Method
 - Incorrectly Located
- SurfaceWaterSPA
 - ACTIVE
 - INACTIVE
- Ground Water SPA
 - Active/Shared
 - Proposed
 - Inactive
- Parcels (standardized)
- Stream
 - Stream
 - Intermittent Stream
- Roads
 - Interstate
 - US Highway; 1
 - State Highway
 - Town Highway (Class 1)
 - Town Highway (Class 2,3)
 - Town Highway (Class 4)
 - State Forest Trail
 - National Forest Trail
 - Legal Trail
 - Private Road/Driveway
 - Proposed Roads
- Town Boundary

1: 15,630

1in = 1302 ft.
1cm = 156 meters



794.0 0 397.00 794.0 Meters

WGS_1984_Web_Mercator_Auxiliary_Sphere
© Vermont Agency of Natural Resources. February 27, 2025


DISCLAIMER: This map is for general reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable. ANR and the State of Vermont make no representations of any kind, including but not limited to, the warranties of merchantability, or fitness for a particular use, nor are any such warranties to be implied with respect to the data on this map.

THIS MAP IS NOT TO BE USED FOR NAVIGATION

NOTES

Map created using ANR's Natural Resources Atlas

Soil Map—Chittenden County, Vermont




MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

Special Point Features



Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow



Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot



Sinkhole



Slide or Slip



Sodic Spot



Spoil Area



Stony Spot



Very Stony Spot



Wet Spot



Other



Special Line Features

Water Features



Streams and Canals

Transportation



Rails



Interstate Highways



US Routes



Major Roads



Local Roads

Background



Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:15,800.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Chittenden County, Vermont

Survey Area Data: Version 28, Aug 28, 2024

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jun 18, 2020—Jun 20, 2020

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
AdA	Adams and Windsor loamy sands, 0 to 5 percent slopes	21.3	42.8%
BIA	Belgrade and Eldridge soils, 0 to 3 percent slopes	12.3	24.7%
DdA	Duane and Deerfield soils, 0 to 5 percent slopes	12.4	24.8%
ScA	Scantic silt loam, 0 to 2 percent slopes	0.6	1.1%
TeE	Terrace escarpments, silty and clayey	1.4	2.9%
W	Water	1.9	3.8%
Totals for Area of Interest		49.9	100.0%

Vermont Operational Stormwater Permit - Standards Compliance Workbook

General Discharge Point Information

Project name	The H at Mallets Bay
Discharge point serial number (e.g. S/N 001)	S/N 001
Name of receiving water	Lake Champlain
Latitude (decimal degrees to five decimal places)	44.54664
Longitude (decimal degrees to five decimal places)	-73.21928

Precipitation Data

* Precipitation values shall be obtained from [NOAA Atlas 14](#)

Storm	WQ Storm	1 yr, 24 hr	10 yr, 24 hr	100 yr, 24 hr
Precipitation (inches)	1.00	1.87	3.19	4.76

Drainage Area Information

Pre Development Land Use (acres)

Landuse	A	B	C	D	Total
Grass	0.000	0.000	0.000	2.995	2.995
Meadow	0.000	0.000	0.000	0.000	0.000
Woods	0.000	0.000	0.000	0.000	0.000
Existing Impervious	0.000	0.000	0.000	1.025	1.025
Impervious previously authorized under 2002 VSMM (not included in calculations)					0.000
Total Pre Site Area					4.020

Post Development Land Use (acres)

Landuse	A	B	C	D	Total	%
Grass	0.000	0.000	0.000	1.850	1.850	
Meadow	0.000	0.000	0.000	0.000	0.000	
Woods	0.000	0.000	0.000	0.000	0.000	
New Impervious	0.000	0.000	0.000	1.145	1.145	28.5%
Existing for Permit Coverage (Treated to New Standards)	0.000	0.000	0.000	1.025	1.025	25.5%
Existing Impervious Not for Permit Coverage					0.000	0.0%
Redeveloped Impervious					0.000	0.0%
Impervious previously authorized under 2002 VSMM					0.000	
Total Site Area					4.020	
Total Impervious for Permit Coverage					2.170	
Net Reduced Impervious					0.000	0.0%
Reduced Existing Impervious (for redevelopment)					0.000	0.0%

Information for Calculating T_c by the Watershed Lag Method

	Average Catchment Slope, Y (%)	Hydraulic Length, I (ft)
Pre Development	1.87	1015.00
Post Development	1.98	960.00

Vermont Operational Stormwater Permit - Standards Compliance Workbook

Runoff Calculations	1 yr, 24-hr	10 yr, 24-hr	100 yr, 24-hr
Predevelopment runoff volume (ac-ft)	0.2616	0.6006	1.0564
Pre-routed, post development runoff volume (ac-ft)	0.3723	0.7498	1.2319

Tier 1/Runoff Reduction Practices

List all Tier 1 practices below with the associated treatment volume (T_v). The T_v will be applied to all treatment standards, except for Green Roofs, which do not receive recharge or water quality credit. Please include the appropriate STP worksheet(s) with the application.

Practice	T_v (ac-ft)	Practice	T_v (ac-ft)
Simple Disconnection	0.003		

Runoff Reduction Calculations

Standard	Re	WQ	CP	Q_{P10}	Q_{P100}
T_v Required (ac-ft)	0.0000	0.1795	0.2188	0.2989	0.3549
T_v Provided (ac-ft)	0.0029	0.0029	0.0029	0.0029	0.0029
T_v Remaining (ac-ft)	0.0000	0.1766	0.2159	0.2960	0.3520
Standard met with HCM?	n/a	No	No	No	No
Post-Development CN	n/a	95	92	91	90
CN _{adj}	n/a	94	92	91	90
Pre-Development CN	n/a	n/a	87	86	85

Groundwater Recharge Standard (Re)

Standard Applicable?	<input type="radio"/> Yes <input checked="" type="radio"/> No	Reason recharge not required (if No is selected):	HSG D Soils
Re _v	0.0000		
Standard met with Tier 1 Practices?	n/a		
Recharge Notes:			

Vermont Operational Stormwater Permit - Standards Compliance Workbook

Water Quality Treatment Standard (WQ)

	(ac-ft)		Apply Reduction?
WQ _v - New & Existing	0.1795	% Net Reduction	0.0% <input checked="" type="radio"/> No <input type="radio"/> Yes
WQ _v - Redevelopment	0.0000	% Removed Existing Impervious (Redevelopment)	0.0% <input checked="" type="radio"/> No <input type="radio"/> Yes
Total WQ _v	0.1795		
WQ _v met with Tier 1 practices	0.0029	Is all impervious treated by disconnection?	<input checked="" type="radio"/> No <input type="radio"/> Yes (WQ _v met)
WQ _v to be met with Tier 2 and/or Tier 3 practices	0.1766		

NOTE: Please include a copy of the appropriate STP worksheet(s) with the application.

Tier 2 & 3 Water Quality Practice	WQ _v Provided (ac-ft)	Tier
Gravel Wetland	0.1795	Tier 2
Total WQ _v Provided (ac-ft)	0.1795	ac-ft
Is the WQ _v Standard met?	Yes	

Water Quality Notes:

Channel Protection Standard (CP)

Standard Applicable?	<input type="radio"/> Yes <input checked="" type="radio"/> No	Waiver (if No is selected):	Direct discharge to drainage area ≥10 sq.mi
Standard Met with HCM?	No	The channel protection standard has not been fully met. Either increase Tv credit to fully meet HCM or provide extended detention.	
Provide Extended Detention for:	0.369 ac-ft		
Warm or Cold Water Fishery?	<input checked="" type="radio"/> Cold <input type="radio"/> Warm	→ Provide:	12 hours of extended detention
			OR
		<input type="checkbox"/> The Alternative Extended Detention Method (§2.2.5.4) is being used.	

[See the Vermont Water Quality Standards for warm and cold water designations](#)

Extended Detention STP:

Modeling Info: When demonstrating CP compliance with extended detention in a hydrologic model, use the CN and T_c below if the practice being modelled is not a Tier 1 practice. The CN_{Adj} takes into account the reduction in runoff volume achieved through Tier 1 practices. The T_c is calculated by the watershed lag method using CN_{Adj} as CN'.

CN _{Adj}	92	Post Development T _c (min)	14.3 (Watershed Lag Method)
-------------------	-----------	---------------------------------------	------------------------------------

Channel Protection Notes:

Vermont Operational Stormwater Permit - Standards Compliance Workbook

Overbank Flood Protection (Q_{P10})

Standard Applicable?

☐ Yes ☒ No

Waiver (if No is selected):

Direct discharge to drainage
area ≥ 10 sq.mi

Standard Met with HCM?

No

The Q_{P10} standard has not been fully met. Provide additional STPs to ensure post development peak runoff does not exceed pre development peak runoff for the 10 yr, 24 hour storm event.

STP used:

Pre-development peak discharge rate (cfs)

Pre-routed, post-development peak discharge rate (cfs)

Routed, post-development peak discharge rate (cfs)

Modeling Info: When demonstrating Q_{P10} compliance in a hydrologic model, use the following CN and T_c below, if the practice used to meet Q_{P10} is not itself a Tier 1 practice. The CN_{Adj} takes into account the reduction in runoff volume achieved through Tier 1 practices. The T_c is calculated by the watershed lag method using CN_{Adj} as CN' .

Pre-Development CN (Flow-weighted composite)

86

Pre Development T_c (min)

19.5

(Watershed
Lag Method)

CN_{Adj}

91

Post Development T_c (min)

14.8

Overbank Flood Notes:

Extreme Flood Protection (Q_{P100})

Standard Applicable?

☐ Yes ☒ No

Waiver (if No is selected):

<10 acres impervious

Standard Met with HCM?

No

The extreme standard has not been fully met. Provide additional STPs to ensure post development peak runoff does not exceed pre development peak runoff for the 100 yr, 24 hour storm event.

STP used:

Pre-development peak discharge rate (cfs)

Pre-routed, post-development peak discharge rate (cfs)

Routed, post-development peak discharge rate (cfs)

Modeling Info: When demonstrating Q_{P100} compliance in a hydrologic model, use the following CN and T_c below, if the practice used to meet Q_{P100} is not a Tier 1 practice. The CN_{Adj} takes into account the reduction in runoff volume achieved through runoff reduction practices. The T_c is calculated by the watershed lag method using CN_{Adj} as CN' .

Pre-Development CN (Flow-weighted composite)

85

Pre Development T_c (min)

19.9

(Watershed
Lag Method)

CN_{Adj}

90

Post Development T_c (min)

15.2

Extreme Flood Notes:

STP Selection Matrix

Version 5/8/2017

Project Name:

The H at Mallets Bay

Discharge Point:

1

Step 1: Is the Water Quality Treatment Standard entirely managed with one or more of the following Tier 1 practices?

Infiltration Basins/ Trenches/ Chambers

Simple Disconnection

Drywells

Disconnection to Filter Strips and Vegetated Buffers

Bioretention (designed to infiltrate)

Dry Swales (designed to infiltrate)

Filters (designed to infiltrate)

Permeable Pavement¹

Reforestation¹

☐ Yes ☒ No


Proceed to Step

2

1. These practices do not require specific justification due to feasibility limitations

Step 2: Assess the feasibility of using Tier 1 Practices

Complete the matrix below in its entirety for each drainage area.

Tier 1 Practices are available to meet the Water Quality Treatment Standard. If using one of these practices, stop here. If additional site constraints exist other than those listed here, proceed to Step 3.		Infiltration Basin/ Trench/ Chamber	Drywell	Bioretention (infiltrating)	Simple Disconnection	Disconnection to Filter Strips or Vegetated Buffer	Dry Swales (infiltrating)	Filters (infiltrating)
Practice Availability for Water Quality Treatment? 		Not Feasible	Not Feasible	Not Feasible	Yes	Yes	Not Feasible	Not Feasible
Feasibility Restriction	Response	Practice Availability Based on Restrictions						
Do underlying soils have an infiltration rate of less than 0.2 inches per hour, as confirmed by field geotechnical tests or are classified as Hydrologic Soil Group D according to the NRCS Soil survey?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Not Feasible	Not Feasible	Not Feasible	n/a	n/a	Not Feasible	Not Feasible
Will runoff to the practice include discharge from a hotspot landuse or activity?	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	Available	Available	Available	Available	Available	Available
Is the site a brownfield or contaminated site where infiltration is restricted or where infiltration would increase the threat of pollution migration, as confirmed in writing by the Department's Waste Management and Prevention Division?	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	Available	Available	Available	Available	Available	Available
Is the slope of the vegetated buffer greater than 15%	<input type="radio"/> Yes <input checked="" type="radio"/> No	n/a	n/a	n/a	Available	Available	n/a	n/a
Is the slope of the filter strip greater than 15%	<input type="radio"/> Yes <input checked="" type="radio"/> No	n/a	n/a	n/a	Available	n/a	n/a	n/a
Is the slope of the vegetated buffer greater than 8%	<input type="radio"/> Yes <input checked="" type="radio"/> No	n/a	n/a	n/a	n/a	Available	n/a	n/a
Are natural slopes where an infiltration trench or basin could be sited greater than 15%	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	n/a	Available	n/a	n/a	Available	Available
Bottom of practice would be below seasonal high water table	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	Available	Available	n/a	n/a	Available	Available
Seasonal high water table or bedrock would be less than 1 foot from the bottom of the practice.	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	Available	n/a	n/a	n/a	n/a	n/a
Seasonal high water table or bedrock would be less than 3 feet from the bottom of the practice.	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	n/a	n/a	n/a	n/a	n/a	n/a

Will the practice be located within 75 feet down-gradient of a wastewater disposal area system, within 35 feet up-gradient or 75 feet down-gradient of a wastewater disposal system?	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	Available	Available	n/a	n/a	Available	Available
Will the practice be located within 150 feet of a drinking water source located in an unconfined aquifer?	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	Available	Available	n/a	n/a	Available	Available
Will the practice be located within 100 feet of a drinking water source located in bedrock or a confined unconsolidated aquifer?	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	Available	Available	n/a	n/a	Available	Available
Will the practice be located within Zone 1 or Zone 2 of a public community groundwater source protection area?	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	Available	Available	n/a	n/a	Available	Available
Will the practice be located within 200 feet of non-transient non-community groundwater source?	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	Available	Available	n/a	n/a	Available	Available
Will the practice violate any restrictions of the Vermont Wastewater and Potable Water Supply Rules, or their replacement?	<input type="radio"/> Yes <input checked="" type="radio"/> No	Available	Available	Available	Available	Available	Available	Available

Step 3: Other feasibility constraints for remaining Tier 1 and Tier 2 practices

If, following completion of Step 2 of the STP Selection Tool there are no Tier 1 Practices available for use on the project site, designers shall consider the use of Tier 2 practices for treatment of the Water Quality Treatment Standard.

Is the Water Quality Treatment Standard entirely managed with Tier 2 Practices?

☒ Yes ☐ No

Stop. No further justification is needed.

If the the use of a Tier 1 or Tier 2 Practice is infeasible for reasons beyond those listed in Step 2 of the STP Selection Matrix, a designer may submit site specific detailed feasibility justification that such practices are not feasible following the guidance in Section 2.2.4.1 of the 2017 VSMM. Only after completion of the STP Selection Matrix and determination that Tier and Tier 2 Practices are infeasible shall a designer consider Tier 3 Practices or existing stormwater infrastructure for meeting the Water Quality Treatment Standard (WQTS) on the project site.

Provide written feasibility justification below or list attachments

Treatment Wetlands (4.3.5)

Treatment Wetland # 1

Practice Drainage Area	For Permit Coverage	Not for Permit Coverage	Total to Practice
1 Total Area (acres)	4.010	0.000	4.010
2 New Impervious (acres)	2.170	0.000	2.170
3 Redeveloped Impervious	0.000	0.000	0.000
	WQ _V for credit	WQ _V not for credit	Total WQ _V
4 WQ _V to practice	0.1795	0.0000	0.1795
↑Enter this value on the Standards Compliance Workbook			
5 Practice Type	<input type="radio"/> Shallow surface wetland <input checked="" type="radio"/> Gravel wetland		
6 Discharges to Cold or Warm Water Fishery?	<input checked="" type="radio"/> Cold <input type="radio"/> Warm		

Modified CN for WQ_V (1.0") storm

95

Note: Designers may use the Practice Drainage Area Runoff Calculator (second tab) for calculation of practice-specific runoff volumes for other treatment standards.

* Questions preceded by an asterisk (*) may change based on previously entered values

Conveyance (4.3.5.2)

	Response	Attachment location
7 Are inlets stabilized to ensure that non-erosive conditions exist for at least the 1-year, 24 hour storm?	<input type="radio"/> Yes <input type="radio"/> No	Plan Sheet C-2.1
8 Has a low for orifice been provided to meet the the WQ _V and CP _V extended	<input checked="" type="radio"/> Yes <input type="radio"/> No	Detail Sheet CD-6
9 Have the outfalls and the conveyance to the discharge point been designed and protected to avoid erosion?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Plan Sheet C-2.1 & Detail Sheet CD-6
10 Has a liner designed in accordance with Section 4.3.5.2 been provided if the infiltration rate exceed 0.05 inches per hour and the wetland is located above	<input checked="" type="radio"/> Yes <input type="radio"/> No	Detail Sheet CD-6
11* Have inlet pipes been set at the permanent pool or the base of the gravel bed?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Plan Sheet C-2.1 & Detail CD-7
12* Is outlet elevation designed such that a sub-surface water level is maintained in the gravel wetland?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Detail CD-7
13* If the gravel wetland is designed with an organic soil layer at the surface, have vertical perforated riser pipes been provided to deliver stormwater from the surface down to the gravel bed?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Detail CD-6

Pre-Treatment (4.3.6.3)

	Response	Attachment location
14 Has pretreatment been provided for non-rooftop runoff?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Sheet C-2.1

15	What type of pretreatment is being used?	<input type="checkbox"/> Swale <input checked="" type="checkbox"/> Forebay (10% WQv) <input type="checkbox"/> Proprietary <input type="checkbox"/> Filter Strip <input type="checkbox"/> Deep Sump Catch Basins	
----	--	--	--

Treatment (4.3.6.4)		Response	Attachment location
16	What is the volume stored in the forebay or other volumetric pre-treatment if used? (minimum 10% WQ _v)	ft ³ 782	N/A
17	What is the volume stored in the permanent pool?	ft ³ 3149	WQV Modeling
18	What is the total WQ _v stored at the normal water level (pre-treatment + permanent pool)?	ft ³ 3931	WQv Modeling
19*		<input type="radio"/> Yes <input checked="" type="radio"/> No	
20*		<input type="radio"/> Yes <input type="radio"/> No	
21	Does the pre-treatment volume plus the permanent pool equal at least 50% of the WQ _v ?	50.3%	Yes
22	Is the remaining WQ _v provided for by extended detention over 24 hours?	<input checked="" type="radio"/> Yes <input type="radio"/> No	N/A
23	Has a minimum flow path at normal water level of 3:1 been provided?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Plan Sheet C-2.1
24	What is the Storage Volume of the practice. Include the permanent pool and any volume used for providing extended detention.	ac-ft 0.0547	Enter this on the eNOI

Landscaping (4.3.6.5)		Response	Attachment location
25	Are all deep pool areas of ≥ 4 feet depth with side slopes steeper than 4:1 (H:V) surrounded by a safety bench with ≤6% slope extending 10 feet outward from the normal water edge to the toe of the side slope?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Plan Sheet C-2.1
26	Has an aquatic been provided that extends at least 5 feet inward from the normal water edge and is no more than 18 inches deep?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Plan Sheet C-2.1
27	Has a planting plan been prepared showing how aquatic and terrestrial areas will be stabilized, including plant species, plant locations, sources of plant material and any required soil amendments?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Detail CD-6
28	Has a setback been provided that extends 25 feet from the maximum design water surface elevation of the practice?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Plan Sheet C-2.1
29	Does the planting plan specify that no woody vegetation >2 inches in diameter shall be planted or allowed to grow on the dam, within 15 feet of the dam or the toe of the embankment, or within 25 of a principal spillway outlet?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Detail CD-6
30	Are any donor organic soils used in the practice obtained from a source other than natural wetlands?	<input checked="" type="radio"/> Yes <input type="radio"/> No	N/A

Attachment location: Indicate the specific location (i.e. appendix, page, plan sheet) where the requisite support documentation has been provided within the application.

Version: 3/28/2018

Project Name: The H at Mallets Bay

Discharge Point: 1

Disconnection Area #: 1

Simple Disconnection (4.2.2)

Disconnected Area		For Permit Coverage	Not for Permit Coverage	Total to Practice
1	Total Area (acres)	0.070	0.000	0.070
2	Impervious (acres)	0.035	0.000	0.035
		WQ _V for credit	WQ _V not for credit	Total WQ _V
3	WQ _V to practice	0.0029	0.0000	0.0029
4	Disconnected Area Type	<input type="checkbox"/> > 10 ft, or conveyed by downspout <input checked="" type="checkbox"/> 10 ft contributing length or less		

Modified CN for WQ_V (1.0") storm

94

* Questions preceded by an asterisk (*) may change based on previously entered values

Feasibility (4.2.2.1)		Response	Attachment location
5	For areas conveyed by sheetflow, is the width of the disconnection area (perpendicular to the direction of flow) equal to or greater than the area being disconnected?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Sidewalk/RecPath
6*		<input type="radio"/> Yes <input type="radio"/> No	
7*		<input type="radio"/> Yes <input type="radio"/> No	
8	Do the underlying soils of the disconnection area meet the Post-Construction Soil Depth and Quality Standard?	<input checked="" type="radio"/> Yes <input type="radio"/> No	
9*		<input type="radio"/> Yes <input type="radio"/> No	
10*	Is the maximum flow path length from the contributing impervious area 10 feet or less?	<input checked="" type="radio"/> Yes <input type="radio"/> No	
11	Are disconnection areas configured such that there is no overlap between adjacent disconnection areas?	<input checked="" type="radio"/> Yes <input type="radio"/> No	
12	Is the maximum slope of the disconnection area no steeper than 15%?	<input checked="" type="radio"/> Yes <input type="radio"/> No	
13	For sites with septic systems, is the disconnection flow path cross-gradient or down-gradient of the leachfield?	<input type="radio"/> Yes <input type="radio"/> No	NA

Conveyance (4.2.2.2)		Response	Attachment location
14	Is the runoff conveyed as sheet flow across the disconnection area for the applicable design storms and prevented from channelizing?	<input checked="" type="radio"/> Yes <input type="radio"/> No	
15	Is the disconnection surface directed away from buildings so as to protect foundations and basements?	<input checked="" type="radio"/> Yes <input type="radio"/> No	

16*		<input type="radio"/> Yes <input type="radio"/> No	
17*		<input type="radio"/> Yes <input type="radio"/> No	
18	For runoff not conveyed by downspout, does the runoff drain either as sheet flow or drain to a subsurface drain field that is not directly connected to the drainage network?	<input checked="" type="radio"/> Yes <input type="radio"/> No	

Pretreatment (4.2.2.3)		Response	Attachment location
19	Is runoff from qualifying surfaces prevented from co-mingling with other runoff, such that pre-treatment is not required?	<input checked="" type="radio"/> Yes <input type="radio"/> No	

Required Disconnection Length for Contributing Areas >10 ft and Downspouts		Response	Attachment location
20*	n/a, Downspout/Contributing area >10 ft is not selected in Question 4 acres	0.00	
21*	$f_c \geq 1$ in/hr for $T_V = HC_V$ $f_c \geq 0.5$ in/hr for $T_V = WQ_V$ $f_c < 0.5$ in/hr for $T_V = WQ_V$	<input type="radio"/> A <input type="radio"/> A/B <input type="radio"/> C/D	
22*		<input type="radio"/> <8% <input type="radio"/> 8-15%	
23*	inches	0.00	
24*	ft	0.0	
25*	ft	0.0	

Required Disconnection for Contributing Areas ≤10 ft		Response	Attachment location
26*	Disconnected Area ≤10ft wide acres	0.035	
27*	What is the flow path length from the sidewalk, path, or driveway? (max 10 ft) ft	4	
28*	What is the slope of the disconnection area?	<input checked="" type="radio"/> <8% <input type="radio"/> 8-15%	
29*	Is the disconnection area on A soils ($f_c \geq 1$ in/hr)?	<input type="radio"/> Yes <input checked="" type="radio"/> No	
30*	inches	0.00	
31*	What is required length of the disconnection for the path/sidewalk/driveway (≤10 ft)? ft	4.0	
32*	What disconnection length is provided for the path/sidewalk/driveway (≤10 ft)? ft	10.0	

Treatment Volume Calculation

33	What is the treatment volume provided by the STP?	T_V (cu-ft)	127.05	
34	What is the treatment volume provided by the STP?	T_V (ac-ft)	0.0029	

↑ Enter this value on the Standards Compliance Worksheet

Treatment (4.2.2.4)			Response	Attachment location
35*			<input type="radio"/> Yes <input type="radio"/> No	

Landscaping (4.3.2.5)			Response	Attachment location
36	Is a dense vegetative cover specified for the disconnection area on the plan sheet/detail sheet?		<input checked="" type="radio"/> Yes <input type="radio"/> No	

Attachment location: Indicate the specific location (i.e. appendix, page, plan sheet) where the requisite support documentation has been provided within the application.

Channel Protection Standard Waiver Worksheet

Fill out this worksheet for each discharge point in which use of this waiver is sought.

Channel Protection Standard (CP_v) Waiver (*check only one*):

- ☐ 1. A site where the pre-routed, post-development discharge from the 1-year, 24-hour storm event is less than 2 cubic feet per second (cfs).

Enter the total pre-routed post-development stormwater discharge rate (cfs):

Guidance: "Pre-routed post development discharge" means the runoff after development, including post-development conveyance, but without STPs. Curve Numbers should not be adjusted based on T_v credit from Tier 1 practices. When examining whether or not the site qualifies for this waiver, off-site runoff does not need to be considered, however the overall common plan of development shall be considered. Please attach the runoff calculations/hydrologic modeling for the pre-routed, post-development during the 1-year, 24-hour storm event.

- ☒ 2. A site with a direct discharge to waters with a drainage area equal to or greater than 10 square miles and that is less than 5% of the watershed area at the site's upstream boundary.

Name of Water at Discharge Point: Lake Champlain

Drainage Area of Water at Discharge Point (square miles): 8234

For a project that has more than one discharge point and that discharges to different receiving waters, waiver eligibility shall be determined on a "per receiving water" basis. Receiving waters are considered separate if the drainage area at their downstream point of confluence is greater than 10 square miles.

For example, if discharge point S/N 001 discharges directly to the Winooski River (drainage area of greater than 10 square miles), but discharge point S/N 002 discharges directly to a small tributary of the Winooski River, then S/N 001 could be waived from the Channel Protection Standard using Waiver 2, but S/N 002 could not. However S/N 002 may still be eligible for Waiver 1.

Overbank Flood Protection Standard Waiver Worksheet

Fill out this worksheet for each discharge point in which use of this waiver is sought.

Overbank Flood Protection Standard (Q_{P10}) Waiver (*check only one*):

- ☐ 1. The pre-routed, post-development discharge for the 10-year, 24-hour storm is less than 2 cubic feet per second.

Enter the total pre-routed post-development stormwater discharge rate (cfs):

Guidance: "Pre-routed post development discharge" means the runoff after development, including post-development conveyance, but without STPs. When examining whether or not the site qualifies for this waiver, off-site runoff does not need to be considered, however the overall common plan of development shall be considered. Please attach the runoff calculations/hydrologic modeling for the pre-routed, post-development during the 10-year, 24-hour storm event.

- ☒ 2. A site that has a direct discharge to waters with a drainage area equal to or greater than or equal to 10 square miles.

Name of Waters at Discharge Point: Lake Champlain

Drainage Area of Waters at Discharge Point (square miles): 8234

- ☐ 3. A downstream analysis was completed, pursuant to Section **Error! Reference source not found.** of the 2017 VSMM, that indicated extreme flood control is not necessary for the site.

Has adequate conveyance from the site to the discharge point been verified?

☐ Yes ☐ No

Has supporting information (e.g. narrative description, calculations, modeling) for the completed downstream analysis been included with the application?

☐ Yes ☐ No

For a project that has more than one discharge point and that discharges to different receiving waters, waiver eligibility shall be determined on a "per receiving water" basis. Receiving waters are considered separate if the drainage area at their downstream point of confluence is greater than 10 square miles.

For example, if discharge point S/N 001 discharges directly to the Winooski River (drainage area of greater than 10 square miles), but discharge point S/N 002 discharges directly to a small tributary of the Winooski River, then S/N 001 could be waived from the Overbank Flood Protection Standard using Waiver 2, but S/N 002 could not. However S/N 002 may still be eligible for Waivers 1 or 3.

Extreme Flood Protection Standard Waiver Worksheet

Fill out this worksheet for each discharge point in which use of this waiver is sought.

Extreme Flood Protection Standard (Q_{P100}) Waiver (*check only one*):

- ☒ 1. A site that has a direct discharge to waters with a drainage area equal to or greater than or equal to 10 square miles and that is less than 5% of the watershed area at the site's upstream boundary.

Name of Waters at Discharge Point: Lake Champlain

Drainage Area of Waters at Discharge Point (square miles): 8234

- ☐ 2. The impervious on site or otherwise associated within a common plan of development, constructed after 2002, is less than 10 acres.

☐ Yes

☐ No

- ☐ 3. A downstream analysis was completed, pursuant to Section **Error! Reference source not found.** of the 2017 VSMM, that indicated extreme flood control is not necessary for the site.

Has adequate conveyance from the site to the discharge point been verified?

☐ Yes

☐ No

Has supporting information (e.g. narrative description, calculations, modeling) for the completed downstream analysis been included with the application?

☐ Yes

☐ No

For a project that has more than one discharge point and that discharges to different receiving waters, waiver eligibility shall be determined on a "per receiving water" basis. Receiving waters are considered separate if the drainage area at their downstream point of confluence is greater than 10 square miles.

For example, if discharge point S/N 001 drains directly to the Winooski River (greater than 10 square miles), but discharge point S/N 002 drains to a small tributary of the Winooski River, then S/N 001 could be waived from the Extreme Flood Protection Treatment Standard using Waiver 2, but S/N 002 could not. However, S/N002 may be still eligible for Waiver 1.